

# WIZARA YA ELIMU, SAYANSI NA TEKNOLOJIA

## CHUO CHA UALIMU VIKINDU


### MKATABA WA MANUNUZI KWA MZABUNI

#### A: MASHARTI MAALUM YA MKATABA

1	MWAJIRI	MKUU WA CHUO CHUO CHA UALIMU VIKINDU. S.L.P 16268, DAR ES SALAAM KNY: KATIBU MKUU WIZARA YA ELIMU SAYANSI NA TEKNOLOJIA
2	JINA NA ANWANI YA MZABUNI	Jina: HAMISI OMARI GAWA GAWA T/A SAKASAKA Anwani: P.O. BOX 10072, D.S.M Simu: 0689 928900 / 0715 - 224242
3	ENEO LA UJENZI	CHUO CHA UALIMU VIKINDU.
4	MAELEZO YA KAZI KWA UFUPI	KAZI YA HUDUMA YA KULETA VIFA VYA UJENZI KAMA VILIVYO ORODHESHA KWENYE KIAMBATA.
5	GHARAMA YA KAZI	MALIPO YATAFANYIKA KULINGANA NA CALL OF ORDER
6	MUDA WA MKATABA (Tangu Kusainiwa kwa Mkataba):	Tarehe ya Kusaini..... Muda: ..... Tarehe ya Kuanza Kazi. .... Tarehe ya Kumaliza Kazi. ....
7	MASHARTI YA MALIPO:	<ul style="list-style-type: none"><li>Hakuna Malipo ya Awali</li><li>Mzabuni atalipwa baada ya kuwasilisha vifa: sehemu husika (site), kukaguliwa na kuridhishwa na ubora na viwango vya vifaa vinavyohitajika.</li></ul>

**B: MASHARTI YA JUMLA YA MKATABA**

1. Kuhakikisha mzabuni analeta vifaa kulingana na call of order.
2. Kuhakikisha mzabuni analeta vifaa kulingana na bei zilizo kubalika.
3. Kuhakikisha mzabuni analeta vifaa ndani ya muda uliyopangwa.
4. Mzabuni ana paswa kuleta nyaraka zote muhimu za madai ili kukamilisha mchakato wa malipo.
5. Mzabuni akishindwa kutoa huduma kwa mujibu wa mkataba unavyojieleza, mkataba una weza kubatilishwa /kusitishwa.


**MKUU WA CHUO:** K.n.y. Mkuu wa Chuo  
Saini:  Chuo cha Ualimu Vikindu  
S L P 16268  
DAR ES SALAAM

Jina: SAPUA E. KABORRA

SIMU: 0713418458

Cheo: MKUU WA CHUO

Tarehe: 03/02/2022

**SHAHIDI WA MKUU WA CHUO:** K.n.y. Mkuu wa Chuo  
Saini:  Chuo cha Ualimu Vikindu  
S L P 16268  
DAR ES SALAAM

Jina: SAID CHARLES

SIMU: 0786415504

Cheo: MAKAMU MKUU WA CHUO

Tarehe: 03/02/2022

**MZABUNI:**

Saini: 

Jina: HAMISI OMARI MPAWA

SIMU: 0689 - 928 900 / 6652 77 889

Cheo: MTOA HUDUMA

Tarehe: 03/02/2022

**SHAHIDI WA MZABUNI:**

Saini: 

Jina: JAMU IDRISA

SIMU: 0742 900 178 / 0713 - 137167

Cheo: MTOA HUDUMA MSAIDI

Tarehe: 03/02/2022



CHUO CHA UALIMU VIKINDU TC-SAWA SAWA STORE					
	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	SUB-STRUCTURE -PROVISIONAL				
2	<u>Strip Foundation - Grade 15 Plain</u>				
3	Aggregate (3/4") Kokoto Nyeusi	16	M <sup>3</sup>	110,000.00	1,760,000.00
4	Cement-50kgs 42.5N	338	Bags	15,000.00	5,070,000.00
5	Tofali Vibrated Block 6" not less 4.5Mpa	3,600	Nr	1,500.00	5,400,000.00
6	<u>Moram, Hardcore &amp; Site sterilization</u>				-
7	Moram (12m <sup>3</sup> lorry)	3	Trips	100,000.00	300,000.00
8	Aldrín solution or equal and approved	2	Litres	10,000.00	20,000.00
9	<u>Oversite Concrete (100mm thick - 20 grade) &amp; Ground Beam - 20 grade and column base</u>				-
10	DPM	2	Roll	120,000.00	240,000.00
11	Reinforcement - 12mm diameter high tensile	80	PC'S	27,000.00	2,160,000.00
12	Reinforcement - 8mm diameter	82	PC'S	15,000.00	1,230,000.00
13	Timber 1" X 10" (5.2m long) (Hazina dawa)	42	PC'S	17000	714,000.00
14	Timber 2" X 2" (Hazina Dawa)	25	PC'S	3500	87,500.00
15	Aggregates (1/2") Kokoto Nyeusi	27	M <sup>3</sup>	110,000.00	2,970,000.00
16					-
17	<u>Roof Structure - Provisional ( 5.2m long)</u>				-
18	Timber 2" X 2" Purlins (Zenye Dawa)	202	PC'S	8100	1,636,200.00
19	Timber 2" X 4" King Post, wall plate and struts(Zenye Dawa)	75	PC'S	16200	1,215,000.00
20	Timber 2" X 6" Rafter and Tie beam(Zenye Dawa)	83	PC'S	25200	2,091,600.00
21	Fascia board 1" X 10" (5.2m long) (Zenye Dawa)	15	PC'S	20000	300,000.00
22	Gypsum board -9mm thick Thailand	51	PC'S	23000	1,173,000.00

23	Plain Cornice (8ft)	35	PC'S	3000	105,000.00
24	Gypsum Screw 1" 800pcs/box	1	Box	10000	10,000.00
25	Screw 1.25" 800pcs/box	1	Box	10000	10,000.00
26	Fibre tape nchl 3" Upana	1	Roll	10000	10,000.00
27	PVC ceiling with its fittings	2	Pc's	15000	30,000.00
28	900 x2200mm high(Mninga Au Mkongo)	3	PC'S	300000	900,000.00
29	900 x 2500 mm high frame	3	PC'S	200000	600,000.00
30	5mm thick clear glass to Vents	1	M <sup>2</sup>	20000	20,000.00
31	16 mm burglar bars	1	PC'S	50000	50,000.00
32	Brush 3"	3	Pcs	4000	12,000.00
33	Clear Varnish -( 4Litres)	1	TIN	30000	30,000.00
34	Mortice lock Three lever - ref: union	1	Pcs	75000	75,000.00
35	Brass hinges - 100mm	5	Pairs	6000	30,000.00
36	Wood Screw	1	Box	10000	10,000.00
37	1500 X 1750mm high	1	PC'S	320,000.00	320,000.00
38	1800 X 1750mm high	11	PC'S	370,000.00	4,070,000.00
39	Tiles Floor 40x40	115	Box	25000	2,875,000.00
40	Scatting Tiles	14	Box	35000	490,000.00
41	Grouts	3	Kgs	3000	9,000.00
42	Strips	7	Pcs	5000	35,000.00
43	Solvent - 5LTRS	2	TIN	7000	14,000.00
44	Brush 3" Made in Tanzania	2	Pcs	4000	8,000.00
45	Gloss paint-4LTR Gold Star equivalent	3	TIN	23000	69,000.00

46	Bitumen paint - 4Litres Gold Star eqvnt	4	TIN	30000	120,000.00
47	6 Ways SPN distribution board (DB 3 ) with 63A/0.3mA RCCB Incomer and outgoing MCBs as shown In Schematic diagram as MERLIN GERIN or approved equal Tronic make	1	Pcs	320,000.00	320,000.00
48					-
49	4C x16 mm <sup>2</sup> Cu,PVC/PVC cable from neaby Tanesco LV Pole to Distribtion Board(DB 1).	25	m	28000	700,000.00
50					-
51	1C x 10mm <sup>2</sup> Cu/PVC Green/Yellow earth cable.	20	m	5000	100,000.00
52					-
53	<b>Small Power Distribution</b>				-
54	25mm Heavy duty PVC Conduity concealed under walls and roof for all power and Data points	66	Pcs	2500	165,000.00
55					-
56	Single core 2.5 sqmm PVC copper cables from distribution Boards to all power outlet points EAC make for lighting circuits (Euro)				-
57	Red Wire	2	RoLL	95000	190,000.00
58	Black Wire	2	Roll	95000	190,000.00
59	Green Wire	2	Roll	95000	190,000.00
60	20mm Heavy duty PVC Conduity concealed under walls and roof for all Lighting and DataFire points	100	Pcs	1800	180,000.00
61	TYPE A:1 x 36W; 1200mm standard, fluorescent fitting as LIGHTING DIRECT PHOENIX	20	Pcs	22000	440,000.00
62					-
63	TYPE B :Bulkhead lamp C/W energy saver for external lights as THORN LUX TLX - 1204 ( In black finish)	4	Pcs	20000	80,000.00
64	56" Blade Panasonic Ceilling fan c/w fan regulator ex.Japan	10	Pcs	150000	1,500,000.00
65	1 way 2 gang light switch as Legrand or equivalent	3	Pcs	5000	15,000.00
66	Cable Connector Tronic Making	1	Pcs	3000	3,000.00
67	Metal Twin Square Box	1	Pcs	2500	2,500.00

68	Hoe	5	PCS	10000	50,000.00
69	Manila rope	30	PCS	1000	30,000.00
70	reflector	30	PCS	5000	150,000.00
71	Helment	30	PCS	5000	150,000.00
72	Ndoo 10L	49	PCS	3000	147,000.00
73	Axe	2	PCS	12000	24,000.00
74	sururu	2	PCS	15000	30,000.00
75	pipe level	3	PCS	10000	30,000.00
76	nyundoya misumari	4	PCS	15,000.00	60,000.00
77	makoleo	5	PCS	12000	60,000.00
78	Store ledger	15	PCS	12,000.00	180,000.00
79	gum boots	15	PCS	15,000.00	225,000.00
80	Brush 4"	10	PCS	4000	40,000.00
81	panga	3	PCS	5000	15,000.00
82	Bending Spring 25Mm For Conduit	3	PCS	19600	58,800.00
83	Bending Spring 20Mm For Conduit	3	PCS	15000	45,000.00
84	Horse pipe 3/4	1	Roll	65000	65,000.00
	TOTAL				41,704,600.00