

THE UNITED REPUBLIC OF TANZANIA



**PRESIDENT OFFICE
REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
MKALAMA DISTRICT COUNCIL**



**CONTRACT AGREEMENT FOR CONSTRUCTION OF EMERGENCY MEDICAL
DEPARTMENT BUILDING
TENDER NO LGA/147/2021/2022/W/IMF/6**

**CLIENT
DISTRICT EXECUTIVE DIRECTOR,
P.O BOX 1007,
MKALAMA.**

**CONTRACTOR
KUYELLAENTERPRISES LTD,
P.O BOX 2880,
DAR ES SALAAM.**

**PROJECT MANAGER,
DISTRICT ENGINEER,
P.O BOX 1007,
MKALAMA**

: 2022

TABLE OF CONTENT

SECTION I	:	FORM OF CONTRACT AGREEMENT
SECTION II	:	LETTER OF ACCEPTANCE
SECTION III	:	SUBMISION BID FORM
SECTION IV	:	GENERAL CONDITION OF CONTRACT
SECTION V	:	SPECIAL CONDITION OF CONTRACT
SECTION VI	:	BILL OF QUANTITY
SECTION VII	:	DRAWINGS
SECTION VIII	:	SPECIFICATIONS
SECTION IX	:	BIDDER ELIGIBILITY

SECTION I : FORM OF CONTRACT AGREEMENT

Form of Contract Agreement

This Agreement, made the 25 day of February, 2022, between Mkalama District Council, P.O. Box 1007 Mkalama (hereinafter called "the Employer") and Kuyella Enterprises Ltd, P.O. Box 2880, Dar es Salaam (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute Construction of Emergence Department (EMD) (hereinafter called "the Works") and the Employer has accepted the Tender by the Contractor for the execution and completion of such works and the remedying of any defects therein in the sum of *Two Hundred Ninety Nine Million Six Hundred Thirty Four Thousand Two Hundred Fourteen Shillings Only* (299,634,214/=) (hereinafter called "Contract Price").

Now this Agreement witnessed as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all respects with the provisions of the Contract.
3. the Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying of defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

In Witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of JAMES JOHN NKWEGA
Was hereunto affixed in the presence of: [Signature]

CHAIRMAN
MKALAMA DISTRICT COUNCIL

Signed, Sealed, and Delivered by the said _____

In the presence of: MKALAMA DISTRICT COUNCIL

Binding Signature of Employer [Signature] DISTRICT EXECUTIVE DIRECTOR
MKALAMA DISTRICT COUNCIL

Binding Signature of Contractor [Signature]



SECTION II : LETTER OF ACCEPTANCE

THE UNITED REPUBLIC OF TANZANIA



PRESIDENT OFFICE
REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
MKALAMA DISTRICT COUNCIL



Ref NO MDC/PMU/A.10/147

14 February 2022

M/S KUYELLA ENTERPRISES LTD,
P.O Box 2880,
Dar es Salaam

REF : LETTER OF ACCEPTANCE

Reference is made to the above subject matter and notice of intention to award the contract with Ref MDC/PMU/A.10/144, dated 04 February 2022.

This is to notify that your bid dated 14 January 2022 for execution of Construction of Emergency Medical Department (EMD) at Mkalama District Hospital.

Tender No : LGA/147/2021/2022/W/IMF/06 For the bid price of Tanzanian Shillings, Two Hundred Ninety Nine Million, Six Hundred Thirty Four Thousand Two Hundred Forteen Shillings Only (299,634,214/=) VAT Inclusive for duration of Four (4) calendar months as corrected and modified in accordance with the instruction to bidder is here by accepted by us.

Your are hereby instructed to proceed with the execution of the said works in accordance with the contract documents and you are required to furnish the Performance bond to the client before signing the contract.

Authorized Signature *Ausios*
Name and Title of Signatory *MIA JUMA MESSIS - DED*
Name of Agency *MKALAMA DISTRICT COUNCIL*
DISTRICT EXECUTIVE DIRECTOR
'MKALAMA DISTRICT COUNCIL'

SECTION III : SUBMISION BID FORM

Form of Tender

13/01/2022

To: THE SECRETARY
MKALAMA DISTRICT COUNCIL
P.O.BOX 1007,
MKALAMA - SINGIDA.

We KUYELLA ENTERPRISES LIMITED, offer to execute the PROPOSED CONSTRUCTION OF EMERGENCY MEDICAL DEPARTMENT BUILDING AT MKALAMA DISTRICT COUNCIL HOSPITAL, LGA/147/2021/2022/W/IMF/6 in accordance with the Conditions of Contract accompanying this Tender for the Contract Price of 345,731,032.00, THREE HUNDRED AND FOURTY FIVE MILLION, SEVEN HUNDRED AND THIRTY ONE THOUSAND, AND THIRTY TWO TANZANIA SHILLINGS (VAT INCLUSIVE).

The Contract shall be paid in the following currencies:

Currency	Percentage payable in currency	Rate of exchange: one foreign equals [insert local]	Inputs for which foreign currency is required
(a)		-NIL-	
(b)		-NIL-	

The advance payment required is:-

Amount	Currency
(a) 34,573,103.2	TSHs
(b)	

We declare that our tendering price did not involve agreements with other tenderers for the purpose of tender suppression.

We hereby confirm NATIONAL CONSTRUCTION COUNCIL (NCC), to be the Appointing Authority, to appoint the adjudicator in case of any arisen disputes in accordance with ITT 43.1 [Adjudicator]

We are not participating, as tenderers, in more than one Tender in this tendering process other than alternative tenders in accordance with the tendering documents.

We declare that, as tenderer(s) we do not have conflict of interest with reference to ITT 3.7 [Eligibility of Tenderers]

With reference to ITT 3.11 [Eligibility of Tenderers], it is our intention to subcontract approximately 0% percentage of the Tender /Contract Price, details of which are provided herein.

Our firm, its affiliates or subsidiaries, including any subcontractors or suppliers for any part of the contract has not been declared ineligible by the Government of the United Republic of Tanzania under Tanzania's laws or official regulations or by an act of compliance with a decision of the United Nations Security Council.

The following commissions or gratuities of fees have been paid or are to be paid by us to agents relating to this tender, and to contract execution if we are awarded the contract:-

Name and address of agent or recipient	Amount and currency	Purpose of commission or gratuity
NONE	NONE	NONE

(if none has been paid or is to be paid, state "none")

This tender and your written acceptance of it shall constitute a binding Contract between us.

We understand that you are not bound to accept the lowest or any Tender you receive.

We hereby confirm that this tender complies with the tender validity and Tender Security required by the tendering documents and specified in the Tender Data Sheet.

Authorized Signature: _____ *[Signature]*

Name and Title of Signatory: Feix Kuyewa - *[Signature]*

Name of Tenderer: KUYEWA ENTERPRISES LTD

Address: Box 2890 - D.M.



SECTION IV : GENERAL CONDITION OF CONTRACT

GENERAL CONDITIONS OF CONTRACT

A. General

1. Definitions

1.1

Boldface type is used to identify defined terms.

The **Adjudicator** is the person appointed jointly by the Employer and the Contractor to resolve disputes in the first instance, as provided for in Clauses 26 and 27 hereunder.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Bid.

Compensation Events are those defined in Clause 46 hereunder.

The **Completion Date** is the date of completion of the Works as certified by the Project Manager, in accordance with sub-Clause 57.1.

The **Contract** is the Contract between the Employer and the Contractor to execute, complete, and maintain the Works. It consists of the documents listed in Clause 2.3 below.

The **Contractor** is a person or corporate body whose Bid to carry out the Works has been accepted by the Employer.

The **Contractor's Bid** is the completed bid document submitted by the Contractor to the Employer.

The **Contract Price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.

Corrupt practice means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution and includes inter alia, bribery and extortion or coercion which involves threats of injury to person, property or reputation, and

Fraudulent practice means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Employer, and includes collusive practice among

Bidders (prior to or after bid submission) designed to establish bid prices at artificial non-competitive levels and to deprive the Employer of the benefits of free and open competition.

Days are calendar days; months are calendar months.

Day works are varied work inputs subject to payment on a time basis for the Contractor's employees and Equipment, in addition to payments for associated Materials and Plant.

A **Defect** is any part of the Works not completed in accordance with the Contract.

The **Defects Liability Certificate** is the certificate issued by Project Manager upon correction of defects by the Contractor.

The **Defects Liability Period** is the period named in the **Special Conditions of Contract** and calculated from the Completion Date.

Drawings include calculations and other information provided or approved by the Project Manager for the execution of the Contract.

The **Employer** is the party who employs the Contractor to carry out the Works.

Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works.

The **Initial Contract Price** is the Contract Price listed in the Employer's Letter of Acceptance.

The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the **Special Conditions of Contract**. The Intended Completion Date may be revised only by the Project Manager by issuing an extension of time or an acceleration order.

The **Intended Commencement Date** is the date on which it is intended that the Contractor shall start the Works. The Intended Commencement date is specified in the **Special Conditions of Contract**. The Intended commencement Date may be revised

only by the Project Manager by issuing an extension of time.

Materials are all supplies, including consumables, used by the Contractor for incorporation in the Works.

Plant is any integral part of the Works that shall have a mechanical electrical, chemical, or biological function.

The **Project Manager** is the person named in the **Special Conditions of Contract** (or any other competent person appointed by the Employer and notified to the Contractor, to act in replacement of the Project Manager) who is responsible for supervising the execution of the Works and administering the Contract.

The **Site** is the area defined as such in the **Special Conditions of Contract**.

Site Investigation Reports are those that were included in the bidding documents and are factual and interpretative reports about the surface and subsurface conditions at the Site.

Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Project Manager.

The **Start Date** is given in the Special Conditions of Contract. It is the latest date when the Contractor shall commence execution of the Works. It does not necessarily coincide with any of the Site Possession Dates.

A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract, which includes work on the Site.

Temporary Works are works designed, constructed, installed, and removed by the Contractor that are needed for construction or installation of the Works.

A **Variation** is an instruction given by the Project Manager which varies the Works.

"Force Majeure" means an event which is beyond the reasonable control of a Party and which makes a

Party's performance of its obligations under the Contract impossible or so impractical as to be considered impossible under the circumstances.

The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the **Special Conditions of Contract**.

2. Interpretation

2.1 In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Project Manager will provide instructions clarifying queries about these Conditions of Contract.

2.2 If sectional completion is specified in the Special Conditions of Contract, references in the Conditions of Contract to the Works, the Completion Date, and the Intended Completion Date apply to any Section of the Works (other than references to the Completion Date and Intended Completion Date for the whole of the Works).

2.3 The documents forming the Contract shall be interpreted in the following order of priority:

- (1) Agreement,
- (2) Letter of Acceptance,
- (3) Contractor's Bid,
- (4) Special Conditions of Contract,
- (5) Conditions of Contract,
- (6) Specifications,
- (7) Bill of Quantities, and
- (8) Any other document listed in the Special Conditions of Contract as forming part of the Contract.

3. Language and Law

3.1 The language of the Contract and the law governing the Contract are stated in the **Special Conditions of Contract**.

4. Project Manager's Decisions

4.1 Except where otherwise specifically stated, the Project Manager will decide contractual matters

- between the Employer and the Contractor in the role representing the Employer.
5. Delegation 5.1 The Project Manager may delegate any of his duties and responsibilities to other people except to the Adjudicator, after notifying the Contractor, and may cancel any delegation after notifying the Contractor.
6. Communications 6.1 Communications between parties that are referred to in the Conditions shall be effective only when in writing. A notice shall be effective only when it is delivered.
7. Subcontracting 7.1 The Contractor may subcontract with the approval of the Project Manager, but may not assign the Contract without the approval of the Employer in writing. Subcontracting shall not alter the Contractor's obligations.
8. Other Contractors 8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer between the dates given in the Schedule of Other Contractors, as referred to in the **Special Conditions of Contract**. The Contractor shall also provide facilities and services for them as described in the Schedule. The Employer may modify the Schedule of Other Contractors, and shall notify the Contractor of any such modification.
9. Personnel 9.1 The Contractor shall employ the key personnel named in the Schedule of Key Personnel, as referred to in the **Special Conditions of Contract**, to carry out the functions stated in the Schedule or other personnel approved by the Project Manager. The Project Manager will approve any proposed replacement of key personnel only if their relevant qualifications and abilities are substantially equal to or better than those of the personnel listed in the Schedule.
- 9.2 If the Project Manager asks the Contractor to remove a person who is a member of the Contractor's staff or work force, stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.
10. Employers Contractor's Risks and 10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor

carries the risks which this Contract states are Contractor's risks.

11. Employers Risks

11.1 From the Start Date until the Defects Correction Certificate has been issued, the following are Employer's risks:

(a) The risk of personal injury, death, or loss of or damage to property (excluding the Works, Plant, Materials, and Equipment), which are due to:

(i) use or occupation of the Site by the Works or for the purpose of the Works, which is the unavoidable result of the Works or

- Negligence, breach of statutory duty, or interference with any legal right by the Employer or by any person employed by or contracted to him except the Contractor.

(b) The risk of damage to the Works, Plant, Materials, and Equipment to the extent that it is due to a fault of the Employer or in the Employer's design, or due to war or radioactive contamination directly affecting the country where the Works are to be executed.

11.2 From the Completion Date until the Defects Correction Certificate has been issued, the risk of loss or damage to the Works, Plant, and Materials is an Employer's risk except loss or damage due to:

(a) a Defect which existed on the Completion Date,

(b) an event occurring before the Completion Date, which was not itself an Employer's risk, or

(c) the activities of the Contractor on the Site after the Completion Date.

12. Contractor's Risks

12.1 From the Starting Date until the Defects Correction Certificate has been issued, the risks of personal injury, death, and loss of or damage to property (including, without limitation, the Works, Plant, Materials, and Equipment) which are not Employer's risks are Contractor's risks.

13. Insurance

13.1 The Contractor shall provide, in the joint names of the Employer and the Contractor, insurance cover from the Start Date to the end of the Defects Liability Period, in the amounts and deductibles stated in the

Special Conditions of Contract for the following events which are due to the Contractor's risks:

- (a) loss of or damage to the Works, Plant, and Materials;
- (b) loss of or damage to Equipment;
- (c) loss of or damage to property (except the Works, plant, Materials, and Equipment) in connection with the Contract, and
- (d) Personal injury or death.

13.2 Policies and certificates for insurance shall be delivered by the Contractor to the Project Manager for the Project Manager's approval before the Start Date. All such insurance shall provide for compensation to be payable in the types and proportions of currencies required to rectify the loss or damage incurred.

13.3 If the Contractor does not provide any of the policies and certificates required, the Employer may effect the insurance which the Contractor should have provided and recover the premiums the Employer has paid from payments otherwise due to the Contractor or, if no payment is due, the payment of the premiums shall be a debt due.

13.4 Alterations to the terms of insurance shall not be made without the approval of the Project Manager.

13.5 Both parties shall comply with any conditions of the insurance policies.

14. **Site Investigation Reports** 14.1 The Contractor, in preparing the Bid, shall rely on any Site Investigation Reports referred to in the **Special Conditions of Contract**, supplemented by any information available to the Bidder.
15. **Queries about the Special Conditions of Contract** 15.1 The Project Manager will clarify queries on the **Special Conditions of Contract**.
16. **Contractor to Construct the Works** 16.1 The Contractor shall construct and install the Works in accordance with the Specifications and Drawings.
17. **Commencement and Completion of Works** 17.1 The Contractor may commence execution of the Works by the Start Date and shall carry out the Works in accordance with the Program submitted by the Contractor, as updated with the approval of the

- Project Manager, and complete them by the Intended Completion Date.
- 18. Approval by the Project Manager**
- 18.1 The Contractor shall submit Specifications and Drawings showing the proposed Temporary Works to the Project Manager, who is to approve them if they comply with the Specifications and Drawings.
- 18.2 The Contractor shall be responsible for design of Temporary Works.
- 18.3 The Project Manager's approval shall not alter the Contractor's responsibility for design of the Temporary Works.
- 18.4 The Contractor shall obtain approval of third parties to the design of the Temporary Works, where required.
- 18.5 All Drawings prepared by the Contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Project Manager before this use.
- 19. Protection of the environment**
- 19.1 The Contractor shall take all reasonable steps to protect the environment and to limit damage and nuisance to people and property resulting from pollution, noise and other results of his operations.
- 19.2 The Contractor shall ensure that emissions, surface discharges and effluent from his activities shall not exceed values prescribed in relevant environmental laws.
- 20. Labour Laws**
- 20.1 The Contractor shall comply with all the relevant labour laws applicable in the Country, including laws relating to workers employment, working hours, health, safety, welfare, immigration and shall allow them all their legal rights.
- 20.2 The Contractor shall require his employees to obey all applicable laws, including those concerning safety at work.
- 21. Health and Safety**
- 21.1 The Contractor shall at all times take all reasonable precautions to maintain the health and safety of his personnel.
- 21.2 The Contractor shall ensure that first aid facilities are available at all times at the site and that suitable arrangements are made for all necessary welfare and

hygiene requirements and for the prevention of epidemics

21.3 The Contractor shall notify the Employer details of any accident as soon as practicable after its occurrence. The Contractor shall maintain records and make reports concerning health, safety, and welfare of persons, and damage to the property, as the Employer may reasonably require.

21.4 The Contractor shall conduct an HIV-Aids awareness programme, and shall take other such measures as specified in the **SCC** to reduce the risk of transfer of HIV virus between and among Contractor's personnel, the Employers Staff and the surrounding community.

22. Discoveries

22.1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site shall be the property of the Employer. The Contractor shall notify the Project Manager of such discoveries and carry out the Project Manager's instructions for dealing with them.

23. Possession of the Site

23.1 The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date stated in the **Special Conditions of Contract**, the Employer will be deemed to have delayed the start of the relevant activities, and this will be a Compensation Event

24. Access to the Site

24.1 The Contractor shall allow the Project Manager and any person authorized by the Project Manager access to the Site and to any place where work in connection with the Contract is being carried out or is intended to be carried out.

25. Instructions, inspections and audits

25.1 The Contractor shall carry out all instructions of the Project Manager which comply with the applicable laws where the Site is located.

25.2 The Contractor shall permit the Government, of the United Republic of Tanzania to inspect the Contractor's accounts and records relating to the performance of the Contractor and to have them audited by auditors appointed by the Government of the United Republic of Tanzania if so required by the Government of the United Republic of Tanzania.

26. Disputes

26.1 If the Contractor believes that a decision taken by the Project Manager was either outside the authority

given to the Project Manager by the Contract or that the decision was wrongly taken, the decision shall be referred to the Adjudicator within 14 days of the notification of the Project Manager's decision.

27. Procedure for Disputes
- 27.1 The Adjudicator shall give a decision in writing within 28 days of receipt of a notification of a dispute.
- 27.2 The Adjudicator shall be paid by the hour at the rate specified in the Bid Data Sheet and Special Conditions of Contract, together with reimbursable expenses of the types specified in the **Special Conditions of Contract**, and the cost shall be divided equally between the Employer and the Contractor, whatever decision is reached by the Adjudicator. Either party may refer a decision of the Adjudicator to an Arbitrator within 28 days of the Adjudicator's written decision. If neither party refers the dispute to arbitration within the above 28 days, the Adjudicator's decision will be final and binding.
- 27.3 The arbitration shall be conducted in accordance with the arbitration procedure published by the institution named and in the place shown in the **Special Conditions of Contract**.
28. Replacement of Adjudicator
- of 28.1 Should the Adjudicator resign or die, or should the Employer and the Contractor agree that the Adjudicator is not functioning in accordance with the provisions of the Contract; a new Adjudicator will be jointly appointed by the Employer and the Contractor. In case of disagreement between the Employer and the Contractor, within 30 days, the Adjudicator shall be designated by the Appointing Authority designated in the **Special Conditions of Contract** at the request of either party, within 14 days of receipt of such request.

B. Time Control

29. Program
- 29.1 Within the time stated in the **Special Conditions of Contract**, the Contractor shall submit to the Project Manager for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.
- 29.2 An update of the Program shall be a program showing the actual progress achieved on each activity and the effect of

the progress achieved on the timing of the remaining work, including any changes to the sequence of the activities.

29.3 The Contractor shall submit to the Project Manager for approval an updated Program at intervals no longer than the period stated in the **Special Conditions of Contract**. If the Contractor does not submit an updated Program within this period, the Project Manager may withhold the amount stated in the **Special Conditions of Contract** from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Program has been submitted.

29.4 The Project Manager's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Project Manager again at any time. A revised Program shall show the effect of Variations and Compensation Events.

30. Extension of the Intended Completion Date

30.1 The Project Manager shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date without the Contractor taking steps to accelerate the remaining work, which would cause the Contractor to incur additional cost.

30.2 The Project Manager shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Project Manager for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information. If the Contractor has failed to give early warning of a delay or has failed to cooperate in dealing with a delay, the delay by this failure shall not be considered in assessing the new Intended Completion Date.

31. Acceleration

31.1 When the Employer wants the Contractor to finish before the Intended Completion Date, the Project Manager will obtain priced proposals for achieving the necessary acceleration from the Contractor. If the Employer accepts these proposals, the Intended Completion Date will be adjusted accordingly and confirmed by both the Employer and the Contractor.

31.2 If the Contractor's priced proposals for acceleration are accepted by the Employer, they shall be incorporated in the Contract Price and treated as a Variation.

32. Delays Ordered by the Project Manager 32.1 The Project Manager may instruct the Contractor to delay the start or progress of any activity within the Works.
33. Management Meetings 33.1 Either the Project Manager or the Contractor may require the other to attend a management meeting. The business of a management meeting shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.
- 33.2 The Project Manager shall record the business of management meetings and provide copies of the record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken shall be decided by the Project Manager either at the management meeting or after the management meeting and stated in writing to all who attended the meeting.
34. Early Warning 34.1 The Contractor shall warn the Project Manager at the earliest opportunity of specific likely future events or circumstances that may adversely affect the quality of the work increase the Contract Price or delay the execution of the Works. The Project Manager may require the Contractor to provide an estimate of the expected effect of the future event or circumstance on the Contract Price and Completion Date. The estimate shall provided by the Contractor as soon as reasonably possible.
- 34.2 The Contractor shall cooperate with the Project Manager in making and considering proposals for how the effect of such an event or circumstance can be avoided or reduced by anyone involved in the work and in carrying out any resulting instruction of the Project Manager.

C. Quality Control

35. Identifying Defects 35.1 The Project Manager shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Project Manager may instruct the Contractor to search for a Defect and to uncover and test any work that the Project Manager considers may have a Defect.
36. Tests 36.1 If the Project Manager instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect, the test shall be a Compensation Event.
37. Correction of Defects 37.1 The Project Manager shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion, and is defined in the **Special Conditions of Contract**. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.
- 37.2 Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Project Manager's notice.
38. Uncorrected Defects 38.1 If the Contractor has not corrected a Defect within the time specified in the Project Manager's notice, the Project Manager will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

39. Bill of Quantities 39.1 The Bill of Quantities shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.
- 39.2 The Bill of Quantities is used to calculate the Contract Price. The Contractor shall be paid for the quantity of the work done at the rate in the Bill of Quantities for each item.
40. Changes in the Quantities 40.1 If the final quantity of the work done differs from the quantity in the Bill of Quantities for the particular item by more than 25 percent, provided the change exceeds 1 percent of the Initial Contract Price, the Project Manager shall adjust the rate to allow for the change.

- 40.2 The Project Manager shall not adjust rates from changes in quantities if thereby the Initial Contract Price is exceeded by more than 15 percent, except with the prior approval of the Employer.
- 40.3 If requested by the Project Manager, the Contractor shall provide the Project Manager with a detailed cost breakdown of any rate in the Bill of Quantities.
- 41. Variations** 41.1 All Variations shall be included in updated Programs produced by the Contractor.
- 42. Payments for Variations** 42.1 The Contractor shall provide the Project Manager with a quotation for carrying out the Variation when requested to do so by the Project Manager. The Project Manager shall assess the quotation, which shall be given within seven days of the request or within any longer period stated by the Project Manager and before the Variation is ordered.
- 42.2 If the work in the Variation corresponds with an item description in the Bill of Quantities and if, in the opinion of the Project Manager, the quantity of work above the limit stated in sub-Clause 38.1 or the timing of its execution do not cause the cost per unit of quantity to change, the rate in the Bill of Quantities shall be used to calculate the value of the Variation. If the cost per unit of quantity changes, or if the nature or timing of the work in the Variation does not correspond with items in the Bill of Quantities, the quotation by the Contractor shall be in the form of new rates for the relevant items of Work.
- 42.3 If the Contractor's quotation is unreasonable, the Project Manager may order the Variation and make a change to the Contract Price, which shall be based on the Project Manager's own forecast of the effects of the Variation on the Contractor's costs.
- 42.4 If the Project Manager decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.
- 42.5 The Contractor shall not be entitled to additional payment for costs that could have been avoided by giving early warning.
- 43. Cash Flow Forecasts** 43.1 When the Program is updated, the Contractor shall provide the Project Manager with an updated cash flow forecast. The cash flow forecast shall include different currencies, as defined in the Contract, converted as necessary using the Contract exchange rates.

44. Payment Certificates

- 44.1 The Contractor shall submit to the Project Manager monthly statements of the estimated value of the work executed less the cumulative amount certified previously.
- 44.2 The Project Manager shall check the Contractor's monthly statement and certify the amount to be paid to the Contractor within twenty eight (28) days from the receipt of certificate.
- 44.3 The value of work executed shall be determined by the Project Manager.
- 44.4 The value of work executed shall comprise the value of the quantities of the items in the Bill of Quantities completed.
- 44.5 The value of work executed shall include the valuation of Variations, Compensation Events and Variation of Price.
- 44.6 The Project Manager may exclude any item certified in a previous certificate or reduce the proportion of any item previously certified in any certificate in the light of later information.
- 44.7 The Project Manager shall not bound to certify any payment, if the net amount, after all retentions and deductions would be less than minimum amount of Interim Payment Certificate stated in the **Special Condition of Contract**.

45. Payments

- 45.1 Payments shall be adjusted for deductions for advance payments and retention. The Employer shall pay the Contractor the amounts certified by the Project Manager within 28 days of the date of each certificate. If the Employer makes a late payment the Contractor shall be paid interest on the late payment in the next payment. Interest shall be calculated from the date by which the payment should have been made up to the date when the late payment is made at the prevailing rate of interest for commercial borrowing for each of the currencies in which payments are made.
- 45.2 If an amount certified is increased in a later certificate or as a result of an award by the Adjudicator or an Arbitrator, the Contractor shall be paid interest upon the delayed payment as set out in this clause. Interest shall be calculated from the date upon which the increased amount would have been certified in the absence of dispute.
- 45.3 Unless otherwise stated, all payments and deductions will be paid or charged in the proportions of currencies comprising the Contract Price.

46.
Compensation
Events

45.4 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

46.1 The following shall be Compensation Events:

- (a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Special Conditions of Contract.
- (b) The Employer modifies the Schedule of Other Contractors in a way that affects the work of the Contractor under the Contract.
- (c) The Project Manager orders a delay or does not issue Drawings, Specifications, or instructions required for execution of the Works on time.
- (d) The Project Manager instructs the Contractor to uncover or to carry out additional tests upon work, which is then found to have no Defects.
- (e) The Project Manager unreasonably does not approve a subcontract to be let.
- (f) Ground conditions are substantially more adverse than could reasonably have been assumed before issuance of the Letter of Acceptance from the information issued to bidders (including the Site Investigation Reports), from information available publicly and from a visual inspection of the Site.
- (g) The Project Manager gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
- (h) Other contractors, public authorities, utilities, or the Employer does not work within the dates and other constraints stated in the Contract, and they cause delay or extra cost to the Contractor.
- (i) The advance payment is delayed.
- (j) The effects on the Contractor of any of the Employer's Risks.
- (k) The Project Manager unreasonably delays issuing a Certificate of Completion.
- (l) Other Compensation Events described in the Contract or determined by the Project Manager shall apply.

- 46.2 If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date shall be extended. The Project Manager shall decide whether and by, how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.
- 46.3 As soon as information demonstrating the effect of each Compensation Event upon the Contractor's forecast cost has been provided by the Contractor, it shall be assessed by the Project Manager, and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Project Manager shall adjust the Contract Price based on the Project Manager's own forecast. The Project Manager will assume that the Contractor will react competently and promptly to the event.
- 46.4 The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor's not having given early warning or not having cooperated with the Project Manager.
- 47. Taxes** 47.1 The Project Manager shall adjust the Contract Price if taxes, duties, and other levies are changed between the date 28 days before the submission of bids for the Contract and the date of the last Completion certificate. The adjustment shall be the change in the amount of tax payable by the Contractor, provided such changes are not already reflected in the Contract Price or are a result of Clause 49.
- 48. Currencies** 48.1 Where payments are made in currencies other than the Tanzania Shillings, the exchange rates used for calculating the amounts to be paid shall be the exchange rates stated in the Contractor's Bid.
- 49. Price Adjustment** 49.1 The amounts payable to the Contractor, in various currencies pursuant to sub-Clause 44.1, shall be adjusted in respect of the rise or fall in the cost of labour, Contractor's Equipment, Plant, materials, and other inputs to the Works, by applying to such amounts the formulae prescribed in this clause.
- 49.2 To the extent that full compensation for any rise or fall in costs to the Contractor is not covered by the provisions of this or other clauses in the Contract, the unit rates and prices included in the Contract shall be deemed to include amounts to cover the contingency of such other rise or fall of costs.

- 49.3 The adjustment to be applied to amount payable to the Contractor as certified in Payment Certificates shall be determined formulae for each of the currencies in which the Contract Price is payable. No adjustment is to be applied to work valued on the basis of Cost or current prices. The formulae shall be as follows:

$$P_n = a + b \frac{L_n - L_o}{L_o} + c \frac{M_n - M_o}{M_o} + d \frac{E_n - E_o}{E_o} + \text{etc.}$$

where;

P_n is a price adjustment factor to be applied to the amount in each specific currency for the payment of the work carried out in the subject month, where such variations and daywork are not otherwise subject to adjustment;

a is a constant, specified in the **Appendix to Bid**, representing the nonadjustable portion in contractual payments;

b, c, d, etc., are weightings or coefficients representing the estimated proportion of each cost element (labour, materials, equipment usage, etc.) in the Works or sections thereof, net of Provisional Sums, as specified in the **Appendix to Bid**; the sum of a, b, c, d, etc., shall be one;

L_n, M_n, E_n, etc., are the current cost indices or reference prices of the cost elements in the specific currency of origin for month "n," determined pursuant to Sub-Clause 49.5, applicable to each cost element; and

L_o, M_o, E_o, etc., are the base cost indices or reference prices corresponding to the above cost elements at the date specified in Sub-Clause 49.5

The value of net work done, certified by the Project Manager, in any monthly Interim or Final Certificate as payable by the Employer to the Contractor before deduction of any retention money shall be increased or decreased by an amount of 'F'.

$$F = P_n x P_c$$

where;

The effective value P_c of work done which is to be subjected to increase or decrease shall be the difference between:

- (i) the amount which, in the opinion of the Project Manager, is due to the Contractor under Clause 44 (before deduction of retention money and before deducting sums previously paid on account) less:
 - any amount for payment or repayment of any advance payment;
 - any amount for materials on site (if any);
 - any amounts for nominated sub-contractors (if any)
 - any amounts for any other items based on actual cost or current prices; or
 - any sums for increase or decreases in the Contract Price paid under this Sub-Clauseand
 - (ii) the amount calculated in accordance with (i) above of this Sub-clause and included in the last preceding statement.
- 49.4 The sources of indices shall be those listed in the **Appendix to Bid**, as approved by the Engineer. Indices shall be appropriate for their purpose and shall relate to the Contractor's proposed source of supply of inputs on the basis of which his Contract Price and expected foreign currency requirements shall have been computed. As the proposed basis for price adjustment, the Contractor shall have submitted with his bid the tabulation of Weightings and Source of Indices in the **Appendix to Bid**, which shall be subject to approval by the Engineer.
- 49.5 The base cost indices or prices shall be those prevailing on the day 28 days prior to the latest date for submission of bids. Current indices or prices shall be those prevailing on the day 28 days prior to the last day of the period to which a particular Interim Payment Certificate is related. If at any time the current indices are not available, provisional indices as determined by the Engineer will be used, subject to subsequent correction of the amounts paid to the Contractor when the current indices become available
- 49.6 If the Contractor fails to complete the Works within the time for completion prescribed under Clause 57 adjustment of prices thereafter until the date of completion of the Works shall be made using either the indices or prices relating to the prescribed time for completion, or the current indices or prices, whichever is more favourable to the Employer, provided that if an extension of time is granted pursuant to

Clause 28, the above provision shall apply only to adjustments made after the expiry of such extension of time.

49.7 The weightings for each of the factors of cost given in the **Appendix to Bid** shall be adjusted if, in the opinion of the Engineer, they have been rendered unreasonable, unbalanced, or inapplicable as a result of varied or additional work already executed or instructed under Clause 42 or for any other reason.

50. Retention

50.1 The Employer shall retain from each payment due to the Contractor the proportion stated in the **Special Conditions of Contract** until Completion of the whole of the Works.

50.2 On completion of the whole of the Works, half the total amount retained shall be repaid to the Contractor and the other half when the Defects Liability Period has passed and the Project Manager has certified that all Defects notified by the Project Manager to the Contractor before the end of this period have been corrected.

50.3 On completion of the whole Works, the Contractor may substitute retention money with an 'on demand' Bank guarantee.

51. Liquidated Damages

51.1 The Contractor shall pay liquidated damages to the Employer at the rate per day stated in the **Special Conditions of Contract** for each day that the Completion Date is later than the Intended Completion Date. The total amount of liquidated damages shall not exceed the amount defined in the Special Conditions of Contract. The Employer may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages shall not affect the Contractor's liabilities.

51.2 If the Intended Completion Date is extended after liquidated damages have been paid, the Project Manager shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment certificate. The Contractor shall be paid interest on the overpayment, calculated from the date of payment to the date of repayment, at the rates specified in Sub- Clause 43.1.

52. Bonus

52.1 The Contractor shall be paid a Bonus calculated at the rate per calendar day stated in the **Special Conditions of Contract** for each day (less any days for which the Contractor is paid for acceleration) that the Completion is earlier than the Intended Completion Date. The Project Manager shall certify that the Works are complete, although they may not be due to be complete.

53. Advance Payment 53.1 The Employer shall make advance payment to the Contractor of the amounts stated in the **Special Conditions of Contract** by the date stated in the Special Conditions of Contract, against provision by the Contractor of an Unconditional Bank Guarantee or Performance bond in a form and by a bank acceptable to the Employer in amounts and currencies equal to the advance payment. The Guarantee shall remain effective until the advance payment has been repaid, but the amount of the Guarantee shall be progressively reduced by the amounts repaid by the Contractor. Interest will not be charged on the advance payment.
- 53.2 The Contractor is to use the advance payment only to pay for Equipment, Plant, Materials, and mobilization expenses required specifically for execution of the Contract. The Contractor shall demonstrate that advance payment has been used in this way by supplying copies of invoices or other documents to the Project Manager.
- 53.3 The advance payment shall be repaid by deducting proportionate amounts from payments otherwise due to the Contractor, following the schedule of completed percentages of the Works on a payment basis. No account shall be taken of the advance payment or its repayment in assessing valuations of work done, Variations, price adjustments, Compensation Events, Bonuses, or Liquidated Damages.
54. Performance Securities 54.1 The Performance Security shall be provided to the Employer no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form and by a bank or surety acceptable to the Employer, and denominated in the types and proportions of the currencies in which the Contract Price is payable as specified in the **SCC**. The Performance Security shall be valid until a date 28 days from the date of issue of the Certificate of Completion in the case of a Bank Guarantee, and until one year from the date of issue of the Completion Certificate in the case of a Performance Bond
55. Dayworks 55.1 If applicable, the Dayworks rates in the Contractor's Bid shall be used for small additional amounts of work only when the Project Manager has given written instructions in advance for additional work to be paid for in that way.
- 55.2 All work to be paid for as Dayworks shall be recorded by the Contractor on forms approved by the Project Manager. Each completed form shall be verified and signed by the Project Manager within two days of the work being done.
- 55.3 The Contractor shall be paid for Dayworks subject to obtaining signed Dayworks forms.


56. Cost of Repairs 56.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

57. Completion Certificate 57.1 The Contractor shall request the Project Manager to issue a certificate of Completion of the Works, and the Project Manager will do so upon deciding that the work is completed.
58. Taking Over 58.1 The Employer shall take over the Site and the Works within seven days of the Project Manager's issuing a certificate of Completion.
59. Final Account 59.1 The Contractor shall supply the Project Manager with a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Project Manager shall issue a Defects Liability Certificate and certify any final payment that is due to the Contractor within 56 days of receiving the Contractor's account if it is correct and complete. If it is not, the Project Manager shall issue within 56 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Project Manager shall decide on the amount payable to the Contractor and issue a payment certificate.
60. Operating and Maintenance Manuals 60.1 If "as built" Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the **Special Conditions of Contract**.
- 60.2 If the Contractor does not supply the Drawings and/or manuals by the dates stated in the **Special Conditions of Contract**, or they do not receive the Project Manager's approval, the Project Manager shall withhold the amount stated in the **Special Conditions of Contract** from payments due to the Contractor.

- 61. Termination**
- 61.1 The Employer or the Contractor may terminate the Contract if the other party causes a fundamental breach of the Contract.
- 61.2 Fundamental breaches of Contract shall include, but shall not be limited to, the following:
- a) the Contractor stops work for 28 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Project Manager;
 - b) the Project Manager instructs the Contractor to delay the progress of the Works, and the instruction is not withdrawn within 28 days;
 - c) the Employer or the Contractor is made bankrupt or goes into liquidation other than for a reconstruction or amalgamation;
 - d) a payment certified by the Project Manager is not paid by the Employer to the Contractor within 84 days of the date of the Project Manager's certificate;
 - e) the Project Manager gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Project Manager;
 - f) the Contractor does not maintain a Security, which is required; and
 - g) the Contractor has delayed the completion of the Works by the number of days for which the maximum amount of liquidated damages can be paid, as defined in the **Special Conditions of Contract**.
 - h) If the Contractor, in the judgment of the Employer, has engaged in corrupt or fraudulent practices in competing for or in executing the Contract.
- 61.3 When either party to the Contract gives notice of a breach of Contract to the Project Manager for a cause other than those listed under sub-Clause 61.2 above, the Project Manager shall decide whether the breach is fundamental or not.
- 61.4 Notwithstanding the above, the Employer may terminate the Contract for convenience.

- 61.5 If the Contract is terminated, the Contractor shall stop work immediately, make the Site safe and secure, and leave the Site as soon as reasonably possible.
- 62. Payment upon Termination of Contract**
- 62.1 If the Contract is terminated because of a fundamental breach by the Contractor, the Project Manager shall issue a certificate for the value of the work done and Materials ordered less advance payments received up to the date of the issue of the certificate and less the percentage to apply to the value of the work not completed, as indicated in the **Special Conditions of Contract**. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor, the difference shall be a debt payable to the Employer.
- 62.2 If the Contract is terminated for the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Project Manager shall issue a certificate for the value of the work done, Materials ordered, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works, and less advance payments received up to the date of the certificate.
- 63. Property**
- 63.1 All Materials on the Site, Plant, Equipment, Temporary Works, and Works shall be deemed to be the property of the Employer if the Contract is terminated because of the Contractor's default.
- 64. Release from Performance**
- 64.1 If the Contract is frustrated by the outbreak of war or by any other event entirely outside the control of either the Employer or the Contractor, the Project Manager shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which a commitment was made.
- 65. Suspension of Financing**
- 65.1 In the event that the source of financing is suspended to the Employer, from which part of the payments to the Contractor are being made:
- (a) The Employer is obligated to notify the Contractor of such suspension within 7 days of having received the financing agency's suspension notice.
 - (b) If the Contractor has not received sums due it within the 28 days for payment provided for in Sub-Clause 45.1, the Contractor may immediately issue a 14-day termination notice.



SECTION V : SPECIAL CONDITION OF CONTRACT

Special Conditions of Contract

Instructions for completing the Special Conditions of Contract

SCC Clause	GCC Clause	Description
1.	1.1	<p>The Employer is : District Executive Director, Mkalama District Council, P.O. Box 1007 Mkalama, TANZANIA Authorized representative: DE MKALAMA DC</p> <p>The Project Manager is DE MKALAMA DC</p> <p>The name and identification number of the Contract is .LGA/147/2021/2022/WIMF/06</p> <p><i>Constraction of Emergency Building at District Hospital</i></p> <p>The Start Date shall be within 10 days after official possession of site</p> <p>The Intended Completion Date for the whole of the Works shall be Two Months</p> <p>The following documents also form part of the Contract:</p> <ul style="list-style-type: none"> Agreement, Letter of Acceptance, Contractor's Bid, Special Conditions of Contract, General Conditions of Contract, Specifications, Drawings, Bill of Quantities, and <p>The sites are located at District Hospital</p>
2.	2.2	Indicate whether there is section completion is specified: not specified.
3.	2.3(9)	List other documents that form part of the contract if any: Not Applicable
4.	3.1	The language of the Contract documents is English The law that applies to the Contract is the Tanzanian Law.

5.	8.1	Include the Schedule of Other Contractors, if any. Not Applicable																					
6.	9.1	<p>Include the Schedule of Key Personnel.</p> <table border="1"> <thead> <tr> <th>Position</th> <th>Total experience (years)</th> <th>In similar works (years)</th> </tr> </thead> <tbody> <tr> <td>Project Manager</td> <td>5</td> <td>5</td> </tr> <tr> <td>Site Agent</td> <td>5</td> <td>3</td> </tr> <tr> <td>Site Engineer</td> <td>5</td> <td>3</td> </tr> <tr> <td>Civil Engineering Technician</td> <td>5</td> <td>3</td> </tr> <tr> <td>Land Surveyor</td> <td>5</td> <td>3</td> </tr> <tr> <td>Electro-Mechanical Engineer</td> <td>5</td> <td>3</td> </tr> </tbody> </table>	Position	Total experience (years)	In similar works (years)	Project Manager	5	5	Site Agent	5	3	Site Engineer	5	3	Civil Engineering Technician	5	3	Land Surveyor	5	3	Electro-Mechanical Engineer	5	3
Position	Total experience (years)	In similar works (years)																					
Project Manager	5	5																					
Site Agent	5	3																					
Site Engineer	5	3																					
Civil Engineering Technician	5	3																					
Land Surveyor	5	3																					
Electro-Mechanical Engineer	5	3																					
7.	14.1	<p>The minimum insurance covers shall be:</p> <p>The minimum insurance covers shall be:</p> <ul style="list-style-type: none"> (a) loss of or damage to the Works, Plant, and Materials Tshs. 299,000,000 million (b) loss of or damage to Equipment Tshs 299,000,000 million (c) loss of or damage to property (except the Works, Plant, Materials, and Equipment) in connection with the Contract Tshs 20 million; and (d) personal injury or death Tshs 10 million 																					
8.	15.1	Site Investigation Reports available to the Bidder are: Not Applicable																					
9.	22.4	<p>The other measures include:</p> <ul style="list-style-type: none"> a. Minimising the number of migrant workers employed on the project and household in the site camp b. Providing access to voluntary counselling and testing (VCT) c. Providing psychological support and health care including prevention and treatment of opportunistic infections for workers infected and affected, as well as their families d. Providing condoms (male and female) to workers 																					
10.	24.1 & 47.1	The Site Possession Date shall be within 14 days after signing of contract.																					
11.	28.2	<p>Hourly rate of Fees payable to the Adjudicator is: TShs. 100,000/-</p> <p>Types of reimbursable expenses to be paid to the Adjudicator include:</p>																					

		a) Transport b) Subsistence allowances
12.	28.3	Arbitration will take place at Dar es Salaam in accordance with rules and regulations published by National Construction Council
13.	29.1	Appointing Authority for the Adjudicator: Mkalama District Council.
A. Time Control		
14.	30.1	The Contractor shall Submit a Programme for the Works within seven (7) days of delivery of the Letter of Acceptance.
15.	30.3	The period between Programme updates is fourteen (14) days.
16.	30.3	The amount to be withheld by the Project Manager in the case the contractor does not submit an updated programme is: Tanzania Shillings One Million (1,000,000).
B. Quality Control		
17.	38.1	The Defects Liability Period is 360 days.
C. Cost Control		
18	46.1	The interest rate shall be the prevailing borrowing rates of the Bank of Tanzania at the date of payment.
19.	47.1	The currency is: Tanzanian Shillings
20.	47.1(a)	The Site Possession Date shall be within 14 days after signing of contract
21.	50	The contract is not subject to price adjustment in accordance with Clause 50 of the General Conditions of Contract.
22.	51.1	The amount of retention is ten (10) percent of value of works of Interim Payment Certificate'.
		Limit of retention will be five (5) percent of contract price.
23.	52.1	The amount of liquidated damages is 0.1% of the contract sum per day to a maximum of 10% of the Contract sum.
	52.1	The maximum amount of liquidated damages must be equivalent to the amount of the performance security; 10% of the Contract sum
24.	53.1	The bonus for early completion is Not Applicable
25.	54.1	The amount of advance payment shall be 10% for bank Guarantee and 30% for performance bond of the contract sum payable within 28 days of submission of acceptable advance payment guarantee. (Performance bond or Bank Guarantee)

		Monthly Recovery of Advance Payment: Repayment through percentage deductions with every interim payment with equal proportions provided it exceeds 20% of works done per certificate.
26.	55.1	The Performance Security shall be an amount equivalent to percent of the contract price as follows: <ul style="list-style-type: none"> • Performance Bank guarantee – 10% of contract price OR • Performance bond - 30% of the contract price. (From Bank)
		D. Finishing the Contract
27.	61.1	As built drawings shall be supplied by the contractor no later than one month after completion of works Operating manual shall be supplied by the contractor by no later than one month after completion of works
28.	61.2	The amount to be withheld by the Project Manager in the case the contractor does not submit as built drawings is: Tanzania Shillings Five Million (5,000,000) The amount to be withheld by the Project Manager in the case the contractor does not submit operating manual is: Tanzania Shillings Five Million (5,000,000)
29.	62.2 (g)	Number of days for which the maximum amount of liquidated damages can be paid is 100 days
30.	63.1	The percentage to apply to the value of the work not completed, representing the Employer's additional cost for completing the Works, is forty (40) percent

SECTION VI : BILL OF QUANTITY

PRESIDENT'S OFFICE
REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT



BILL OF QUANTITIES FOR THE PROPOSED CONSTRUCTION OF
EMERGENCY MEDICAL DEPARTMENT BUILDING



November, 2021

GENERAL SUMMARY

GENERAL DESCRIPTIONS	AMOUNT
BILL No 01 - PRELIMINARIES	2,500,000.00
BILL No 02 - SPECIFICATIONS	-
BILL No 03 - MEASURED WORKS (EMD BLOCK)	249,427,300.00
BILL No 04 - PRIME COSTS AND PROVISIONAL SUMS	1,000,000.00
SUB-TOTAL	252,927,300.00
INSURANCE CLAUSES:	
<ul style="list-style-type: none"> . Clause 13 - Contractor to maintain in joint names of the Employer and Contractor, Insurance Against Loss and Damages to the works by fire, earthquakes, etc. . Clause 54 - Performance Security 	1,000,000.00
SUB-TOTAL ----- (1)	253,927,300.00
<u>ADD:</u> 18% Value Added Tax (VAT) -----	45,706,914.00
SUB-TOTAL ----- (2)	299,634,214.00
AMOUNT CARRIED TO FORM OF TENDER TShs.	299,634,214.00

Signed by [Signature] For and on behalf of KUMILA ENTERPRISES

In the capacity of Managing Director made this 2nd day of FEB 2022



[Signature]

ITEM	DESCRIPTIONS OF WORKS	TSHS.
	<p>DESCRIPTION OF SITE:</p> <p>A. The site is located District/Councils WITHIN TANZANIA COUNTRY</p> <p>B. The Contractor shall provide and maintain any necessary temporary roads; sleeper tracks; and temporary cross over during the execution of the works; clear away the same at completion and reinstate and make good any work disturbed to the satisfaction of the Local Authority and the Employer.</p> <p>C. The Contractor shall be deemed to have visited the site and satisfied himself as to:-</p> <ul style="list-style-type: none"> i) The nature of the site ii) The amount of bush; rubbish or debris to be cleared away before commencement. iii) The nature of proximity and size of adjoining building and property. iv) The nature of existing communications by roads or otherwise. v) The means of access to the site. vi) The availability of land for the erection and positioning of all temporary structures; plant and materials necessary for the execution of the works. vii) The source of adequate supplies of labour, plant and materials for the completion of the works. <p>D. If the Contractor wishes to execute trial holes before submitting his tender; he may do so in positions to be agreed with the Employer and at his sole expenses; including the reinstatement of the ground if so required by the Employer.</p> <p>E. The whole of the site will be available to the Contractor immediately upon the issue of the order to commence.</p> <p>F. Any sand; aggregate to or other building materials shall be the property of the Employer and shall not be used in the construction of the works without the written consent of the Employer.</p> <p>G. The Contractor is to satisfy himself as to any difficulties that the site may present and to make all necessary enquiries to any point which in his opinion requires further elucidation as no claim for lack of information on any of the above will be entertained.</p>	
	<p>TO COLLECTION TSHS.</p>	



ITEM	DESCRIPTIONS OF WORKS	TSHS.
A.	<p>DESCRIPTION OF WORKS: The work within this contract comprises of: <i>Substructure, Frames, Walls, ramp, Stairs, Roof, Doors, Windows, Service Engineering, Finishings, Decorations and External Works on Construction of Emergency Medical Department</i></p>	
B.	<p>SINGULAR AND PLURAL Word importing the singular only also includes the plural.</p>	
C.	<p>LAW GOVERNING CONTRACT The contract shall be in all respect to be constructed and operated in accordance with the law of Tanzania.</p>	
D.	<p>METHOD OF MEASUREMENT: These Bills of Quantities have been prepared in accordance with the standard method of measurement of Building Works for East Africa first edition (metric) published by the architectural association of Kenya chapter of Quantity Surveyor Act: 1970. and applied equally to the measurement of proposed works and of variations by Quantity Surveyors.</p>	
E.	<p>Variation of 'Builder's Work' will be subject to the same amended rates of percentage of adjustment.</p>	
F.	<p>DEFINITIONS OF ABBREVIATIONS: The Contractor should take due notice of the under mentioned abbreviations:- mm - millimetres cm - centimetres M³ - cubic meters M² - square metres M - linear metres No - Number Kg - Kilograms P.C - Prime cost</p>	
G.	<p>The Contractor shall allow for keeping all records appertaining to the work and shall keep on the site a daily diary recording weather conditions; temperature; visitors to the site, etc.</p>	
H.	<p>The Contractor is to supply to the Employer such information as he may be required in connection with the work; including statement showing the number of men employed in all trades daily; and delivery notes (stating the name of the project) for all materials delivered to the site.</p>	
TO COLLECTION TSHS.		



8/1/3

ITEM	DESCRIPTIONS OF WORKS	TSHS.
A.	<p>EMPLOYER'S INSPECTION: No work shall be covered up until it is inspected and approved by the Employer.</p>	
B.	<p>The Employer may at any time before the end of defects liability period or during any extended time where any defect are being made good, instruct the Contractor to open up; pull down; test or expose any part of the works in order to satisfy himself as to the quality of materials or workmanship used. If in the opinion of the Employer such parts are not in strict accordance with the contract documents he may order the Contractor to remove all defective work, replace with approved materials and reinstate any such part of the works and any other disturbed at his own expenses and to the entire satisfaction of the Employer. If any such parts of the works are found to be in accordance with the contract documents the Contractor will be reimbursed with the General conditions of contract.</p>	
C.	<p>DISTURBANCE OR NUISANCE: The Contractor shall allow for taking all necessary precautions in the order and execution of the work so as to avoid causing disturbance or nuisance to the occupants of existing buildings and those adjacent to the works and for complying with the Employer's instructions in this respect. The Contractor shall be in tort for such nuisance and shednets.</p>	
D.	<p>TRESPASS, DAMAGE AND CARE OF WORKS: The Contractor shall prevent any trespass on the opinion adjoining property and he shall take all reasonable precautions during the progress of the contract to prevent any damage to the adjoining property or plant or private roadways and to prevent material, plant; rubbish and debris, etc. collecting on the adjoining property or roadways.</p>	
E.	<p>Should the Contractor wish to erect scaffolding or to make use of adjoining property; he shall obtain prior permission from the Employer and clear away at a completion of his work or when directed and make good any damage to his satisfaction. Except as provided for in the General conditions of contract, the Contractor; shall be held responsible for the care of works generally until their completion; including all works executed and materials deposited on the site by himself or his Sub-Contractors or supplier together with all risks arising from weather, carelessness of operatives; damages and he shall make good all such damage or loss at his own expense</p>	
F.	<p>The Contractor shall be responsible for the protection of any adjacent building; boundary walls; fences; services either overhead or underground and for the making good of or paying for all damage thereto; should such be caused in the course of building operations.</p>	
G.	<p>The Contractor shall allow for making good all damage to the road; kerbs; surface water channels; etc. occasioned by heavy traffic; delivery of materials and building operations generally to the entire satisfaction of the Employer and shall be responsible for observing any by law of Local Authority regarding keeping the road free from mud; filth dirt; etc. out of the execution of the works.</p>	
<p>TO COLLECTION TSHS.</p>		



ITEM	DESCRIPTIONS OF WORKS	TSHS.
A.	<p><u>PROTECTION FROM THE WEATHER:</u> The Contractor shall allow for covering up and protecting all new work from injury by weather or any other cause. Any damage, loss or expense caused by non-compliance with the clause shall be at sole risk of the contract.</p>	
B.	<p><u>TOOLS, PLANT AND SCAFFOLDING:</u> Provide all necessary concrete mixer and other plant including ladder, staging, access gangways tackle, tarpaulins, tools, moulds templates and other requisites necessary for proper executing, adapting from time to time as may be necessary and maintain all plant and equipment during the course of the contract.</p>	1,000,000.00
C.	<p>The Contractor shall allow for providing adapting from time to time as may be necessary and maintaining all scaffolding scaffold boards and temporary staging, etc, necessary for the execution of the works.</p>	
D.	<p>The Contractor is to provide everything necessary for the proper execution of the works according to the true intent and meaning of the drawings; etc. whether the same may or may not be particularly shown on the drawings, specifications provided that the same is reasonably to be inferred there from.</p>	
E.	<p><u>SITE ACCOMODATION.</u> The Contractor shall provide and maintain any necessary temporary office accommodation required by himself and his Sub-Contractors suitably equipped with desks, chairs, drawing boards; and electric lighting and telephone.</p>	1,00,000.00
F.	<p>The Contractor shall provide and maintain for his workers latrine facilities washing and drinking water, first aid equipment's and shelters equipped with tables; benches and checking facilities all to the reasonable satisfaction of the workers and approved by the Employer and Health Authorities.</p>	1,00,000.00
G.	<p>The Contractor shall provide and maintain any temporary storage, shed or buildings which in his opinion are necessary for himself and his Sub-Contractors for the execution of the works.</p>	1,00,000.00
H.	<p><u>WATER FOR THE WORKS</u> The Contractor shall allow for all necessary clean fresh water for the works, including that required by Sub-Contractors and for any temporary plumbing metres and storage facilities and pay all charges in connection therewith and clear away on completion and make good works disturbed.</p>	300,000.00
J.	<p>The Contractor shall allow for providing and maintaining a temporary electricity supply for the works including that required by Sub-Contractor and for any meters and fittings to give artificial lighting and power necessary for the execution of the works and pay all charges, in connection and make good all works disturbed.</p>	200,000.00
TO COLLECTION TSHS.		1,800,000.00



Jr

ITEM	DESCRIPTIONS OF WORKS	TSHS.
A.	<p>WATCHING AND LIGHTING:</p> <p>The Contractor shall allow for providing and maintaining any barriers; hoarding; watching; lighting which must comply with the By-laws of requirements of the Local Authority and policy regulations and the Contractor must give all requisite policies to those authorities and provide everything necessary to protect the general public workmen; plant; materials and the whole of the works</p> <p>No advertisement will be permitted without the written authority of the Employer.</p>	250,000.0
C.	<p>SIGN BOARD:</p> <p>The Contractor shall provide and erect a large sized sign board on the site showing the title of the contract, the name and address of the Employer; consultant, nominated suppliers and Sub-Contractor and such information as may be required by the Employer who shall provide the sign layout and colours of the Board. The board shall be repainted when necessary and removed when no longer required.</p>	250,000.0
D.	<p>PROTECTION:</p> <p>The Contractor is required to protect works section until completion.</p>	
E.	<p>TESTING:</p> <p>Allow for testing all the installations required to be tested and provide everything necessary for this purpose and leave the whole in perfect working order to the satisfaction of the Employer and Local Authority.</p>	
F.	<p>REMOVING RUBBISH AND CLEANING:</p> <p>The Contractor shall make good all defects and injuries to the works, clean down external faces wash off stains to face work, clean off marks mortar and cement, clean windows inside and out, scrub floors, flush drains run and leave all parts of the works clean, free from rubbish and waste materials and perfect on completion.</p>	100,000.0
G.	<p>The Contractor shall clean and cart away all rubbish as it accumulate and keep the works in orderly condition to the satisfaction of the Employer</p>	100,000.0
TO COLLECTION		700,000.0
COLLECTION		
Page No. 8/1/1		—
Page No. 8/1/2		—
Page No. 8/1/3		—
Page No. 8/1/4		1,800,000.0
Page No. 8/1/5		700,000.0
BILL No. 01- PRELIMINARIES CARRIED TO GENERAL SUMMARY		2,500,000.0



[Handwritten signature]

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NR. 1: SUBSTRUCTURE					
EXCAVATION AND EARTHWORK					
A	Site clearance of small trees, shrubs and the like including grubbing up roots	643	m ²	500	321,500
	<u>Excavating</u>				
B	Surfaces to reduce levels average 150mm deep vegetable soil and remove from site	643	m ²	500	321,500
	<u>Trenches in natural ground; to receive foundations; starting from reduced level</u>				
C	Not exceeding 1.50 meters deep	219	m ²	2,000	438,000
D	Ditto over 1.50 m not exceeding 3.0 m deep	0	m ²		
	<u>Pits; to receive foundations; starting from stripped level</u>				
E	Not exceeding 1.50 meters deep	15	m ²	2,000	30,000
F	Extra over all kinds of excavations irrespective of depth for breaking up rock	5	m ²	2,000	10,000
G	Backfilling; depositing and compacting in layers maximum 150mm thick impoed material around foundations	126	m ²	1,000	126,000
H	Remove away from the site surplus excavated materials.	0	m ²		
	<u>Disposal of water</u>				
J	Keeping all excavation free from all water by pumping, bailing or other means including spring or running water		Item		
	<u>Planking and Strutting</u>				
K	Allow for provision and subsequent removal for planking and strutting to uphold and maintain all faces of excavations		Item		
To Collection					1,247,000



ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>filling</u> Sand filling in making up levels: average 150 mm thick	133	m ²	1,000	133,000
B	<u>hardcore and the like</u> 150mm thick stone hardcore bed: leveled compacted and sand bladed to receive damp proof membrane: measured separately.	536	m ²	2,000	1,072,000
C	<u>Soil Sterilization</u> Chemical anti termite treatment around the building plinth	125	m	500	62,500
D	Aldrin' solution applied at a rate of 7 litres per square metre	536	m ²	500	268,000
E	<u>Concrete works</u> <u>In situ concrete plain grade 10' mix ratio (1:4:8)</u> 50mm thick blinding	5	m ²	15,000	75,000
F	<u>Plain in-situ concrete; grade 15N/sq.mm nominal mix (1:3:6)</u> 100mm Bed	536	m ²	10,000	5,360,000
G	Ditto to ramp	112	m ²	15,000	1,680,000
H	Foundation footing	48	m ²	170,000	8,160,000
J	<u>Vibrated Reinforced in-situ concrete; grade 25 nominal mix (1:11/2:3)</u> Column bases	4	m ³	170,000	680,000
K	Plinth beam	23	m ³	170,000	3,910,000
L	Columns	1	m ³	170,000	170,000
M	<u>Reinforcement; bars; BS 4449:1969 hot rolled round high yield steel straight or bent</u> 12mm Diameter bars	1363	kg	2,500	3,407,500
N	8mm Diameter bars	826	kg	2,500	2,065,000
To Collection					27,043,000



[Handwritten signature]

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Formwork, sawn formwork</u>				
A	Vertical sides of columns:	3	m ²	10,000	30,000
B	Lift to vertical sides of beams	203	m ²	10,000	2,030,000
C	Vertical sides of slab over 75mm not exceeding 150mm	125	m	10,000	1,250,000
	<u>Walling</u>				
	<u>Concrete block B.S 2028 type A: 5N per square millimetre: solid in cement sand mortar (1:4)</u>				
D	230mm Thick wall	258	m ²	25,000	6,450,000
E	Damp-proof Courses (DPC) 230mm Wide	240	m	1,000	240,000
	<u>Damp-proof Membrane (DPM)</u>				
F	500Gauge polythene sheet laying on blinded hardcore with 150mm sides and end laps	536	m ²	1,000	536,000
	<u>Sundries</u>				
G	12mm Cement and sand (1:3) external rendering to concrete block wall	57	m ²	4,000	228,000
H	Prepare and apply two coats of black bituminous paint on rendered or concrete surfaces, externally	57	m ²	1,000	57,000
					10,821,000
	<u>To Collection</u>				
	COLLECTION				
	Page 2/1/1				1,247,000
	Page 2/1/2				27,043,00
	Page 2/1/3				10,821,000
	ELEMENT NO. 1 - SUBSTRUCTURE CARRIED TO SUMMARY				39,111,000



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO. 2 - FRAME					
<u>Concrete work</u>					
<u>Vibrated Reinforced in-situ concrete; grade 25 nominal mix (1-11/2:3)</u>					
A	Beams; horizontal or sloping not exceeding 15 degrees from horizontal	26	m ³	170,000	4,420,000
B	Columns	2	m ³	170,000	340,000
C	Fin wall	4	m ³	170,000	680,000
D	150mm Thick suspended roof slab	65	m ³	170,000	11,050,000
E	150mm thick roof gutter	85	m ³	170,000	14,450,000
F	150mm thick side gutter wall	105	m ³	170,000	17,850,000
<u>Reinforcement; bars; BS 4449:1969 hot rolled round high yield steel straight or bent</u>					
G	16mm Diameter bars	470	kg	2,500	1,175,000
H	12mm Diameter bars	4948	kg	2,500	12,370,000
J	8mm Diameter bars	851	kg	2,500	2,127,000
K	BRC Mesh	45	m ²	2,500	90,000
<u>Sawn formwork(Marine plywood) to</u>					
L	Vertical sides of column	20	m ²	7,000	140,000
M	Horizontal sides and soffits of beams	360	m ²	7,000	2,520,000
N	To soffits of suspended slab	63	m ²	7,000	441,000
P	To soffits of roof gutter	83	m ²	7,000	581,000
Q	To sides of gutter wall	200	m ²	7,000	1,400,000
R	To vertical sides fin walls	91	m ²	7,000	637,000
S	To edge of roof gutter over 75mm but n.e 150mm high	140	m ²	7,000	980,000
ELEMENT NO. 2 - FRAME CARRIED TO SUMMARY					71,251,500

NOVEMBER 2021



PO-RALG

71,274,000

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO4: WALLS					
<u>Block Work</u>					
<u>Internal wall</u>					
<u>Solid Concrete block B.S 2028 type A. 5MPa bedded and jointed in cement/sand mortar (1:4)</u>					
A.	150mm Wall	492	m ²	21,500	10,578,000
<u>External wall</u>					
<u>Solid Concrete block B.S 2028 type A. 5MPa bedded and jointed in cement/sand mortar (1:4)</u>					
B.	230mm Wall	238	m ²	25,000	5,950,000
C.	150mm Wall fin wall	80	m ²	21,500	1,720,000
<u>Vibrated reinforced concrete grade 25 nominal mix (1:11/2:3)</u>					
D.	230x150mm Coping with wire mesh 2.5mm and all formwork	36	m	2,500	90,000
E.	250x100mm window Cill ditto	55	m	2,500	137,500
<u>METAL WORKS</u>					
<u>Supply and fix weldable Mild steel to smooth edges grills walls, comprising of 75 x75 mm RHS framework and braces, 25x25mm top, bottom, vertical and horizontal bars welded to frames spaced at 150mm centre to centre including all paints</u>					
F.	Metal grille wall	20	m ²	70,000	1,400,000
ELEMENT NO4: WALLS CARRIED TO SUMMARY					19,875,500



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO 5: DOORS					
<u>Hardwood materials</u>					
A	50x150mm Frame with one labour	283	m	1,500	424,500
B	50x150mm Transome and Mullion with one labour	48	m	1,500	72,000
C	25 x 25mm Glazing beads	143	m	1,000	143,000
<u>Hardwood Mninga or equal and approved</u>					
D	45mm thick panelled door hardwood size 1800x 2100mm double swing door; comprising of 45x100mm rebated stiles; all panel filled in with and including 25mm thick hardwood boards; {D1}	2	Nr.	700,000	1,400,000
E	Ditto Size 1500 x 2100m double swing door {D2}	4	Nr.	600,000	2,400,000
F	Size 1000 x 2100m Single door {D4}	3	Nr.	400,000	1,200,000
G	Size 800 x 2100m Single door {D6}	2	Nr.	300,000	600,000
<u>Flush door</u>					
Doors; formica plastic laminated facing both sides cherry Mkongo or Mninga or equal aproved hardwood lipping to all edges; solid core flush door; formic; storm grey with hardwood edge strip; 45mm thick MDF doors					
H	Size 1000 x 2100mm single doors	22	Nr.	320,000	7,040,000
J	Size 800 x 2100m single door shutter	4	Nr.	300,000	1,200,000
Ironmongery; supply and fix the following as manufactured by Union ltd. or other equal and approved to hardwood with matching screws"					
K	Double Action Swing Hinges for hardwood door approx 25 - 50Kg	9	Pairs	20,000	180,000
L	150mm Brass butt hinges.	46.5	Pairs	5,000	232,000
M	3 Lever Mortice lock	33	Nr.	80,000	2,640,000
N	Two Lever Mortice lock	4	Nr.	60,000	240,000
					17,772,000



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>Clear glass</u> 5mm thick glass including beads glass over 0.5m ² not exceeding 1.00m ² Supply and fix weldable Mild steel to smooth edges grills comprising of 75 x75 mm RHS framework and braces, 25x25mm top, bottom, vertical and horizontal bars welded to frames spaced at 150mm centre to centre including all paints	30	m ²	25,000	750,000
B	Size 1500 x 2100mm double door complete with all accessories and associated Ironmongery to the Approval Project Engineer	1	Nr.	280,000	280,000
C	Door vent size 1800 x 700mm high	2	Nr.	115,000	230,000
D	Size 1500 x 700mm high	4	Nr.	95,000	380,000
E	Size 1000 x 700mm high	3	Nr.	65,000	195,000
F	Size 800 x 700mm high	2	Nr.	50,000	100,000
<u>To Collection</u>					1,935,000
<u>COLLECTION</u>					
Page 2/5/1					17,772,000
Page 2/5/2					1,935,000
ELEMENT NO 5: DOORS CARRIED TO SUMMARY					19,707,000



J2

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO 6: WINDOWS					
<u>Aluminium glazing approved by the Architect; single glazed combination frame and windows, 45 x 50mm Aluminium section framing, all mullions and transomes; epoxy power coat RAL 9006 finish, 6.14mm laminated glass pre assembled with stainless steel plates and screws window ironmongery, glazed beads, fiber mosquito net, rubber gaskets and backer rods and fixing to masonry or concrete grounds, sealing all around with non-hardening EPDM silicone sealant; screws bolts and fasteners</u>					
A	Size 1800 x 1800mm high	5	Nos	250,000	1,250,000
B	Ditto, Size 1500 x 1800mm high	6	Nos	200,000	1,200,000
C	Ditto, Size 1200 x 1800mm high	9	Nos	150,000	1,350,000
D	Ditto, Size 1200 x 1050mm high	6	Nos	120,000	720,000
E	Ditto, Size 900 x 1800mm high	2	Nos	120,000	240,000
F	Ditto, Size 900 x 1050mm high	9	Nos	80,000	720,000
G	Ditto, Size 600 x 1050mm high	2	Nos	50,000	100,000
ELEMENT NO6:WINDOWS CARRIED TO SUMMARY					5,580,000



ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO.7: ROOFING					
<u>Sawn soft wood; Impregnated with Preservatives</u>					
A	50X150mm Beam	336	m	3,500	1,176,000
B	50X150mm Rafters	356	m	3,500	1,246,000
C	50X100mm Struts	445	m	2,500	1,112,500
D	50X100mm Wall Plate	141	m	2,500	352,500
E	50X50mm Purfins	612	m	1,500	918,000
<u>28 gauge IT5 resincoated roofing sheets fixed to timber purfins with 150mm end laps, 1 1/2 corrugations side laps fixed with roofing nails.</u>					
F	Roof covering; sloping not exceeding 45 degrees from horizontal	599	m ²	16,000	9,584,000
G	Ridge capping	60	m	5,000	300,000
H	Valley capping	45	m	4,500	202,500
<u>Metal Works</u>					
J	16mm Diameter Anchor Bolts	160	No	4,000	640,000
K	10mm thick steel plate	80	No	10,000	800,000
<u>Roof drainage:</u>					
L	150mm Diameter UPVC drain down pipe Class D; fixing with and including brackets and fixing accessories	55	M	12,000	660,000
M	Extra; Drain Body.	15	No	5,000	75,000
N	Extra; Elbow	15	No	5,000	75,000
P	Extra; 150mm thick outlet fullbora	15	No	3,000	45,000
ELEMENT NO. 07 - ROOFING CARRIED TO SUMMARY					17,186,500



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO. 08: FINISHINGS					
<u>Insitu finishings</u>					
<u>Plastering in two coats steel trowelled to smooth finish internally</u>					
A	15mm To walls and columns	1087	m ²	3,000	3,261,000
B	15mm to sides of beams	289	m ²	3,000	867,000
C	15mm thick to soffits of slab, roof gutter etc.	146	m ²	3,000	438,000
D	15mm thick to sides of gutter walls	200	m ²	3,000	600,000
<u>Plastering in two coats steel trowelled to smooth finish externally</u>					
E	22mm To walls	355	m ²	3,500	1,242,500
TILES, SLAB OR BLOCK FINISHINGS					
<u>Glazed ceramic wall tiles with cushion edges to BS 1281 fixed to backings with cement sand mortar and pointing with white cement</u>					
F	400 x 250 x 6mm Tiling to walls	155	m ²	10,000	1,550,000
<u>Graniti GN 572 Mid Grey porcelain tiles "high quality" bedding in premixed thin set cement mortar and grouting with coloured sandless tile grout</u>					
G.	600x600x8mm; 4mm diagonally joints ways; to floors to level; to cement and sand base	457	m ²	18,000	8,226,000
H.	400 x400 x 8mm; 4mm diagonally joints ways to floor level of toilets, cement and sand base	36	m ²	15,000	540,000
J.	150mm Thick skirting	417	m	5,000	2,085,000
<u>C-Tiles "high quality" to ramp and drop off area bedding in premixed thin set cement mortar and grouting with coloured sandless tile grout</u>					
K	450x450x15mm; joints ways: to floors to levels to drop off point/ramps by cement and sand base	170	m ²	15,000	2,550,000
<u>Floor edge strips</u>					
L	GENESIS ESA 10(10mm high) or similar and approved, aluminium straight edge trim; junctions of flooring finishes	30	m	1,500	45,000
To Collection					21,404,500



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Weather Bars</u>				
A	6 x 25mm Brass weather bar strip at external door thresholds; in prepared groove	15	m	1,000	15,000
	<u>Tanga stone or equal and approved other materials</u>				
B	Wall finishing materials to the external façade as per drawings	43	m ²	2,000	86,000
	<u>Beds and Backings</u>				
	<u>Cement and sand (1:4) wood floated surface finish</u>				
C.	32mm Bed to receive floor tiles	613	m ²	2,000	1,226,000
D.	12mm Backing to receive wall tiles and tanga stone	198	m ²	2,000	396,000
	<u>Gypsum plasterboard BS 1230 Pt. 2 1970 tapered wallboard self tapping galvanized drive screws</u>				
E.	9mm Thick ceiling; horizontal; internal	493	m ²	3,000	1,479,000
F	Cornice	415	m	4,000	1,660,000
G	Extra; moulding gypsum	65	m	5,000	3,25,000
H	Extra ceiling access panel	4	Nr.	10,000	40,000
J.	Supply and fix PVC ceiling complete including PVC and corner joints, shoe nail and all accessories	100	M ²	1,000	100,000
	<u>Sawn softwood pressure impregnated with preservatives</u>				
K.	50x50mm branderling fixed at 600mm centre to centre	1300	m	4,000	5,200,000
To Collection					10,577,000



ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
SLAB TREATMENT					
<i>Water proofing to exposed surface, concrete treatment for permanent corrosion free water/ Moisture proofing by using by using krystal technology</i>					
<i>Thoroughly clean concrete surfaces to remove all types of dirt, fill all visible cracks, honeycombs and holes as per krystal specification No 1; sand surface to smooth level, prepare and apply full coat of krystal T2; protect and cure properly as per manufacture's direction and krystal specification</i>					
A	To roof slabs.	65	M ²	2,000	130,000
B	To sides and bottom of concrete gutters.	240	M ²	2,000	480,000
WORKTOP/PARTITION					
C	Supply and fix Aluminium Partition as per Architect drawings and details at reception counter including associated finishes of mable and any other to the aproval of Architect	15	m2	30,000	450,000
D	Ditto worktop to kitchen/sluice/labaratory	11	m2	30,000	330,000
E	Allow sum for LOGO for writing EMERGENCY MEDICAL DEPARTMENT to respective name of the council Hospital. As per elevation by using ALUCOBOND Materials			Sum	100,000
To Collection					1,490,000
COLLECTION					21,404,
Page 2/8/1					10,527,
Page 2/8/2					1,490,000
Page 2/8/2					
ELEMENT NO 08: FINISHINGS CARRIED TO SUMMARY					33,421,



[Handwritten signature]

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
ELEMENT NO. 09: PAINTING AND DECORATIONS					
<u>Internal works</u>					
<u>Prepare and apply one thinned coat and two full coats of wash 'n' ware paint</u>					
A	Plastered walls	1676	m ²	3,000	5,028,000
B	Gypsum ceiling	493	m ²	3,000	1,479,000
<u>External works</u>					
<u>Prepare and apply one thinned coat and two full coats of weather guard paint to</u>					
C	Rendered surfaces	355	m ²	3,000	1,065,000
<u>Varnishing; internal work; prepare and apply three coats of clear polyurethane clear varnish; wood surfaces.</u>					
D	General surfaces	155	m ²	3,000	465,000
E	Frames, linings and associated mouldings 200-300mm girth	331	m	3,000	993,000
ELEMENT NO. 09 : PAINTING AND DECORATIONS CARRIED TO SUMMARY					9,030,000

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
<p>ELEMENT NO. 10: SANITARY WARE INSTALLATIONS</p> <p><u>KITCHEN SINK</u></p> <p>Stainless steel kitchen single with single drainer complete with tap hole provided on the sink the waste unit as manufactured by castleware; sink Model No. D10050A including all fixing fixtures</p>					
A	Overall size L1000 X W500mm x D180mm bowl size L380 x W330mm	1	Nr.	110,000	110,000
<p><u>WASH HAND BASIN</u></p>					
B	White vitreous wash hand basin (HWB), size 750x440x200mm complete with self closing; semi pedestal and chain stay hole; fairline 1/2in pillar taps with clear acrylic handles; 1 1/2in bead chain waste and plug; 80cm slotted tail bolt stay; isovalve servicing valves, rubber plug with slotted tail; 32mm plastic bottle trap with 75mm seal. And other accessories as manufactured by castleware or equal and approved	14	No	80,000	1,120,000
<p><u>SLUICE SINKS</u></p>					
C.	B22362 Wall Mounted slop Hopper with Draining Board stainless steel slop hopper manufactured from Grade 304 stainless steel for the efficient and hygienic disposal of waste including draining boards, top slab, intergral flushing rim, standard outlet for PVC sewerage systems Either P-trap or S- trap and the unit must be space -effective as per manufactured to the approval of Project Manager/ Engineer	2	Nr.	200,000	400,000
<p><u>SOAP DISH</u></p>					
D.	Ceramic soap dish Model A:101 as manufactured by castleware or equal aproved including fixing fixtures, fixed to the wall as per manufacturer recommendations	2	Nr.	10,000	20,000
To Collection					



Handwritten signature

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
WC					
A	Western type low level W.C suite vitrious china to B.S 3402 s/p-trap, 9litres flushing tank with single push button complete with all necessary accessories. "Casterware "	1	No	350,000	350,000
B	Ditto but Eastern type as per Armitage or other approved, complete with 9 Litres flush tank and all accessories	4	No	250,000	1,000,000
C	Finned and plain plastic W.C outlet connector to B.S 5627:1984	4	No	20,000	80,000
D	Supply and install complete set of Disabled toilets with HWB,grab rails,mixer and all necessary accessories including HWB and handrails set as per Service Engineer approval "RAK/ROCA	1	No	350,000	350,000
E	80mm Diameter high quality plastic floor drain (ALBETONY) trap built in concrete bed.	3	No	10,000	30,000
TOILET PAPER ROLL HOLDER					
F	Wall mounted stainless Toilet paper holder Model BC 70 complete with fixing accessories as manufactured by castleware or equal and approved	5	Nr.	5,000	25,000
To Collection					1,835,000



ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
SHATTAF					
A	Wall mounted 'trigger spray' shattaf Oasis chrome finish complete with fixing accessories as manufactured by castleware or equal and approved	6	Nr.	8,000	48,000
BRUSH HOLDER					
B	Toilet brush holder 'model : BC 60 as manufactured by castleware or equal and approved including all fixing fixtures	4	Nr.	3,000	12,000
MIRROR					
C	600 X 800 X 4mm Thick mirror with JX -S501 as per castleware or other approved, fixed on lacquer with double sided self adhesive pads finished with bevelled edges.	14	Nr.	10,000	140,000
FLOOR DRAIN					
D	150 X 150mm stainless steel grating ABS flange with adaptor or ring complete with kerdin-fix bounding compound, all as to manufacturers recommendations	5	Nr.	10,000	50,000
COLD WATER INSTALLATION:					
<u>IPS pipes, Class D painted with special paint; including joints in running length. Fixing in accordance with manufacture's instructions.</u>					
<u>Distribution pipes IPS pipes including screwed screwed and socketted joints in running length:</u>					
E	25mm Diameter Polypipe, class D	40	M	2,500	100,000
F	19mm Diameter Polypipe, class D	99	M	800	79,200
G	Extra; elbow	2	No	1,000	2,000
H	IPS Socket	1	No	1,000	1,000
J	Ditto connectors	1	No	1,000	1,000
K	Ditto Union	1	No	1,000	1,000
L	Ditto Tee	1	No	1,000	1,000
M	Ditto Reducing bush 25 x 19mm	9	No	1,000	9,000
TO COLLECTION					444,200



AA

ITEM	DESCRIPTIONS OF WORKS	QTY	UNIT	RATE	AMOUNT
A.	19 mm Diameter supply IPS pipes; in blockwork chase.	45	M	1,000	45,000
B.	Extra ditto; elbow	16	No	800	12,800
C.	Ditto tee	16	No	1,000	16,000
D.	Ditto: Union	14	No	1,000	14,000
E.	Ditto: Nipple	16	No	1,000	16,000
F.	Ditto: connector	16	No	1,000	16,000
G.	Ditto:tee connector	16	No	1,000	16,000
H.	15 mm Diameter supply IPS pipes; in blockwork chase.	40	M	1,000	40,000
J.	Extra reducing tee 19x19x15	9	No	1,000	9,000
K.	Extra; reducing bush 19x15	9	No	1,000	9,000
L.	Extra; 15mm elbow.	40	No	800	32,000
M.	Ditto; tee.	15	No	1,000	15,000
N.	Ditto: Nipple	50	No	1,000	50,000
P.	Ditto; socket	40	No	1,000	40,000
Q.	Ditto; tee coupling	16	No	1,000	16,000
	<u>Flexible piping:</u>				
R.	Flexible pipe to cistern	5	No	1,000	5,000
S.	Flexible pipe to Hand Wash Basin	14	No	1,000	14,000
T.	Flexible pipe to Kitchen sinks and sluice	1	No	1,000	1,000
V.	angle valve	16	No	5,000	80,000
W.	Bib tape pex 1/2	6	No	5,000	30,000
X.	Pillar tape pex 1/2	14	No	10,000	140,000
Z.	Stop cock pex 3/4	9	No	10,000	90,000
TO COLLECTION					706,800



[Handwritten signature]

ITEM	DESCRIPTIONS OF WORKS	QTY	UNIT	RATE	AMOUNT
SOIL AND PIPES:					
<u>UPVC pipes and fittings; Class 'B'; in running lengths; BS 4660 for underground pipes and B.S 3506 for pipes above ground.</u>					
A	100mm. Diameter pipes; fixed to walls including fixing accessories.	30	M	5,000	150,000
B	Ditto; laid in trenches.	50	M	5,000	250,000
C	Extra; 100mm bend.	5	No	2,500	12,500
D	Extra; 100mm Equal Double Y-Tee.	4	No	2,500	10,000
E	Extra; 100mm Equal Tee	8	No	2,500	20,000
F	100mm Diameter PVC vent coil.	1	No	5,000	5,000
G	P-Trap 4'	4	No	5,000	20,000
H	Bottle trap flexible 38mm	14	No	4,000	56,000
Ancillaries:					
<u>Draw off taps; stop valves; copper alloy to BS 5154 or BS 1010:</u>					
J	38mm Diameter stop valve.	2	No	3,000	6,000
K	32mm Diameter stop valve.	2	No	3,000	6,000
L	25mm Diameter stop valve	2	No	3,000	6,000
M	19mm Diameter stop valve	5	No	3,000	15,000
N	13mm Diameter bib taps	14	No	3,000	42,000
Gas pipe installation					
P	50mm Heavy Gauge PVC Class C for Gas to concealed along the ceiling/concrete work, for supply Gas from Distribution room to all required room as per detailed drawing including builder's works	60	m	10,000	600,000
					2,198,500



ITEM	DESCRIPTIONS OF WORKS	QTY	UNIT	RATE	AMOUNT
<u>EQUIPMENT:</u>					
<u>FIRE FIGHTING INSTALLATIONS:</u>					
A	9Kg, dry powder 'NAFFCO' or any other equal and approved fire extinguishers, fixed to wall with and including brackets plugged on block work.	2	No	50,000	100,000
B	Fire assembly point signage	1	No	10,000	10,000
<u>GULLY TRAPS</u>					
C	Construct a standard gully trap 300x300x300mm deep; in thick concrete block walls complete with benching and all fittings and gully trap cover	13	No	4,000	52,000
<u>TESTING</u>					
D	Allow for testing and commissioning the whole plumbing and drainage installation as per service Engineer approval	-	Item	-	
E	Builders work in connection to plumbing	-	Item	-	
<u>SUNDRIES:</u>					
F	Allow for preparation and production of two (2) copies of 'AS BUILT DRAWINGS' of plumbing and engineering installations to Engineer's satisfaction.	-	Item	-	
COLLECTION					162,000
<u>COLLECTIONS</u>					
	Page 3/10/1				1,650,000
	Page 3/10/2				1,835,000
	Page 3/10/3				444,200
	Page 3/10/4				706,800
	Page 3/10/5				745,600
	Page 3/10/6				1,198,000
	Page 3/10/7				162,000
<u>ELEMENT NO. 10 SANITARY WARE AND INSTALLATIONS CARRIED TO SUMMARY</u>					6,742,100



[Handwritten signature]

[Handwritten signature]
6,652,100

S/N	DESCRIPTION OF MATERIALS	UNIT	QTY	RATE	AMOUNTS
ELEMENT NR. 11- ELECTRICAL INSTALLATION					
DISTRIBUTION SYSTEM					
A	4Ways TPN distribution board (DB 3) with 100A/300mmA RCCB incomer and outgoing MCBs as shown in Schematic diagram as ABB or approved equal.	No	3	500,000	1,500,000
POWER POINTS					
B	2 x 13A switch socket c/w steel box as ABB or HAGER or LEGRAND make	No	33	5,000	165,000
C	20A DP control switch with neon indicator c/w steel box for Air Conditioners, Security lights and Hand driers as ABB or HAGER or LEGRAND make	No	12	10,000	120,000
D	45A DP Cooker Control Unit with neon indicator c/w steel box as ABB or HAGER or LEGRAND make	No	1	15,000	15,000
E	2.4KW Hand dryer c/w sensing unit automatically controlled as GET Ex UK	No	4	15,000	60,000
LIGHT FITTINGS, FANS AND SWITCHES					
F	Single fluorescent fitting complete LED philips or other equal approved	No	28	15,000	420,000
G	LED: Fluorescent fitting 60mm cassette type	No	16	10,000	160,000
H	LIGHT FITTING TYPE Ceiling light complete with energy saver 18W	No	21	15,000	315,000
J	80W 56" Sweep ceiling fan c/w regulator, ceiling rose and hooks as Panasonic or National or KDK of Japan.	No	1	80,000	80,000
K	10A 1 gang 1 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	30	2,500	75,000
L	10A 2 gang 1 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	10	5,000	50,000
M	10A 1 gang 2 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	1	5,000	5,000
N	10A 2 gang 2 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	1	5,000	5,000
To collection					2,970,000




S/N	DESCRIPTION OF MATERIALS	UNIT	QTY	RATE	AMOUNT
A	10A 3 gang 1 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	2	4,000	8,000
B	Twin switch socket ABB or other equal approved	No	30	10,000	300,000
C	10A 3 gang 2 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	10	6,000	60,000
D	10A 4 gang 1 way flush light switch c/w steel box as ABB or HAGER or LEGRAND make	No	10	5,000	50,000
LIGHTNING PROTECTION SYSTEM					
E	Soil treatment and interconnection to general earthing of building to meet the requirement of IEE regulations. NB: Cables for 1.5sqmm 2.5sqmm and 4sqmm should be EURO or other equal approved	Item	1	150,000	150,000
CABLES					
F	1C x 1.5mm ² PVC copper cable				
	(i) Brown	Roll	8	60,000	480,000
	(ii) Blue	Roll	8	60,000	480,000
	(iii) Yellow/Green	Roll	8	60,000	480,000
G	1C x 2.5mm ² PVC copper cable				
	(i) Brown	Roll	5	90,000	450,000
	(ii) Blue	Roll	5	90,000	450,000
	(iii) Yellow/Green	Roll	5	90,000	450,000
H	1C x 4.0mm ² PVC copper cable				
	(i) Brown	M	30	2,000	60,000
	(ii) Blue	M	30	2,000	60,000
	(iii) Yellow/Green	M	30	2,000	60,000
FIXED ENCLOSURES FOR CABLE RUNS					
J	20mm Dia heavy gauge PVC conduit to all lighting, fans c/w all accessories as MCL make	Pcs	210	1,500	315,000
K	25mm Dia heavy gauge PVC conduit for Cooker Control unit, DP control switches and switch socket points and ICT related works c/w all necessary accessories as MCL make	Pcs	20	3,000	60,000
L	75mm Dia heavy gauge PVC conduit for supply from the Main Panel Distribution Board to all necessary accessories as MCL/ PLASCO make	Pcs	10	4,000	40,000
To collection					3,953,000

NOVEMBER 2021



PO-RALG

S/N	DESCRIPTION OF MATERIALS	UNIT	QTY	RATE	AMOUNT
A	Accessories (Single PVC Rectangular/Square Boxes, Twin PVC Rectangular/Square Boxes, Round PVC Boxes, Cover plates, metal box single and twin, coupling, elbow, fine screw, plastic clips 22mm, bulk head light fitting) and Binding wires	Item	1	400,000	400,000
EARTHING SYSTEM.					
B	Soil treatment and interconnection to general earthing of building to meet the requirement of IEE regulations. Two earth pits with adequate number of earth rods linked together with the earthing cables from the main distribution panel board, filled with wet charcoal/salt or bentonite powder.	Item	1	50,000	50,000
C	Earth wire 4sqmm	Mts	60	2,000	120,000
D	Earth rod approved copper 16mm not less than 1200mm	Nr.	6	100,000	600,000
"AS BUILT/INSTALLED" DRAWINGS					
E	Prepare "As Built/Installed" drawings clearly indicating all conduit routes and submit in hard and soft copies.	Sets	2	200,000	400,000
F	Prepare "As Built/Installed" drawings clearly indicating all installed fittings and submit in hard and soft copies.	Sets	2	150,000	300,000
AIR CONDITIONING					
<u>Supply and Install Air conditioning as per LG or equal and approved Manufacturer by Mechanical/ Electrical Engineer</u>					
G	Smart inveter indoor wall mounted fan evaporating units with its outdoor unit, the indoor unit shall be complete with a wireless remote controller, pipes brackets and connecting cable, including all accessories, cooling capacity 18000BTU/hr	Sets	5	1,600,000	8,000,000
H	Smart inveter indoor wall mounted fan evaporating units with its outdoor unit, the indoor unit shall be complete with a wireless remote controller, pipes brackets and connecting cable, including all accessories, cooling capacity 24000BTU/hr	Sets	4	540,000	2,160,000
To collection					12,030,000



S/N	DESCRIPTION OF MATERIALS	UNIT	QTY	RATE	AMOUNT
A	Smart inveter indoor cassette fan evaporating units with its outdoor unit, the indoor unit shall be complete with a wireless remote controller, pipes brackets and connecting cable, with and including all accessories cooling capacity 24000BTU/hr	Sets	3	540,000	1,620,000
B	PVC conduits pipe sleeve class C size 2 inch in the ceiling/blockwall or duct for Airconditions, including Elbow and other connection	m	24	3,000	72,000
To collection					1,692,000
<u>COLLECTION</u>					
Page 3/11/1					2,970,000
Page 3/11/2					3,953,000
Page 3/11/3					12,030,000
Total Cost for Electrical Carried to Summary Page					20,645,000



Handwritten signature

ITEM	DESCRIPTIONS OF WORKS	QTY	UNIT	RATE	AMOUNT
ELEMENT NR. 12: FOUL WATER DRAINAGE					
DRAINAGE					
A.	Excavate trench to receive pipes; commencing at ground level; not exceeding 1.5m. deep; average 1000mm. deep; including grading bottom; backfilling and compacting and removal of surplus excavated material.	50	m	3,000	150,000
SEPTIC TANK:					
B	Construct septic tank overall internal dimensions; size 4800 x 3000 x 2800mm. deep in 230mm. thick solid concrete blocks walls; 230mm. thick plain in-situ concrete grade '15' bed; 100mm. thick reinforced in-situ concrete grade '20' suspended slab reinforced with 10mm diameter x 100 x 100mm BRC square mesh; 80mm. thick baffle wall; complete with necessary pipe fittings; 4No. cast iron manholes covers and frames; vent pipe; finished to wall sides and top of slab with 15mm thick, water proof cement and sand render; including excavation back filling and removal of surplus material; all as per and shown in the drawings.	1	No	1,500,000	1,500,000
SOAK PIT (S.P)					
C	Construct Soak pit overall size 3800mm diameter x 3500mm from invert level average depth; in 230mm. solid concrete block walls with weep holes at a height shown in the drawings; 230 x 450mm. plain insitu concrete grade '15' foundation at the bottom; 100mm. Thick suspended slab in reinforced insitu concrete grade '20' reinforced with 10mm diameter x 100 x 100mm BRC square mesh; 1No. Cast iron manhole cover and frames; vent pipe; top of slab finished with cement and sand (1:3) screed; including excavations; backfilling and removal of surplus material; all as per and shown in the drawing.	1	No	1,500,000	1,500,000
MANHOLES:					
D	Construct standard manhole size 600 x 600mm average depth 1500mm deep; in 150mm. thick solid concrete blocks walls; 150mm. thick plain in-situ concrete grade '15' bed; complete with berching and all necessary pipe fittings; 1No. cast iron manholes covers and frames; finished to wall sides and top of slab with water proof cement and sand render; including excavation back filling and removal of surplus material; all as per and shown in the drawings.	13	No	50,000	650,000
ELEMENT NO. 12 FOUL WATER DRAINAGE					3,800,000
CARRIED TO SUMMARY					



Handwritten signature or initials.

ITEM	DESCRIPTIONS OF WORKS	QTY	UNIT	RATE	AMOUNT
ELEMENT NR. 13: ICT INSTALLATION					
A	Switch 24-port with Gigabit Uplinks	1	PC	15,000	15,000
B	UTP CABLE Cat 6	2	PC	250,000	500,000
C	6U data cabinet wall mounted including all accessories eg.	1	PC	15,000	15,000
D	Rack Mountable UPS 1100VA	1	PC	4,000	4,000
E	1m Patch cord	22	PC	8,000	176,000
F	3m Patch cord	22	PC	24,000	528,000
G	Cat 6 patch panel 24 Port	1	PC	120,000	120,000
H	Cable manager	1	PC	25,000	25,000
J	Dual face plate	11	PC	50,000	550,000
K	Back Box Single (Steel)	11	PC	2,200	24,200
L	Conduit pipe 1.0"	40	PC	5,500	220,000
Sub Total for ICT Materials					2,177,200
Add :Labour cost for subtotal 1					300,000
Add :Profit from Sub total 1					300,000
Add: Attendance for sub total 1					300,000
Grand total for Element Nr. 13 ICT Installation carried to Summary Page					3,077,200



ITEM	DESCRIPTION	PAGE	AMOUNT
BILL NR.3: EMD MEASURED WORKS SUMMARY			
	ELEMENT NO. 01 - SUBSTRUCTURE	3/1/3.	39,111,000
	ELEMENT NO. 02 - FRAME	3/2/1.	71,251,500
	ELEMENT NO. 03 - STAIRS	NA	NA
	ELEMENT NO. 04 - WALLS	3/4/1.	19,875,500
	ELEMENT NO. 05 - DOORS	3/5/2	19,707,000
	ELEMENT NO. 06 - WINDOWS	3/6/1	5,589,000
	ELEMENT NO. 07 - ROOF	3/7/1.	17,186,000
	ELEMENT NO. 08 - FINISHINGS	3/8/3.	33,421,500
	ELEMENT NO. 09 - PAINTING AND DECORATIONS	3/9/1.	9,030,000
	ELEMENT NO.10: SANITARY WARE AND INSTALATIONS	3/10/7.	6,742,100
	ELEMENT NO. 11: ELECTRICAL INSTALLATION	3/11/3.	20,645,000
	ELEMENT NO. 12: FOUL WATER DRAINAGE	3/12/1.	3,800,000
	ELEMENT NO. 13: ICT INSTALLATIONS	3/13/1.	3,077,200
BILL NO.3 - MEASURED WORKS CARRIED GENERAL SUMMARY		T.Shs	249,427,300



BILL NO: 04 - PRIME COST AND PROVISIONAL SUMS

TEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<p>BILL NR.4: PRIME COST AND PROVISIONAL SUM</p> <p><u>Prime Cost (PC) Sums for works to be carried out by Nominated subcontractors or Nominated suppliers</u></p>				
A	Electrical Connection and water connection		Sum		1,000,000
	<p>BILL NR.4- PC AND PROVISIONAL SUMS WORK CARRIED TO GENERAL SUMMARY</p>				1,000,000




PROGRAMME OF WORK FOR TENDER NO. LGA/097/2021 - 2022/SDC/W/03 CONSTRUCTION OF EMERGENCY MEDICA

Unit	Description	Activity Description	Days																																	
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	
A. SUBSTRUCTURE																																				
1	Site clearance and leveling setting out																																			
2	Excavation of foundation (concrete footing + strip foundation + collar chairs)																																			
3	Blanking and filling of foundation																																			
4	Rebarbing and filling of Main wall																																			
5	Setting of Main wall and floor slab formwork for Overalls concrete and Column formwork for Overalls concrete and Column formwork for floor beams and columns																																			
6	Setting of floor beams and columns																																			
7	Setting of floor beams and columns																																			
8	Setting of floor beams and columns																																			
9	Setting of floor beams and columns																																			
B. SUPERSTRUCTURE																																				
1	Formwork setting out and erecting formwork for Upright beam and top beam																																			
2	Formwork for Upright beam and top beam																																			
3	Formwork for Upright beam and top beam																																			
4	Formwork for Upright beam and top beam																																			
5	Formwork for Upright beam and top beam																																			
C. ROOFING																																				
1	Preparation and setting of roof form																																			
2	Formwork setting Formwork for floor beams and top beam																																			
3	Formwork																																			
D. FINISHING																																				
1	Internal plastering and ceiling plastering																																			
2	Plastering of walls, windows and doors																																			
3	Plastering of walls, windows and doors																																			
4	Plastering of walls, windows and doors																																			
E. PAINTING																																				
1	Painting internal external and ceiling																																			
2	Painting internal external and ceiling																																			
3	Painting internal external and ceiling																																			

102 FEB 2022
B. R. R.

L DEPARTMENT BUILDING (EMD) AND THREE IN ONE SEMI DETACHED STAFF HOUSE RURAL TYPE (3 IN 1) AT MTOWISA HOSPITAL








 2022

SECTION VII : DRAWINGS

DOOR & WINDOW SCHEDULE				
NO.	WIDTH	HEIGHT	TYPICAL	TYPE
01	1000mm	2000mm	2	DOUBLE SLIDING DOOR
02	1000mm	2000mm	1	DOUBLE SLIDING DOOR
03	1000mm	2000mm	1	DOUBLE SLIDING DOOR
04	1000mm	2000mm	1	DOUBLE SLIDING DOOR
05	1000mm	2000mm	1	DOUBLE SLIDING DOOR
06	1000mm	2000mm	1	DOUBLE SLIDING DOOR
07	1000mm	2000mm	1	DOUBLE SLIDING DOOR
08	1000mm	2000mm	1	DOUBLE SLIDING DOOR
09	1000mm	2000mm	1	DOUBLE SLIDING DOOR
10	1000mm	2000mm	1	DOUBLE SLIDING DOOR
11	1000mm	2000mm	1	DOUBLE SLIDING DOOR
12	1000mm	2000mm	1	DOUBLE SLIDING DOOR
13	1000mm	2000mm	1	DOUBLE SLIDING DOOR
14	1000mm	2000mm	1	DOUBLE SLIDING DOOR
15	1000mm	2000mm	1	DOUBLE SLIDING DOOR
16	1000mm	2000mm	1	DOUBLE SLIDING DOOR
17	1000mm	2000mm	1	DOUBLE SLIDING DOOR
18	1000mm	2000mm	1	DOUBLE SLIDING DOOR
19	1000mm	2000mm	1	DOUBLE SLIDING DOOR
20	1000mm	2000mm	1	DOUBLE SLIDING DOOR
21	1000mm	2000mm	1	DOUBLE SLIDING DOOR
22	1000mm	2000mm	1	DOUBLE SLIDING DOOR
23	1000mm	2000mm	1	DOUBLE SLIDING DOOR
24	1000mm	2000mm	1	DOUBLE SLIDING DOOR
25	1000mm	2000mm	1	DOUBLE SLIDING DOOR
26	1000mm	2000mm	1	DOUBLE SLIDING DOOR
27	1000mm	2000mm	1	DOUBLE SLIDING DOOR
28	1000mm	2000mm	1	DOUBLE SLIDING DOOR
29	1000mm	2000mm	1	DOUBLE SLIDING DOOR
30	1000mm	2000mm	1	DOUBLE SLIDING DOOR
31	1000mm	2000mm	1	DOUBLE SLIDING DOOR
32	1000mm	2000mm	1	DOUBLE SLIDING DOOR
33	1000mm	2000mm	1	DOUBLE SLIDING DOOR
34	1000mm	2000mm	1	DOUBLE SLIDING DOOR
35	1000mm	2000mm	1	DOUBLE SLIDING DOOR
36	1000mm	2000mm	1	DOUBLE SLIDING DOOR
37	1000mm	2000mm	1	DOUBLE SLIDING DOOR
38	1000mm	2000mm	1	DOUBLE SLIDING DOOR
39	1000mm	2000mm	1	DOUBLE SLIDING DOOR
40	1000mm	2000mm	1	DOUBLE SLIDING DOOR
41	1000mm	2000mm	1	DOUBLE SLIDING DOOR
42	1000mm	2000mm	1	DOUBLE SLIDING DOOR
43	1000mm	2000mm	1	DOUBLE SLIDING DOOR
44	1000mm	2000mm	1	DOUBLE SLIDING DOOR
45	1000mm	2000mm	1	DOUBLE SLIDING DOOR
46	1000mm	2000mm	1	DOUBLE SLIDING DOOR
47	1000mm	2000mm	1	DOUBLE SLIDING DOOR
48	1000mm	2000mm	1	DOUBLE SLIDING DOOR
49	1000mm	2000mm	1	DOUBLE SLIDING DOOR
50	1000mm	2000mm	1	DOUBLE SLIDING DOOR
51	1000mm	2000mm	1	DOUBLE SLIDING DOOR
52	1000mm	2000mm	1	DOUBLE SLIDING DOOR
53	1000mm	2000mm	1	DOUBLE SLIDING DOOR
54	1000mm	2000mm	1	DOUBLE SLIDING DOOR
55	1000mm	2000mm	1	DOUBLE SLIDING DOOR
56	1000mm	2000mm	1	DOUBLE SLIDING DOOR
57	1000mm	2000mm	1	DOUBLE SLIDING DOOR
58	1000mm	2000mm	1	DOUBLE SLIDING DOOR
59	1000mm	2000mm	1	DOUBLE SLIDING DOOR
60	1000mm	2000mm	1	DOUBLE SLIDING DOOR
61	1000mm	2000mm	1	DOUBLE SLIDING DOOR
62	1000mm	2000mm	1	DOUBLE SLIDING DOOR
63	1000mm	2000mm	1	DOUBLE SLIDING DOOR
64	1000mm	2000mm	1	DOUBLE SLIDING DOOR
65	1000mm	2000mm	1	DOUBLE SLIDING DOOR
66	1000mm	2000mm	1	DOUBLE SLIDING DOOR
67	1000mm	2000mm	1	DOUBLE SLIDING DOOR
68	1000mm	2000mm	1	DOUBLE SLIDING DOOR
69	1000mm	2000mm	1	DOUBLE SLIDING DOOR
70	1000mm	2000mm	1	DOUBLE SLIDING DOOR
71	1000mm	2000mm	1	DOUBLE SLIDING DOOR
72	1000mm	2000mm	1	DOUBLE SLIDING DOOR
73	1000mm	2000mm	1	DOUBLE SLIDING DOOR
74	1000mm	2000mm	1	DOUBLE SLIDING DOOR
75	1000mm	2000mm	1	DOUBLE SLIDING DOOR
76	1000mm	2000mm	1	DOUBLE SLIDING DOOR
77	1000mm	2000mm	1	DOUBLE SLIDING DOOR
78	1000mm	2000mm	1	DOUBLE SLIDING DOOR
79	1000mm	2000mm	1	DOUBLE SLIDING DOOR
80	1000mm	2000mm	1	DOUBLE SLIDING DOOR
81	1000mm	2000mm	1	DOUBLE SLIDING DOOR
82	1000mm	2000mm	1	DOUBLE SLIDING DOOR
83	1000mm	2000mm	1	DOUBLE SLIDING DOOR
84	1000mm	2000mm	1	DOUBLE SLIDING DOOR
85	1000mm	2000mm	1	DOUBLE SLIDING DOOR
86	1000mm	2000mm	1	DOUBLE SLIDING DOOR
87	1000mm	2000mm	1	DOUBLE SLIDING DOOR
88	1000mm	2000mm	1	DOUBLE SLIDING DOOR
89	1000mm	2000mm	1	DOUBLE SLIDING DOOR
90	1000mm	2000mm	1	DOUBLE SLIDING DOOR
91	1000mm	2000mm	1	DOUBLE SLIDING DOOR
92	1000mm	2000mm	1	DOUBLE SLIDING DOOR
93	1000mm	2000mm	1	DOUBLE SLIDING DOOR
94	1000mm	2000mm	1	DOUBLE SLIDING DOOR
95	1000mm	2000mm	1	DOUBLE SLIDING DOOR
96	1000mm	2000mm	1	DOUBLE SLIDING DOOR
97	1000mm	2000mm	1	DOUBLE SLIDING DOOR
98	1000mm	2000mm	1	DOUBLE SLIDING DOOR
99	1000mm	2000mm	1	DOUBLE SLIDING DOOR
100	1000mm	2000mm	1	DOUBLE SLIDING DOOR




CONCRETE FINIS

BLOCK FINIS

GROUND PLAN

SCALE: 1:200


FLOOR AREA = 5385sqm



Architect: **Standard Design**
 Project: **EMERGENCY BLOCK**
 Location: **MEVA BUILDING, P.O. BOX 1923, 41185 SOBOONA**
 Date: **NOVEMBER 2017**
 Scale: **1:200**
 Drawing No: **01**

Client: **MEVA BUILDING, P.O. BOX 1923, 41185 SOBOONA**
 Architect: **Standard Design**
 Project: **EMERGENCY BLOCK**
 Location: **MEVA BUILDING, P.O. BOX 1923, 41185 SOBOONA**
 Date: **NOVEMBER 2017**
 Scale: **1:200**
 Drawing No: **01**

PROJECT INFO	
Project Name	EMERGENCY BLOCK
Client	MEVA BUILDING, P.O. BOX 1923, 41185 SOBOONA
Location	MEVA BUILDING, P.O. BOX 1923, 41185 SOBOONA
Scale	1:200
Drawing No	01
Date	NOVEMBER 2017




ROOF PLAN - LEVEL 01
 SCALE: 1:200
 ROOF AREA = 830sqm


Drawing Number: _____
 Project Name: _____
 Client: _____
 Date: _____
 Scale: _____
 Drawing Title: _____
 Drawing No.: _____
 Drawing Date: _____
 Drawing Status: _____
 Drawing Author: _____
 Drawing Checker: _____
 Drawing Approver: _____

Client: _____
 Project Name: _____
 Client Address: _____
 Client Contact: _____
 Client Phone: _____
 Client Email: _____
 Project Location: _____
 Project Start Date: _____
 Project End Date: _____
 Project Status: _____
 Project Manager: _____
 Project Engineer: _____
 Project Designer: _____

Drawing Title	
EMERGENCY BLOCK	
Roof Plan - Level 01	
Scale: 1:200	
Author: _____	
Checked: _____	
Date: _____	
Sheet No. _____	
Total Sheets _____	



SECTION XI: XI



SECTION X2: X2
SCALE: 1:100

Structural Section
 Prepared by: **EMERGENCY BLOCK**
 Drawing No: **EMERGENCY BLOCK**
 Date: **2018**

Client:
**PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND LOCAL GOVERNMENTS,
 MWATA BUILDING, P.O. BOX 1923, 41 685 DODOMA**

Project:		STANDARD DESIGN FOR COURSE, LEVEL HOSPITALS IN TANZANIA	
Scale:	1:100	Scale:	1:100
Author:	EMERGENCY BLOCK	Author:	EMERGENCY BLOCK
Check:	EMERGENCY BLOCK	Check:	EMERGENCY BLOCK
Drawn by:	EMERGENCY BLOCK	Drawn by:	EMERGENCY BLOCK
Approved by:	EMERGENCY BLOCK	Approved by:	EMERGENCY BLOCK



SECTION
SCALE 1:100

SECTION X3:X3

Architect: **STANDARD DESIGN**
 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.

CLIENT: **HOSPITALS DEPARTMENT, MINISTRY OF HEALTH, TANZANIA**
 PROJECT: **HOSPITALS DEPARTMENT, MINISTRY OF HEALTH, TANZANIA**
 ADDRESS: **HOSPITALS DEPARTMENT, MINISTRY OF HEALTH, TANZANIA**

EMERGENCY BLOCK	
Section	EMD ANTI
Scale	1:100
Drawn by	EMD ANTI
Checked by	EMD ANTI
Approved by	EMD ANTI



FRONT ELEVATION



REAR ELEVATION

ELEVATIONS

SCALE: 1:100

Building location: P.O. Box 13275, Dar es Salaam, Tanzania.
 Client: Ministry of Health, Dar es Salaam, Tanzania.
 Date: 1995.
 Project: Emergency Block, P.O. Box 13275, Dar es Salaam, Tanzania.

Architect: STANBACQ DESIGN FOR COUNCIL LEVEL HOSPITALS IN TANZANIA

Client: PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND LOCAL GOVERNMENTS, DAR ES SALAAM, TANZANIA.

Project: STANBACQ DESIGN FOR COUNCIL LEVEL HOSPITALS IN TANZANIA

EMERGENCY BLOCK

Elevations

NOVEMBER 1995

END A18

Scale: 1:100



RIGHT SIDE ELEVATION



ELEVATIONS
SCALE: 1:100

LEFT SIDE ELEVATION

Planning Division
Planning and Design Department
Ministry of Health, Government of Tanzania
Dar es Salaam
P.O. Box 128
Dar es Salaam
Tanzania


Architects: Owen, Bly and Associates Inc.
200 West 12th Street
New York, NY 10011
Tel: (212) 921-1888
Fax: (212) 921-1889

Client:
PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND LOCAL GOVERNMENTS,
MWAHA BUILDING, P.O. BOX 1923, 41195 DODOMA

Project:
STANDARD DESIGN FOR COUNCIL LEVEL HOSPITALS IN TANZANIA

Drawing Title:
EMERGENCY BLOCK
Elevation

Design No.	MD/MS/001	EMD A/01
Scale	1:200	
Sheet No.	343	



Foundation Plan

NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with $f_{cu} = 25N/mm^2$ at 28 days of age
4. Main reinforcement shall be high tensile steel with $f_y = 420N/mm^2$
5. Nominal cover to the reinforcements:
 - a) Foundation Column
 - b) Column Stirrs
 - c) Beam Stirrs
 - d) Slab Stirrs

MINISTRY OF HEALTH, COMMUNITY DEVELOPMENT, GENDER, ELDERLY AND CHILDREN




(In Collaboration with)

PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT:
PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT:
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE:
EMERGENCY MEDICAL DEPARTMENT (EMD)

Designed by:	Eng. A. N. Z.
Drawn by:	Eng. A. M. A.
Checked by:	Eng. E. W.
Approved by:	
Date:	2021
Drawing No.:	EMD/S.101
Sheet:	01



Foundation Details

NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with $f_{yk} \geq 250 \text{ N/mm}^2$ at 28 days of age
4. All reinforcement shall be high tensile steel with $f_y \geq 460 \text{ N/mm}^2$
5. Nominal cover to the reinforcement:
 - a) Foundation 50mm
 - b) Column 25mm
 - c) Beam 20mm
 - d) Slab 25mm


MINISTRY OF HEALTH/DOMINANT DEVELOPMENT/RENDEK, ELDERLY AND CHILDREN

In Collaboration with
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT
PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE
EMERGENCY MEDICAL DEPARTMENT (EMD)

Designed by:	Eng. A.M.A
Drawn by:	Eng. A.M.A
Checked by:	ENO. EW
Approved by:	
Date:	2021
Drawing No:	EMD/S.102
Sheet:	01
Scale:	



NOTE:

1. All dimensions are in mm unless otherwise specified
2. All drawings as staff be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with 20M reinforcement at 20 days of age
4. Main reinforcements shall be top bundle spaced with by = 400mm/100mm nominal cover to the reinforcement
5.
 - a) Foundation System
 - b) Column System
 - c) Slab System
 - d) Stair System

MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT, RENDER, ILDERNY AND CHILDREN

In Collaboration with


PREPONENTS OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT
PREPONENTS OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE
EMERGENCY MEDICAL DEPARTMENT (EMU)

Designed by	Eng. A.M.A
Drawn by	Eng. A.M.A
Checked by	Eng. E.W
Approved by	
Date	2024
Drawing No.	EMD/S.100
	Sheet
	01

Plinth Beam Layout Plan



NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with concrete strength at 28 days of age
4. Main reinforcements shall be high tensile steel with fy = 460N/mm²
5. Member cover to the reinforcement:
 - a) Foundation column by Column Section
 - b) Beam Slab by Slab Section
 - c) Other Section

MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT/ENHANCING ELDERLY AND CHILDREN


in Collaboration with

REGIONS/STATE OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT


PROJECT: PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT: PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE: EMERGENCY MEDICAL DEPARTMENT (EMD)

Designed by:	Eng. A.M.A
Drawn by:	Eng. A.M.A
Checked by:	Eng. E.H
Approved by:	
Date:	2021
Drawing No. EMD/9.104	Sheet 01
Scale:	Sheet



Slab Reinforcement 2: Slabs Layout



Slab Reinforcement 3: Slabs Layout

NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with $f_{cu}=27N/mm^2$ at 28 days of age
4. Main reinforcements shall be high tensile steel with $f_y = 452N/mm^2$
5. Member cover to the reinforcement:
 - a) Foundation column
 - b) Column 25mm
 - c) Beam 25mm
 - d) Slab 20mm

MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT/GENDER, ELDERLY AND CHILDREN


In Collaboration with
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT:
PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT:

PRESIDENT'S OFFICE REGIONAL ADMINISTRATIVE AND LOCAL GOVERNMENT
DRAVING
GITEBEHCF MEDICAL DEPARTMENT (EMO)

Designed by:	ENG. A.M.A.
Drawn by:	ENG. A.M.A.
Checked by:	ENG. LAB
Approved by:	
Date:	2021
Scale:	Scale
Drawing No.:	EMDIS.105
Sheet:	01



Front Slab Beams Details

NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with $f_{ck}=25N/mm^2$ at 28 days of age
4. Main reinforcements shall be high tensile steel with $f_y=400N/mm^2$
5. Neutral layer is the reinforcement:
 - a) Foundation 50mm
 - b) Column 35mm
 - c) Beam 25mm
 - d) Slab 25mm

MINISTRY OF HEALTH, COMMUNITY DEVELOPMENT, RENEWAL AND CHILDREN

By Collaboration with



REGIONS OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT: PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
 DRAWING TITLE: EMERGENCY MEDICAL DEPARTMENT (EMD)

Designed by:	Eng. A.M.A
Drawn by:	Eng. A.M.A
Checked by:	Eng. E.M
Approved by:	
Date:	2021
Drawing No.:	EMD/108
Scale:	Sheet
	01

Ring Beam Layout Plan



NOTE:

1. All dimensions are in mm unless otherwise specified.
2. All dimensions shall be referred to the structural engineer.
3. Reinforced concrete shall be of grade 25 with $f_{ck}=25N/mm^2$ at 28 days of age.
4. Main reinforcements shall be high tensile steel with $f_y = 460N/mm^2$.
5. Minimal cover to the reinforcements:
 - a) Foundation 50mm
 - b) Column 25mm
 - c) Beam 25mm
 - d) Slab 25mm

MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT/ASD&E, ELDERLY AND CHILDREN






In Collaboration with

PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

PROJECT
PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE
EMERGENCY MEDICAL DEPARTMENT (EMU)

Designed by:	Eng. A.M.A
Drawn by:	Eng. A.M.A
Checked by:	Eng. S.W
Approved by:	
Date:	2021
Scale:	Scale
Drawing No.:	EMDIS.107
Sheet:	91



NOTE:

1. All dimensions are in mm unless otherwise specified
2. All discrepancies shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with reinforcement at 28 days of age
4. When reinforcements shall be high tensile steel with fy = 460N/mm²
5. Technical cover to the reinforcement:
 - a) Foundation 50mm
 - b) Column 25mm
 - c) Beam 25mm
 - d) Slab 25mm


MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT/ENGINEER, ELDERLY AND CHILDREY
In Collaboration with

PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT PROJECT

PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT
PRESIDENT'S OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE
EMERGENCY MEDICAL DEPARTMENT

Designed by	Eng. A.M.A
Drawn by	Eng. A.M.A
Checked by	Eng. E.W
Approved by	
Date	2021
Sheet	01
Drawing No.	SH/S.108



NOTE:

1. All dimensions are in mm unless otherwise specified
2. All dimensions shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with four-strength at 20 days of age
4. When reinforcement shall be high tensile steel with a yield strength of 460N/mm²
5. Normal cover to the reinforcement:
 - a) Foundation 50mm
 - b) Column 25mm
 - c) Slab 25mm
 - d) Beam 25mm

MINISTRY OF HEALTH/COMMUNITY DEVELOPMENT/OLDER, ELDERLY AND CHILDREN

In Collaboration with

PRESIDENTS OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT PROJECT

PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT:


PRESIDENTS OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT

DRAWING TITLE

PHARMACY MEDICAL EQUIPMENT

Designed by	Eng. A.M.A
Drawn by	Eng. A.M.A
Checked by	Eng. E.W.
Approved by	
Date	2021
Scale	Scale
Drawing No	Sheet
SHS-110	02

Roof Construction Details



NOTE:

1. All dimensions are in mm unless otherwise specified
2. All descriptions shall be referred to the structural engineer
3. Reinforced concrete shall be of grade 25 with 50-cm spacing at 23 days of age
4. Main reinforcements shall be high tensile steel with fy = 482/570N/mm²
5. Nominal cover to the reinforcement:
 - a) Foundation form
 - b) Column 50mm
 - c) Beam 25mm
 - d) Slab 25mm

MINISTRY OF HEALTH COMMUNITY DEVELOPMENT/ADULT, ELDERLY AND CHILDREN

In Collaboration with PARASITIC OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT


PROJECT
PROPOSED STANDARD DRAWINGS FOR COUNCIL HOSPITALS IN TANZANIA

CLIENT

PARASITIC OFFICE REGIONAL ADMINISTRATION AND LOCAL GOVERNMENT
DRAWING TITLE
EMERGENCY MEDICAL DEPARTMENT

Designed by	Eng. A.M.A.
Drawn by	Eng. A.M.A.
Checked by	Eng. F.W.
Approved by:	
Date	2021
Scale	Scale

Drawing No. EMP/05-111 Sheet 01



KEY

	WATER SUPPLY
	DRAINAGE
	KITCHEN
	DAILY URINE

Building Section:
 Planning and Policy Department
 Ministry of Health, Community Development,
 Gender Equality and Children
 University of Dar es Salaam
 College of Humanities and Social Science 11th
 Building, P.O. Box 263,
 Dar es Salaam

In Collaboration with

Financial Officer, Regional Administration
 and Local Government
 Kigoma Building
 P.O. Box 1503
 41160 Dar es Salaam

Date:

PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND
 LOCAL GOVERNMENT, KIGOMA BUILDING,
 P.O. BOX 1503, DAR ES SALAAM

Project:

STANDARD DESIGN FOR COUNCIL LEVEL HOSPITALS IN TANZANIA

Client's Job:
EMERGENCY MEDICAL DEPARTMENT
 WATER SUPPLY AND DRAINAGE

Number of Floors	2nd FLOOR	EMERGENCY
Capacity	400	
Year of Construction	2011	1:500



Building Section
 Planning and Policy Department
 Ministry of Health, Community Development,
 Gender Equality and Children,
 University of Dodoma
 College of Universities and Social Science 11th
 Building, P.O. Box 743,
 46002 Dodoma

In Collaboration with

President's Office, Regional Administration
 and Local Government,
 Mkwinda Building
 P.O. Box 1023,
 41102 Dodoma

Client

PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND
 LOCAL GOVERNMENT, MKWINDA BUILDING,
 P.O. BOX 1023, 41102 DODOMA

Project

STRATEGIC DESIGN FOR COUNCIL LEVEL HOSPITALS IN TANZANIA

Contractor

EMERGENCY MEDICAL DEPARTMENT
 SHOWING VIEW WATER SUPPLY

Reference	Scale	Sheet
001	1:500	EMERGENCY MEDICAL DEPARTMENT
002	1:100	
003	1:50	



KEY

	DRAINAGE
	MANHOLE
	GULLY TRAP

Planning Section
 Planning and Policy Department
 Ministry of Health, Community Development,
 Gender Equality and Children
 University of Dar es Salaam
 College of Humanities and Social Science 17th
 Building, P.O. Box 745,
 Dar es Salaam

In Collaboration with

President's Office, Regional Administration
 and Local Government
 Region 4 Subreg
 P.O. Box 1928
 41198 Dodoma

Date:

PRESIDENT'S OFFICE, REGIONAL ADMINISTRATION AND
 LOCAL GOVERNMENT, MWAJUMBA BUILDING,
 P.O. BOX 1928, 41198 DODOMA

Project:

STANDARD DESIGN FOR COUNCIL LEVEL WASTEWATER TREATMENT

Drawing title
**EMERGENCY MEDICAL DEPARTMENT
 ISOMETRIC VIEW WASTE WATER COLLECTION
 SYSTEM**

Figure number		
Sheet	504/2023	EMEMD-1
Drawn by	AKS	
Checked by	AK	2024 1/28



KEY

 Dual Face Plate
  Data Cabinet


Building Section
 Policy and Planning Department
 Ministry of Health, Community Development,
 Gender, Elderly and Children
 8 Gamora Maschal Avenue
 P.O. Box 9033, Dar es Salaam
 Tel: +25522234000/5
 Fax: +255222113391

Approved	NO	Description	Date

CLIENT -
PRESIDENT'S OFFICE
PROJECT -
PROPOSED COUNCIL HOSPITAL

LOCAL AREA NETWORK -ACT
EMD BLOCK

Project No
 Date 7 NOV 2021
 Drawn by HM
 Checked by HM
 Scale 1:100



KEY

 Dual Face Plate
  Data Cabinet

Building Section
 Policy and Planning Department,
 Ministry of Health, Community Development,
 Gender, Elderly and Children,
 6 Senora Marinel Avenue,
 P. O. Box 9083, Qui es Sultan,
 Tel: +2552223+0005
 Fax: +255222137581

Approved	NO	Description	Date	CLIENT - PRESIDENTS OFFICE PROJECT - PROPOSED COUNCIL HOSPITAL	Project No Date: 7 NOV. 2021 Drawn by: HM Checked by: HM
					Scale 1:100

LOCAL AREA NETWORK - ICT

EMD BLOCK

SECTION VIII : SPECIFICATIONS

1.0 EXCAVATION AND EARTHWORK

1.1 Nature of excavation

The contractor/Project Engineer must ascertain for him the nature of the material to be excavated and price work accordingly as no allowance will be made beyond the contract sum of any alleged ignorance in this respect.

1.2 Excavations generally

Excavations have been measured from the drawings including the Engineer's site plan showing existing contours. It is the responsibility of the contractor/Project Engineer to check the commencing levels prior to commencing the work as no extra payment will be made in respect of any alleged excavations carried out due to the commencing levels being above that shown upon the drawings without the prior written agreement of the Structural Engineer prior to commencement of excavation.

1.3 Site clearance

The contractor shall clear the construction areas within the site of all bushes, roots, boulders, natural obstructions, rubbish and any other natural or artificial obstructions, which would interfere with construction of buildings, roads, paths and drains.

1.4 Over-site excavation

Excavated material suitable for back-filling around foundations and for making up levels under roads, floors etc., is to be kept separate from soil spoil heaps and to be re-used as directed or spread and levelled on the site at the end of excavation operations when found to be surplus. The amount of any such disposal will be measured on site by the Quantity Surveyor. Vegetable soil is not to be used for back filling around foundations.

1.5 Excavation for foundations and structures

Excavations for foundations and the reinforced concrete structure shall be to the widths, depths and levels to accommodate the structure shown on the drawings. Working space has been allowed for in the measurement of excavation quantities in accordance with the rules of measurement laid down elsewhere in these bills, namely 1.00m from the face of any work which required formwork over 1m deep below the starting level of excavation and 0.30m from the face of any work which requires formwork not exceeding 1m deep below starting level of excavation.

Generally formwork has not been measured for plain concrete foundations or column bases and, therefore, excavations for these have been measured, net. Formwork has been measured to reinforced concrete foundation and column bases and all faces of columns and walls and working space excavation has been measured and included accordingly. Adjustments to excavations widths as measured will therefore be made only in the case of the Structural Engineer

ordering the addition of formwork to plain concrete foundations etc., or the omission of formwork to reinforced concrete foundations or column bases. Ordinary use of planking and strutting along foundations to prevent earth falls and to save concrete will not be considered as formwork.

1.6 Inspection

When the excavations have been made to the sizes and depths required from the drawings, the Structural Engineer shall be called to the site immediately for an inspection, and upon approval the Contractor shall proceed with the work to prevent rainwater or other surface water draining into the foundations. The excavations are to be left open until any variation in depth has been measured and agreed.

1.7 Excavation below required depths

Should any excavation be made below the levels or lines shown on the drawings or otherwise required by the Structural Engineer, the contractor must fill up the resultant over-excavation to the proper levels or lines with concrete nominal mix (1:4:8) at his own expense (see "concrete work").

1.8 Filling

The fill shall be clean, selected coarse sand or gravel. It should be taken from borrow pits if the soil on the site is found to contain too much fines and to have too low plasticity limit to be used as fill.

The fill shall be deposited in horizontal layers of max. 200mm Thickness. As soon as possible after the fill is laid out, it should be compacted in min. three passes of a vibratory-roller and/or vibrating-plate compactor. The equipment to be used must be approved by the Engineer.

At each area (control area) of 500m²-compacted fill, three field density tests (e.g. by the sand-replacement method) should be taken randomly.

The Control area to be accepted if all three test results are above 97% of the max. Density as determined at a homogenous mixing of all three samples by the Standard Proctor Method. Otherwise, repeat the test, each time with three new samples until the above requirement is met or re-compact and test again.

1.9 Return, fill in and ram

Return, fill in and ram suitable filling material as described above around foundations and other concrete structure in layers not exceeding 150mm thick and carefully ram and consolidate with power rammer. No filling in shall be executed until concrete foundations etc., have been inspected and approved by the Structural Engineer.

Regardless of the means of back filling and compaction adopted, the contractor is responsible not only for the standard of the work but also for any possible damage of the permanent work or adjacent structure.

1.10 Levelling

No item is measured for levelling and consolidating ground and rates for excavation must include for levelling and preparing the ground for concrete or other works including ramming or rolling.

1.11 Soil sterilisation

Anti-termite treatment is to be carried out by an approved specialist firm who will be required, upon completion of the soil sterilisation, to furnish a written guarantee qualifying the following: -

That the chemicals applied comply with the requirements specified herein for chemical concentration and rates of application.

That the treatment will remain effective against termite infestation for a period of five years.

The free re-treatment by the firm of any areas showing signs of infestation before the expiry of the five year period.

The chemicals used shall be one of the following: -

- i) Gamalin 0.5% applied in oil solution or water emulsion.
- ii) Benzene hexachloride, 0.8% of gamma isomer applied in oil solution or water emulsion.
- iii) Chlordane 1.0% applied in solution or water emulsion.
- iv) Dieldrin 0.5% applied in oil solution or water emulsion.
- v) Lindane; 0.8% in oil solution or water emulsion
- vi) Pentachlorophenol; 5% in oil solution.
- vii) Trichlorobenzene: 1 part to 3 parts oil.

Some of the chemicals listed above are toxic to animal and plant life and must therefore, be applied only with caution by an experienced person. Where individual water supply systems are proposed precautions must be taken to prevent in filtering and endangering the water supply. Treatment shall not be made when a soil of fill is excessively wet or immediately after heavy rain.

Precautions must also be taken to prevent disturbance of the treatment by animals or human contact with the treated soil. The treated area is to be covered as quickly as possible after treatment.

The rate of application is to be 5 litres per square metre and the areas measured include those under floor and round wall and column foundations.

The contractor shall notify the structural engineer in sufficient time before the filling of foundation trenches and laying of concrete floor bed in order that the Architect/Engineer may nominate a specialist firm to execute the soil sterilisation.

Any additional costs caused by the contractor not rendering sufficient prior notice to the Architect/Engineer will be borne entirely by the Contractor.

1.12 Disposal of surplus excavated material

Surplus excavated material will be carted away from the vicinity of the walls and deposited, spread and levelled on areas to be allocated by the Structural Engineer, reasonably adjacent to the site.

1.13 Disposal of water

The contractor shall keep the excavations free from standing water and silt (or excavated material softened by water) and he shall include for the cost of pumping, construction of temporary drains; soak-way pits, etc., as deemed necessary to achieve this. An item has been included for this in the Bills in each relevant section. The cost of pumping to dispose of any spring or running water has been covered by a Provisional Sum. If spring or running water is encountered the cost of any pumping ordered by the Structural Engineer will be paid for in accordance with the Dayworks schedule.

1.14 Planking and strutting

Sides of all excavations must be supported in order to prevent falls from or collapse of the earth face. The "Planking and Strutting" is deemed to include any method or methods, which the contractor elects to adopt to uphold, protect and maintain the sides of excavations. The contractor will be responsible for any consequences of his failure in this respect including clearing away fallen materials and any extra concrete or other works including formwork ordered by the Structural Engineer due to such failure. An item has been included in these Bills in each relevant section.

1.15 Hardcore

Hardcore shall be hard crushed stone to pass a 100mm ring in all directions. No sand, quarry dust or fine material will be permitted. All hardcore beds shall be topped with a layer of fine stone or aggregates minimum size 12mm to fill the voids on the surface to receive concrete beds. Rates for hardcore shall include for levelling or finishing or laying to falls and consolidating by rolling as described for "Filling" above.

2.0 CONCRETE WORK

2.1 Materials and workmanship generally

The recommendations of the recent British Standard Codes of Practice BS 8110 for the Structural use of reinforced concrete in buildings shall be deemed to be incorporated in these preamble clauses unless otherwise specifically stated.

2.2. Materials generally

All materials to be used in the works shall conform as to quality and description as specified hereunder and shall be equal to approved samples. In particular no materials shall be used until approved samples shall be supplied to the Consulting Engineer for approval at least one week before ordering in bulk and delivery to the site. Any material delivered to the site, which has not been previously approved by the Structural Engineer shall be the Contractor's liability. All materials shall be transported, handled and stored on site so as to preclude damage deterioration or contamination. All condemned materials are to be removed from the site within 24 hours.

2.3 Cement

The cement, unless otherwise specified on the drawings shall be Ordinary Portland Cement of approved manufacture, delivered in the manufacturer's bags and shall comply in all respects with the requirements of the latest British Standard 12. The consignments of cement shall be delivered in sealed bags and shall be stored on the site so as to be used in the order in which they are delivered. The structural engineer shall have the right to take samples for testing in accordance with BS. 12 and the contractor are to obtain current certificates of test from the manufacturer prior to bulk deliveries. Under no circumstances is High Alumina Cement to be used.

Rapid hardening cement may be used in lieu of ordinary Portland cement only with the prior approval of the Architect/Engineer or Engineer, provided that all conditions applying to its use are strictly observed. Any additional expenses in connection with the use of such cement shall be borne by the Contractor.

2.4 Aggregate generally

All aggregate shall be from approved reputable sources and shall be strong, hard, durable or limited porosity, free from dust, soft materials, earth or other extraneous matter, and washed and / or screened by the Contractor if so required by the Structural Engineer. Samples shall be provided as often as called upon by the Structural Engineer for testing in accordance with BS. 882. Normal aggregates will have particle densities of greater than 2000 Kg / m³ but not exceeding 3,000 Kg/ m³. Only approved materials shall be used.

Graded samples of all types of aggregate shall, after approval, be kept on site behind glass for visual checking of subsequent deliveries for grading, shape and where applicable, colour. Aggregate shall be stored on site on paved areas with

divisions between each type of aggregate, and shall be used in the order in which they are received on site. No aggregate shall be stored directly on the ground.

2.5 Fine Aggregate

The Contractor shall ensure that the grading of fine aggregate shall be such that not more than 10% by weight shall exceed 5mm in size and not more than 10% by weight shall pass a sieve BS. No. 100. Between these limits the grading shall conform to the grading for either zone, 1, 2 or 3 (B.S.882).

2.6 Coarse aggregate

Coarse aggregate shall be clean, well-graded crushed granite stone or other equal and approved stone from an approved quarry and washed if required by the Structural Engineer. The pieces shall be angular or rounded in shape and shall have granular or crystalline or smooth (but not glassy) non-powdery surface. Flakey and laminated pieces, mica and shale shall only be present in such quantities as not to affect adversely the strength and durability of the concrete.

The four nominal aggregate sizes shall be 40mm (1½"); 20mm (¾"); 10mm (3/8"); 6mm (¼"); and the grading when analysed as described in BS. 812 shall be within the limits given in BS. 882. Structural Engineer will specify sizes of aggregates to be used in specific areas. For most work 20 mm maximum size aggregates will be used. The nominal maximum size of coarse aggregates should be not greater than ¼ of the minimum thickness of concrete section or element.

2.7 Water

Water used for mixing of concrete, washing out of shuttering and similar purpose shall be clean, fresh and free from organic impurities in amounts likely to impair the quality of the concrete and should comply to requirements of BS 5328 and BS 3148:1980 "Methods of test for water for making concrete".

2.8 Admixtures

Structural Engineer will approve all concrete admixtures after submission of specifications or proprietary brands and relevant trial mix verification at site by Contractor. Admixtures to comply with BS 5075 "Concrete Admixtures".

2.9 Steel reinforcement

Steel for reinforced concrete shall comply with the following specification:-

- i) Mild steel rod reinforcement shall comply with BS. 4449.
- ii) High tensile steel reinforcement shall be either cold worked deformed steel bars of circular octagonal section complying with BS. 4461 or hot rolled deformed high tensile bars having a guaranteed minimum yield stress of 460 N/mm² and other physical qualities in accordance with BS. 4449

- iii) Welded steel fabric reinforcement shall comply with BS. 4483
- iv) BS. 8110, the structural use of reinforced concrete in buildings.

All steel reinforcement shall be supplied by an approved manufacturer; and the contractor may be required to obtain a manufacturer's test certificate in respect of steel reinforcement supplied. In the absence of such a test certificate, the contractor may be required to submit samples to be tested at the contractor's expense in such manner as to comply with BS 8110 requirements.

The steel shall be stored so that it is kept clean and reasonably free from rust.

The placing of all reinforcement shall be checked by the Engineer and in no circumstances is concrete to be deposited around any steel that has not been passed. At least twenty-four hours notice shall be given to the Engineer that reinforcement will be ready for inspection.

2.10 Bending and fixing of reinforcement

All bending, cutting and fixing to be in compliance with the British Standard code of Practice, BS 8110 and BS 4466 Bending schedules are incorporated in the contract drawings.

The number, size, form and position of all reinforcement shall unless otherwise directed or permitted by the Architect/Engineer, be strictly in accordance with the drawings. Bars shall be of the required lengths, and lapping, except where indicated on the drawings, is not permitted unless approved by the Engineer.

Overall dimensions shall not be exceeded and shall not be less than 6mm below the required dimensions. The sizes of links and the like shall be within tolerance of 3mm under or over the specified dimensions. Any tolerance in the total length of the bar as cut shall be taken up in the end hooks or other approved portions of the bar. The internal radius of the bends at corners of links and the like shall equal half the diameter of the bar embraced by the link.

Laps in bars of random lengths shall be staggered in such a way that no more than 1/3 of bars having same number are to be lapped in the same section.

The steel reinforcement shall be assembled and fixed in the form of a rigid cage. To prevent displacement before or during concreting the bars shall be secured to each other with approved wire. Concrete distance blocks shall, unless otherwise directed, be used between the reinforcement and the bottom and sides of the forms to ensure correct concrete cover to the bars, as specified on the drawings. The specified cover shall be provided and maintained within the specified tolerance.

The minimum clear distance between adjacent bars shall be 25mm horizontally and 25mm vertically. Spacer bars shall be inserted at such intervals that the bars do not perceptibly sag.

Great care must be taken to ensure the correct positioning of beam and column starter bars and to secure projecting bars against displacement both during and after concreting.

At the time of fixing and when concrete is being placed, all reinforcement shall be free from oil, paint, grease excessive dust and scale or any other coating, which would destroy its bond with the concrete.

2.11 Formwork to produce a fair face board finish (wrought formwork)

Formwork described as wrought shall be constructed of or lined with 100mm wide planed boards well cramped together or plywood to leave a fair smooth finish in the exposed concrete face when the shuttering is removed.

2.12 Construction and Movement Joints

The positioning, type and frequency of construction joints are to conform to requirement of BS 8110 and be approved by Engineer. Methods of forming movement joints to follow drawings and the requirements of BS 8110.

2.13 Concrete grades

Only designed concrete mixes complying with BS 5328 shall be used. Concrete must comply with the requirements set out in the following table according to the grade (This is for guidance only)

GRADE	NOMINAL MIX	MAX SIZE OF COARSE AGGREGATE	MAX WATER CEMENT RATIO BY WEIGHT	MINIMUM CRUSHING STRENGTH OF WORKS TEST CUBES (N/mm ²)	
				7 DAYS	28 DAYS
30	1:1:2	20mm	0.50	20	30
25	1:1½:3	20mm	0.55	17	25.5
20	1:2:4	20mm	0.60	14	20
15	1:3:6	25mm	0.60	8	14
10	1:4:8	40mm	0.60	-	10

2.14 Concrete Production, Supervision and Tests

Concrete should be produced in accordance with BS 5328 which requires tests to be made on constituent materials in accordance with relevant British Standards and control tests be made on concrete to ensure compliance with specified requirement. Engineer will in addition approve procedures for placing, compacting, curing and working in hot weather.

Concrete should meet appropriate requirements specified in BS 5328 for

- a) Characteristic compressive strength
- b) Specified mix proportions
- c) Maximum and minimum cement content
- d) Maximum free water/cement ratio
- e) Workability

- f) Air content of concrete
- g) Temperature of fresh concrete
- h) Density of fully compacted concrete.

2.15 Preliminary cube tests

The contractor shall specify the sources from which the aggregate will be obtained and shall deliver at his own cost sufficient materials enable preliminary cube tests to be carried out and approved by the Engineer. The Contractor will be responsible for submitting his proposals for the concrete mix proportions together with aggregate grading curves to the Architect/Engineer for approval and for the payment of the fees of an approved Testing Authority in carrying out the crushing tests. The strength of the preliminary cubes must be a minimum of 33% above those in the above table, which is the minimum works strength.

The approval of any mix by the Engineer will not relieve the contractor of the responsibility for ensuring that all concrete used in the works obtain the minimum works strength shown above.

In proportioning the concrete the quantity of cement shall be determined by weight and the quantities of fine and coarse aggregate by either volume or weight, due allowance being made for the moisture content of the aggregate.

Only sufficient water shall be added to the cement and aggregate during mixing to produce a concrete having sufficient workability to enable it to be well consolidated, to be worked into the corners of the shuttering and around the reinforcement, to give the specified surface finish and to have the specified strength. When a suitable amount of water has been determined the resulting consistency shall be maintained throughout the corresponding parts of the work and the slump test or compaction factor test shall be carried out from time to time to ensure the maintenance of this consistency. In no case should the slump be more than 65mm as determined by the standard slump test nor should the compaction factor be more than 0.87 as determined by the standard compaction factor test as described in BS. 1881.

Should the Contractor wish to use patent, plasticising compounds or other admixes, those shall be approved by the Engineer and be used in accordance with the manufacturer's publications.

2.16 Work cube tests

Work cube tests shall be made throughout the contract. Each cube shall be inscribed with the date of manufacture and identification mark. A record shall be kept for each batch of cubes showing the position in the works which the concrete represents, the date of manufacture, the mixture and slump of the concrete, particulars of the cement and aggregate used, a statement of whether or not the cubes were vibrated and other information relating to the subsequent history of the cubes.

The cube shall be made, cured and tested in accordance with the requirements of BS. 1881 when directed by the Engineer and in his presence or that of the

Approved Testing Authority. A sample of concrete shall be taken at random on eight separate occasions during each of the first 5 days of using that mix.

6/10

Thereafter at least one sample shall be taken on each day any concrete of that particular mix is used. From each sample four cubes shall be made two for testing at 7 days and two for testing at 28 days. The works cube results shall be examined both individually and in consecutive (but not overlapping) sets of four, for which the average and the range of each set are calculated.

The mix proportions shall be modified to increase the strength if, in the first and consecutive (but not overlapping) sets, any of the following conditions are not satisfied:-

- i) Not more than 2 individual results of the 40-cube test should fall below the specified work cube strength.
- ii) No value of the range in any set should exceed 4 times the designed standard deviation.
- iii) Not more than one set should have an average, which is less than the specified strength plus $1\frac{1}{3}$ times the designed standard deviations.
- iv) No value of the average for any set should be less than the specified strength plus the designed standard deviation.

After 10 consecutive sets of results have been obtained the overall average and the standard deviation of the 40 results shall be calculated and any appropriate modifications made. Subsequently, if any of the foregoing conditions are not satisfied, the overall average and the standard deviation of the previous consecutive 40 results, including the non-complying sets, should be calculated and the appropriate steps taken if the overall average strength twice the standard deviation is less than the specified work cube strength.

2.17 Quality control requirements

2.17.1 Supervision

A competent person shall be employed whose duty shall be to supervise all stages in the preparation and placing of the concrete. He shall supervise all tests on the materials and cubes and the maintenance and calibration of mixing and measuring plant. This person shall also be responsible for keeping an accurate record of the dates on which concrete is poured and where. Where the Engineer is not satisfied with the performance of concrete supervisor he shall recommend to the Architect/Engineer for removal from site.

2.17.2 Batching and mixing plant

The quantities of cement and of fine and coarse aggregate shall be determined by weight. The amount of water added shall be measured, allowance being made for the water content of the aggregate. The accuracy of weighing and measuring

equipment shall be 2.1/2%. Measuring equipment for water shall be maintained in a clean serviceable condition.

2.18 Workmanship

2.18.1 Placing of reinforcement

Reinforcement shall be accurately placed and maintained in the position described on the drawings or elsewhere to the entire satisfaction of the Engineer. Bars intended to be in contact at passing points shall be securely wired together with 16 gauge annealed soft iron tying wire.

Binders and the like shall tightly embrace the bars and any slackness or misplacement of bars shall be rectified before the Engineer is called for inspection. Spacers of approved design shall be used for ensuring the correct positioning of the bars and diagonal wiring shall be provided to ensure rigidity of all assembled units of reinforcement. The vertical distance required between successive layers of bars in beams or similar members shall be maintained by the provision of mild steel spacer bars inserted at such intervals that the main bars do not perceptibly sag between spacers. The rates for reinforcement must include for all requisite wiring, spacers and precast concrete blocks to maintain the required spacing and cover. All bars are to be bent in accordance with BS. 4466, 1969.

Cover of concrete to the reinforcement shall be, unless shown otherwise:-

Columns	-	40mm minimum to main bars
Base	-	50mm minimum to main bars
Beams	-	25mm minimum to main bars
Slab	-	15mm minimum to main bars
Wall	-	25mm minimum to main bars
Raft slab	-	100mm minimum to main bars

Splices to future work shall be covered in a manner approved by the Engineer to prevent rusting and deterioration. Before any concreting is carried out the approval of the Engineer as to the correctness of the fixed reinforcement shall be obtained but such approval shall not remove the responsibility for the correctness of the placing from the contractor. During concreting a competent steel fixer shall be in attendance on the concrete gang to make minor adjustments to the position of bars should they become displaced.

2.18.2 Formwork generally

Formwork design and construction should take into account of safety and surface finish required and to conform to requirements of BS 8110 and BS 5975. Dimensional deviations of insitu concrete shall be to limitations set in BS 5606

All formwork and moulds shall be rigidly constructed to accurate shape and dimensions as described on the drawings and to requirement of BS 5975. Timber shall be well seasoned, free from loose knots and be of a kind and thickness that will avoid deflection and warping, remaining true to line and level. Faces in contact with the concrete shall be free from adhering grout, projecting nails, splits

or other defects and shall be coated with an approved mould oil so as to prevent grout adhering to them, care being taken to prevent such coatings from any contact with the reinforcement.

Formwork shall be braced and strutted to prevent deformation under the weight and pressure of the wet concrete, construction loads, winds and other forces. The bottoms of beam boxes shall be erected with an upward camber so as to prevent downward deflection. Maximum tolerances, which will be permitted in the finished concrete work, are to BS 5606 as follows:-

Dimensions less than 3m $\pm 3\text{mm}$

Dimensions between 3m & 15m $\pm 6\text{mm}$

Dimensions over 15m $\pm 10\text{mm}$

Joints in the moulds of formwork shall be carefully made so as to prevent leakage of cement grout and particular care shall be exercised to this respect for moulds in which it is intended to place vibrated concrete. Openings in the formwork for inspection of the inside and for the escape of water used for washing out accumulated debris shall be formed in such a manner that they can effectively be closed before placing the concrete.

Formwork connections and joints shall be constructed so as to permit easy removal of the formwork, but shall be so secured as to retain correct shape under pressure exerted by the wet concrete during placing, vibration, setting and hardening. If any wire ties passing through the concrete or bolts are used, measures shall be taken to prevent rust, stains on the finished work and any holes left by the removal of such ties shall be made good. Formwork shall be provided for top faces of sloping work and anchored to prevent floatation, but this shall apply only where the slope exceeds 15 degrees. The formwork for beams and slabs shall be erected so that the sides of the beams and soffits of the slabs can be removed without disturbing the beam bottoms. Props for an upper storey shall be placed directly over these in the storey immediately below and the lowest prop shall bear upon work sufficiently strong to carry this load.

If formwork of columns; walls and other deep sections is erected to the full heights, one side shall be left open and shall be built up in sections as placing of the concrete proceeds. Before concreting, bolts and fixings shall be in position. Cores and other devices used for the forming of openings, holes, pockets, chases, recesses and other cavities shall be fixed to the formwork and no subsequent holes shall be cut in any concrete without the Architect/Engineer's approval

2.18.3 Mixing of Concrete

All concrete shall be mixed in batch mixing machines Hand mixing shall not be permitted. All mixing machines shall be of the fixed drum types and not smaller in size than 0.40/0.28 CM drum mixers will not be permitted. The mixer shall be of the type equipped with an accurate measuring device designed so that no unauthorised person can tamper with the valve or vary the quantity of water delivered once this has been approved and set. The mixing procedure to be adopted by the Contractor shall be approved by the Architect/Engineer.

Mixing of each shall be approved by the Engineer. Mixing of each batch shall continue until the concrete is uniform in colour and, in any case, for not less than two minutes after all the materials and the water is used in the drum. The entire contents of the drum

shall be discharged before the materials for the succeeding batch are fed into the drum. Upon completion of the day's mixing, the drum shall be thoroughly cleaned free of adhering concrete.

2.18.4 Distribution of Concrete

The concrete shall be distributed from the mixer to the position required by approved means, which do not cause separations or otherwise impair the quality of the concrete. All equipment shall be cleaned before commencing mixing and distribution and be kept free from set concrete. All concrete must be in position and consolidated before the initial set is commenced and the contractor shall ascertain the initial setting time for the brand of cement being used and ensure that his means of distribution are such that it is impossible for concrete to have set prior to placing.

Distribution by means of mortar pane generally will be permitted, but for important large structures such as slabs, large beds and elsewhere instructed by the Engineer the minimum requirements shall be wheelbarrows, ramps and runways over the reinforcement.

2.18.5 Placing of Concrete

Before placing of concrete commences, the formwork shall be examined and any accumulated water and rubbish lying therein shall be removed. The concrete shall be placed as near to its permanent position as is practicable and shall not be worked along the formwork to that position. It shall not be dropped from a height not handled in a manner likely to cause separation of the aggregate or loss of the cement matrix. In columns and other similar members the bottom shall be first filled to a depth of between 150mm and 200mm with a cement mortar consisting of sand, cement and water with the sand and cement in the same proportion as that specified for the general mix in that member. The mortar shall have a consistency such that it will work up the formwork and fill in spaces, which may occur due to close spacing of reinforcement in the splice. This mortar must be placed immediately in advance of the concrete and shall not be allowed to attain its initial set before placing the main concrete for the member. Each layer of concrete, while being placed, shall be consolidated by the approved methods of ramming/ tamping or mechanical vibration so as to form a dense homogeneous material free from honeycombing water and air holes or other blemishes. Concrete shall be placed continuously until completion of the part of the work between the specified construction joints. Approved working joints shall be made whenever stopping of concrete placing occurs. In general, concrete shall be placed in a single operation to the full thickness and depth of slabs, beams and similar members and, in any case, shall be placed in horizontal layers not exceeding 750mm deep in walls, columns and other similar members:-

2.18.6 Vibration

Mechanical vibrators or hand tamping must be used in placing all reinforced concrete work unless the Engineer has approved specially designed mixes and preliminary work cube test results have been obtained without their use. Rates for all reinforced concrete work include for this. Where mechanical vibration is required the contractor shall allow for using two vibrators at any one time.

2.18.7 Working joints

Working joints shall be of an approved shape and placed at right angles to the axis of the member. The contractor shall submit his proposals for the design and position of all joints on a drawing to the Architect/Engineer for his approval well before construction is commenced. The position of day-to-day working joints may be determined so as to meet the requirements of the contractor's concreting programme.

Wherever new concrete is to be placed against concrete that has hardened, the face of the old concrete shall be cut back not less than 20mm and all loose particles removed. The face shall then be wire brushed and thoroughly cleaned with water and then coated with a neat cement grout immediately before placing the concrete shall be well rammed and compacted against the prepared face before the neat cement grout sets.

2.18.8 Protection of Concrete

Newly placed concrete shall be protected by approved means from rains, sun and dry winds, and exposed faces shall be kept moist with polythene sheets or hessian coverings or other approved means for at least 7 days. Under no circumstances shall concrete be worked upon until it has reached a cube strength of 140kg per square centimetre. Immature concrete shall be protected from damage by falling debris excessive loading vibrations, running or standing water, abrasives or other influences likely to impair the quality or strength of the finished work.

2.18.9 Concrete in Excavation.

The length and widths of the excavation shall be as necessary for the proper construction of work below ground and in accordance with the Preambles contained in the section 'Excavation and Earthwork'. Blinding concrete has been measured for the net width required for concrete structure and foundations below ground level. Blinding has not been measured to the extra width, if any required for working space. The depths shall be decided by the Architect/Engineer where these are not given on the drawings. Any obstructions or unusual solids encountered during the excavation shall be reported to the Architect/Engineer and dealt with as then instructed.

2.18.10 Removal of formwork.

The period elapsing between placing the concrete and removing the formwork shall be sufficient to allow the concrete to mature to the extent of being able to maintain its own weight and any constructional and structural loads imposed

without damage. The Architect/Engineer's approval for the removal of the formwork shall be as tabulated below:

Position of Formwork	Minimum striking Time
Vertical sides of wall, columns, beams, etc	2 days
Soffits of beams & slabs (props left)	7 days
Slab and props	14 days
Bottom boards of piles (intermediate support left in)	12 days
Soffits of beams under 6m span	16 days
Additional: Period for each 0.6m span in excess of 6m span with a maximum of 28 days	1 day

The formwork shall be removed in all cases by gradual easing without jarring and the process shall be such that the sharp edges of the concrete are not chipped and spilled away. If the imposition of a load is anticipated, props shall be provided in an approved manner after removal of the formwork and before the imposition of the loads.

2.18.11 Surface finishes

Upon removal of the formwork any honeycombing or damaged surfaces or other imperfections shall be reported to the Architect/Engineer. No surfaces shall be repaired or otherwise treated until an inspection has been carried out by the Architect/Engineer and his instructions or approval to remedial work (if any) have been given or obtained.

Concrete surfaces, which are to be plastered or rendered, are to be hacked or roughened by an approved means to form a key.

Sawn formwork is measured for all surfaces requiring support and subsequently concealed or plastered.

2.19. Precast Concrete

Where precast concrete members are specified, these shall be constructed in moulds of approved design and samples from the moulds shall be approved before quality production of the member is commenced to requirement of BS 8110. Large precast members shall be lifted only at points, which will not damage the member, and if necessary temporary bracing of timber shall be used to case the member until it is in position. Small lintels and other small members may be cast in-situ at no extra cost at the contractor's option. Allowance must in all cases be made for any extra reinforcement to counteract temporary stresses whilst handling, transporting and hoisting precast concrete members. Moulds for precast

units described as finished fair on exposed surfaces shall be lined with plywood or hardboard to leave a fair finish on the exposed concrete face when the mould is removed.

The concrete shall be of the grade specified on the drawings but with maximum aggregate size 12mm and shall be thoroughly vibrated in the moulds and shall not be removed until seven days after placing the concrete.

Care must be taken that no concrete is allowed to become prematurely dry and the fresh concrete must be carefully protected from the rain, sun and wind by means of 'Sisal-kraft' paper, well-wetted sacking, wet sand or other approved means. This protective layer and the concrete itself must be kept continuously wet for at least seven days after the concrete has been placed.

Prices for precast concrete shall include for all moulds, reinforcement as specified, hoisting and fixing in the position required, bedding and pointing as described and temporary props and other necessary supports.

2.20 Sub-contractors work Incorporated in the Structure

It shall be the contractor's responsibility to co-ordinate sub-contractor's and others for incorporating any electrical conduit, plumbing fixtures and pipes, bolt holes, etc., in the concrete members as required and shown on the drawings. The contractor shall submit details of cable and pipe runs to the Architect/Engineer before the work is put in hand and shall have the Architect/Engineer's approval of the layout. No holes or chases shall be cut on concrete without the approval of the Architect/Engineer.

2.21 General

No holes or chases are to be cut in any part of the reinforced concrete construction without first consulting the Architect/Engineer. No part of the reinforcement shall be used for conducting electrical current. Notice must be taken of any appearing on the drawing and not mentioned in these preambles.

2.22 Movements and Separation Joints

Movement joints shall comprise of Bitumen impregnated softboard or similar approved.

Joints topping are to be 'Plastic' or similar approved hot poured rubber bitumen compound. Pointing to vertical joints is to be 'Plastic joint' or similar approved bituminous putty applied with a gun. Joints are to be at least 12mm deep and the gap is to be formed either by raking cut (in the case of expanded polystyrene) or by temporary wooden battens of the required width and 12mm deep.

Rates for the expansion or separation joint shall include all necessary labour and the materials described above, temporary supports and cutting where required to line with concrete surfaces finished to falls. Formwork has been measured as a separate item to one side only of expansion joints.

2.23 Mortise and Pockets

Mortise or pockets for holding down bolts or dowels shall be formed in concrete to the size and shapes shown on the drawings. Mortises shall be formed by the use of expanded polystyrene blocks of the required shapes and sizes carefully and accurately placed and maintained in position whilst the concrete is poured.

Rates for mortises shall include for all necessary templates and raking out and the complete removal of the polystyrene when the concrete has set. No deduction from

concrete quantities have been made for any mortise, pocket or any other void in the concrete of 0.05 cubic metre or less and the Contractor may take this into account when pricing. Grouting up has been measured separately.

3.0 WALLING

3.1 Water

Water shall be as previously specified in 'concrete work.'

3.2 Cement

Cement shall be as previously specified in 'concrete work'.

3.3. Fine Aggregate

Fine aggregate shall be as previously specified in 'concrete work.'

3.4 Coarse Aggregate

Coarse aggregate shall be as previously specified in 'concrete work' and shall comprise aggregate of 6, 10 and 20mm gradings in equal proportions.

3.5 Lime

Hydrate limes for cement/lime mortars shall comply with B.S.890 semi-hydraulic class 'B' calcium limes

3.6 Bricks and Clay blocks

Clay bricks and blocks, solid and hollow, shall comply with B.S.3921: 1974. The Architect/Engineer shall approve the manufacturer and/or supplier of clay bricks and clay blocks

The vertical joints of one course should not be less than a quarter-brick from the vertical joints of the courses above and below.

Where strength is critical, bricks with one frog only should be laid with the frog upwards so that it is automatically flushed with mortar.

3.7 Joints

The joints of brickwork may be finished by one of the following methods.

- i) With a flush joint as the work proceeds this joint being formed of the actual mortar used in bedding the bricks.
- ii) Struck or recessed joint formed in the mortar as the work proceeds when it has gone some way towards setting. Recessed pointing must be even and not vary in depth where not recommended otherwise the recess shall be 6mm deep.
- iii) Joints raked out while mortar is soft and cleaned down and pointed at completion. When the joints are raked out and pointed later the pointing mortar should be of a composition similar to that of the bedding mortar.
- iv) Joints raked out and left as key for plaster or roughcast.

3.8 Concrete Blocks

Solid and hollow concrete blocks for walls comply with BS. 6033/2028 type 'A' except that the recommended mix shall be 1:3:6 cement: fine and coarse aggregate respectively by volume and are to have sharp arises. Blocks are to be manufactured on site in approved block making machines and shall be solid or two cavity hollow types as specified on the drawings. No damaged blocks shall be used in walling and half or other part blocks required to maintain bond shall be cut true and even.

The concrete is to be placed into the moulds in thin layers and shall be properly tamped or vibrated to secure complete consolidation without voids or flaws produce smooth surfaces and sharp straight corners.

Blocks shall be cast on loose pellets and after removal from the moulds shall be carefully stored under for at least 24 hours before the pellets are removed. The blocks shall thereafter be stored under cover for a further seven days protected from the sun and drying of the blocks may commence on the ninth day after manufacture and no blocks may be used within 14 days of their production.

The compressive strength of the type 'A' concrete blocks shall be not less than:-

- Average of 13 blocks 50 kg. per square centimetre (700 lbs. per square inch)
- Lowest individual blocks 40kg. per square centimetre (580 lbs per square inch)

Concrete louvre blocks shall be of an approved type and manufacture. They shall be with inclined faces and have overall size 450 x 150 x 150mm (excluding lip protruding outside the bedding face).

3.9 Fair face work

Walls described as finished with a fair face shall be constructed with blocks selected for their uniformity of size and with a smooth exposed face with no chips, blemished, pinholes or cracks. Walling shall be pointed with a neat flush joint as work proceeds and on completion shall be brushed down and left thoroughly clean.

3.10 Mortar

The mortar used for walling shall be composed of one part of cement to two parts of hydrated lime to nine parts of sand (1:1:6) measured in gauge boxes and thoroughly mixed dry and preferably with an approved mixing platform with water added afterwards until all parts are completely incorporated and brought to a proper consistency and used within the hour. No partially or wholly set mortar will be allowed to be re-used or re-mixed.

3.11 Workmanship

All blocks and stone to be wetted before laying out the top of walling where left off, shall be well wetted before recommencing building, walls to be kept wet three days after building.

All walling to be built true, plumb and level with all perpend vertical and in line and work shall not rise more than 900mm above the adjoining work and all such risings are to be properly raked back.

3.12 Damp proof course

Damp proof course between foundations walls and the oversite concrete slab shall be hessian based bitumen strip to BS. 743 type 5A the same width as the block walls. The damp proof course shall be bedded in cement mortar (1:4) with 150mm-end laps and full width at passings and angles. Damp proof courses are required on all external and internal foundation walls.

4.0 ASPHALT WORK

4.1 Generally

The asphalt work shall be executed complete by an approved specialist sub-contractor.

4.2 Asphalt for tanking

Asphalt for tanking and damp proofing shall be mastic asphalt and shall comply in all respects with BS. 1097 and shall be applied in three coats with 150mm laps on horizontal work and 75mm laps on vertical with a two-coat asphalt fillet at all internal angles.

In laying asphalt in basements the contractor must take the following precautions and his prices must include for these:-

- i) Immediately upon completion the horizontal asphalt must be protected by covering it with a fine concrete screed of not less than 50mm thickness, in order to avoid damage by dumping of steel reinforcement rods, spillage of oil etc.
- ii) The vertical asphalt, the angle fillets and the offsets (if any) must be protected as quickly as possible by the erection of the skin walls or of main structural walls as the case may be.
- iii) In particular piercing the asphalt membrane by driving nails, puncturing the asphalt membrane by reinforcement rods or other materials, using asphalt membrane as a base for strutting and dropping petrol, oil or other solvents particularly from the contractor's plants, upon the asphalt or upon the surrounding area, must be avoided. It is essential that pumping operations be maintained on wet site until protective loading coats and protective walls are complete and fully set.

4.3 Asphalt for paving

Asphalt for paving, roads and footways shall be mastic asphalt and shall comply in all respects with BS. 1446 (natural rock aggregate) and BS. 1447 (limestone aggregate) shall be applied in strict accordance with the Architect/Engineer's (or his representative) specifications and instructions.

4.4. Asphalt for roofing

Asphalt for roofing shall be mastic asphalt and shall comply in all respects with BS. 988 (mastic asphalt for roofing-limestone aggregate) or BS. 1162 (mastic asphalt for roofing-natural rock aggregate) and shall be applied in two coats, to a final thickness of 20mm. The composition of asphalt shall be in accordance with BS. 988 Table III columns. Where roofing is to be used by vehicular traffic for example, car park etc. the asphalt to be used will be as for paving. The laying of the roofing shall be in conformity in with C.P.144 (roof coverings part 2, mastic asphalt) and the covering shall be laid on an insulating membrane of black sheathing to BS. 747 type 4A.

The rates inserted in the bills of quantities for roofing must allow for the cost of the sheathing felt, as it is not measured separately.

4.5 Preparation of surfaces

All surfaces to receive asphalt are to be dry and rough, groove or otherwise prepared and finished to the requirements and to the entire satisfaction of the asphalt sub-contractor and the Architect/Engineer.

4.6 Melting asphalt on site

Asphalt blocks shall be broken into pieces of convenient size and carefully melted in cauldron or mechanically agitated mixers, on the site at a temperature not exceeding 215 C or the Molten material may be delivered to the site in mechanically agitated mixers.

4.7 Dusting of buckets

Buckets used for carrying molten asphalt shall be dusted with a fine inert dust. On no account shall ashes or oil be used for this purpose

4.8 Laying of asphalt

Asphalt shall be laid in bays generally not exceeding 2 metres wide and succeeding coats shall be laid breaking joint. Junctions between bays and fillets shall be properly married, the laid asphalt being heated by the application of the hot material, the whole being worked so that the joints are neatly made. Air pockets and stains on the asphalt will not be permitted and the finished asphalt work shall be not ring hollow over any parts of its surfaces.

Joints in all asphalt work shall be made and complete fusion obtained to make them watertight. Fillets shall be run at all internal angles and at least in two operation

5.0 ROOFING

5.1 Vermiculite lightweight screed

Vermiculite lightweight screed shall be mixed in the proportions of 6 parts by volume of vermiculite Grade 5 to 1 part of Ordinary Portland Cement with approximately 2 parts of clean potable water to give a density of 700 kg. per m³.

Vermiculite screed is to be finished to receive a topping coat of water proofed cement and sand (1:4).

5.2 Roof waterproofing

The waterproofing shall be carried out with cement and sand (1:4) waterproofed with 'Puddle' or other equal and approved waterproofing compound in strict accordance with the manufacturer's printed instructions.

5.3 Bitumen felt roofing

5.3.1 Generally

Bitumen felt roofing shall be executed by a specialist subcontractor to approved by the Architect/Engineer.

5.3.2 Materials

Bitumen felt roofing (or built up roofing) shall be in accordance with BS. 747 (roofing felts). The roofing shall be composed of three layers of single roofing felt of specified quality; weight and make.

5.3.3. Fixing

Bitumen felt roofing shall be carried in accordance with the requirements of CP 144 part 1:1968, (built up bitumen felt). The roof screed must be laid to falls of not less than 1 degree from horizontal and the screed must be thoroughly dried before laying of bituminous is commenced.

The first layer shall be partially bonded to the roof deck with bitumen to allow sufficient easing of vapour pressure. The second layer shall be fully bonded to the first layer with minimum 150mm laps at ends and edges in bitumen. The top layer shall be similarly bonded to the second layer.

5.4. Aluminium roofing

5.4.1 Materials

Aluminium roofing shall be resin coated aluminium roof sheeting manufactured by ALUCO, and shall conform to the requirements of BS 2855 or 3455. The gauge and the surface finish of the sheets shall be as recommended by the manufacturer, in writing, and approved by the Architect/Engineer. All accessories shall be of aluminium alloy.

Whenever trough sheets and heavy trough sheets are used they shall comply with the requirements of BS 3428 type 'A' for trough sheets and type 'B' for heavy trough sheets.

5.4.2 Fixing

The sheets shall be fixed to steel angle or timber purlins with aluminium alloy bolts and nuts. The bolts shall be at least 50mm longer in the shank than the purlin to which they are fixed. All bolts shall have approved washers.

Fixing of the sheet must conform strictly to the printed instructions or otherwise to the requirements of CP 143 part 1 BS 2855.

5.5 Galvanised sheet roofing

5.5.1 Materials

Galvanised sheet roofing shall be corrugated iron as manufactured by GALCO and shall comply with BS. 3083:1959: Hot dipped galvanised corrugated steel sheets for general purposes. In addition to the manufacturer's recommendation. The gauge and the surface finish of the sheets shall be specified and approved by the Architect/Engineer.

Accessories shall comply with BS. 1091: 1963 "Pressed steel gutters, rainwater pipes, fittings and accessories".

5.5.2 Fixing

The sheets shall be fixed to steel angle or timber purlins with roofing nails, bolts and nuts or any other accessory to be approved by the Architect/Engineer.

Fixing of the sheet must conform strictly to the printed instructions or otherwise to the requirements of CP 143 part 2 BS. 2855:1962.

NOTE: ASPHALT FOR ROOFING SEE UNDER TRADE "ASPHALT WORK"

6.0 CARPENTRY

6.1 Timber generally

The timber used for carpentry shall be sound, well conditioned, properly seasoned to suit the particular use and free from defects or combination of defects rendering it unsuitable for the purpose intended.

All timber used structurally shall comply with the relevant requirements of and graded in accordance with the Export of Timber Ordinance (cap. 288); The export and Grading of Timber Rules 1969.

All timber is to be ordered as soon as the Contract is signed and is to be delivered to the site for open stacking for as long as possible before use. All timber will be inspected by the Architect/Engineer upon arrival at the site and if not approved by him shall be removed from the site forthwith. Notwithstanding the Architect/Engineer's approval, any timber incorporated in the Works found to be in any way defective before the expiry of the Defects liability Period shall be removed and replaced at the sole expense of the Contractor.

Timber shall be free from live borer beetle or other insect attack when brought to the site. The Contractor shall be responsible to the end of the Defects Liability Period for executing any work necessary to eradicate insect attack at his own expense including the replacement of timber attacked or suspected of being attacked notwithstanding that the timber may have been inspected already and passed fit for use.

6.2 Moisture content

All timber shall be seasoned to a moisture content; if not otherwise specified of not more than 15% The Contractor must allow for the costs of any kiln drying which may be necessary to obtain this figure.

6.3 Samples and testing

The Architect/Engineer/ engineer shall be entitled to select any samples he may reasonably require of materials or prototype of special construction elements for

the purpose of testing (e.g. for moisture content; identification of species, strength etc)

6.4 Protection

All timber delivered to the site shall be stored under cover clear of the ground and protected from sun and dampness and shall be stored in a satisfactory manner to prevent attack of termite, insects or fungi.

6.5 Softwood

Timber for structural use, including rafters, purlins etc. shall be of Grade II strength and Grade 1 appearance. The softwood shall be a seasoned cypress, cedar pine or podo-carpus, which shall be pressure impregnated with the full cell process as described

below, but the contractor's attention is drawn to the Dayworks Schedule where the basic price of various timber requires pricing, in the event of one of these timbers being selected as an alternative then these basic rates will be used in calculating new rates for the item of carpentry concerned.

6.6. Pressure impregnation

The softwood described as pressure impregnated shall be treated with the "Celcure A" or "Tanolith C" full cell process. Timber must be seasoned to a moisture content not exceeding 25% before being treated. The treatment shall be to the minimum standard of:-

Solution concentration - 2 %

Absorption of preservative - 520 litres per cubic metre

Net dry salt retention -10.4 kg. per cubic metre

After treatment the timber shall be seasoned to the specified moisture content.

Cut ends and faces of timber sawn, drilled and cut after treatment are to be swabbed liberally with approved preservative until saturated, allowed to dry and then treated with a second coat and rates for timber must include for this. Approved preservatives are:-

Atlas A, Brunophen Nr. 2, Cuprinol Clear or Water Repellent Clear Enscle Woodtreat 55.

Hardwood for structural and roof timbers shall be third grade scantlings, strength group E or other suitable and approved durable hardwood.

6.8 Preservative treatment

On delivery to the site all structural hardwood is to be treated with two coats of an approved timber preservative. After fixing, the hardwood is to be touched up as required with approved timber preservative.

The timber preservative shall be coal tar creosote to BS. 144 or other equal and approved applied either by brush or by spraying in accordance with the manufacturer's instructions.

Cut ends and faces of timber sawn, drilled and cut after treatment are to be swabbed liberally with approved preservatives until saturated, allowed to dry and then treated with a second coat and rates for timber must include for this.

6.9 Nails

Nails shall be galvanised and comply with B.S.1202 and screws with BS. 1210. Screws shall be brass unless otherwise described. Bolts, nuts and washers shall comply with BS. 916 and rag-bolts, coach screws and other accessories shall comply with BS. 1494. Washers shall be square minimum 3mm thick and 38mm sides.

6.10 Workmanship

"Unwrot" or sawn timber shall be as left from the saw and shall be the full dimensions stated.

All carpentry shall be executed with workmanship of the best quality. Scantlings and boarding shall be accurately sawn and shall be of uniform width and thickness throughout. All carpentry work shall be left with sawn faces except where particularly specified to be wrot.

All carpentry shall be accurately set out in strict accordance with the drawings

All structural timbers shall be framed or jointed together with as is most appropriate in the circumstances in accordance with the rules of good practice. Joints must be executed in strict conformity with the drawings.

All joints shall be secured with a sufficient number of nails disposed as shown on the drawings and rates must include for the jointing of timbers. Surfaces must be in good contact over the whole area of the joint before securing. Holes for nails must be pre-drilled undersize, holes for bolts must be bored slightly oversize from both sides of the timber and washers must be used under the nut which must be tightened sufficiently to permanently secure the joint but not to crush the timber.

7.0 JOINERY

7.1 General

The provisions contained in the carpentry section shall apply also in the joinery section where applicable.

7.2 Hardwood

Joinery is to be executed in approved prime, select and locally available hardwood. Hardwood generally will be Mninga (*Pterocarpus angolensis*) but

hardwood for fittings and built in furniture may be Mkangazi (African Mahogany-Khaya nyasica) unless specifically described otherwise.

7.3 Workmanship

All timber shall be wrot by machine dressing on exposed faces, with all machine marks sanded out, unless otherwise specified.

The dimensions and thickness given in these Bills of Quantities are finished (unless otherwise stated). In the event of nominal sizes being stated, an allowance of 3mm should be allowed for each wrought face.

The joinery shall be worked strictly in accordance with the details drawings and is to be framed up and put together as soon as possible, and is to be stored for as long as possible before being wedged up. All joints and angles are to be glued and where necessary cross-tongued with hardwood tongues, and surfaces finished clean and smooth with machine marks sand papered out before fixing.

Should any of the joinery work shrink, wind or fly unduly before the end of the maintenance period of the contract, the work is to be taken down, and new work fixed in its place, together with any other works, which may thereby be affected at the Contractor's sole expense.

Where joinery is described as screwed, this is deemed to include sinking the head of the screws and pelleting with similar timber and grain in with finished joinery. Screws unless otherwise specified, shall be brass. In pricing the items, the contractor will allow for nails and screws and fixing, all labours, cuttings, notching, havling, mortising, tenoning and welding except where otherwise provided. Rates are also to include for one coat approved priming paint on all concealed surfaces.

Allow in the rates for easing and adjusting all doors, and leave in perfect working order.

7.4 Flush doors

Flush doors shall consist of hardwood core or framing covered with 6mm plywood both sides and complying where applicable with the requirements of BS. 459, Part 2 and 2A. Doors described as skeleton framed shall consist of framing 75mm wide to all stiles, top

and bottom rails, with suitable blocks to receive mortise locks on each long edge. Doors described as solid core shall comprise a solid core of vertical laminations. All flush doors shall be edged all round with 25mm thick hardwood lipping tongued and glued in. Doors described as external shall be covered both sides with 6mm 'exterior' quality plywood as described below. All flush doors shall be perfectly plain on both faces and free from all waves, ripples or distortions of any kind. Any door, which, after the application of paint or polish shows any defects of this nature, shall be removed and replaced at the Contractor's expense. Samples of flush doors, which the contractor intends to use, must be first submitted to the Architect/Engineer for his approval.

7.5 Plywood

Plywood shall be of Tanzania manufacture, manufactured from tropical hardwoods of the first grade with BS 145, and unless otherwise stated shall be 'interior' quality. Where stated to be of 'exterior' quality, the plywood shall be W.B.P. bonded weatherproof grade. Where veneered plywood is specified, samples must be submitted to the Architect/Engineer for his prior approval.

7.6 Blockboard

Blockboard shall be of Tanzania manufacture and comply with BS. 3444 and shall be of moisture resistant quality.

7.7. Chipboard

Chipboard shall comply with BS. 2604 resin-bonded wood chipboard.

7.8 Plugging

All work described as plugged shall be fixed with brass screws to plugs formed by drilling concrete, wall, etc. with a screw of suitable "philplug", "Rawplastic", or other approved plugging compound in accordance with the manufacturer's instructions.

7.9 Protection

Any fixed joinery which, in the opinion of the Architect/Engineer is liable to become damaged in any way shall be cased and protected by the Contractor until the completion of the works and the contractor must allow for this in his rates as no separate item for protection has been measured.

7.10 Ironmongery

All ironmongery will be fixed with matching screws to be supplied by the contractor/Client and the contractor must allow for adjusting locks and striking plates and handing over all keys on completion of the contract with identifying tags attached.

The contractor must also allow for oiling locks and hinges and leaving them in perfect working order

All ironmongery shall be manufactured by Union, Yale, Dryad or Newman-Tonks Ltd. or other equal and approved by the Architect/Engineer/Engineer. The following standard abbreviations have been used to describe the finish to ironmongery:-

S.C.P. -	Satin Chrome Plate
C.P. -	Chrome Plate (polished)
S.A.A. -	Silver Anodised Aluminium

8.0 STRUCTURAL STEEL WORKS

8.1 Generally

Steel angles, tees, channels and plates are to be weldable mild steel grade 434 in accordance with B.S.4360.

8.2 Welding

Electrodes for welding are to be in accordance with current British Standard in application

All welds are to be fillet welds of 5mm by size unless otherwise indicated.

8.3 Bolts

Bolts are to be black bolts in accordance with BS 4190 and all nuts, bolts and washers are to be hot dip galvanised. Bolt holes shall have a diameter of the bolt.

8.4 Painting

All steelwork is to be thoroughly cleaned, wire brushed and painted with two coats of red lead primer at the workshop and one finishing coat for aluminium paint. After erection any damage to the paint is to be made good and a further finishing coat applied.

9.0 METALWORK

9.1 Mild steel

Mild steel shall comply with B.S.15, Grade 1, and the sizes of all small section shall be in accordance with B.S.4 and 4A.

9.2 Galvanised work

Iron and steel, where galvanised shall comply with B.S.729, Part 1, entirely coated with zinc after fabrication by complete immersion in a zinc bath in one operation and all excess carefully removed. The finished surface shall be clean and uniform.

9.3 Aluminium

Aluminium shall be of the alloys described in and shall comply with B.S.1470. Aluminium sheet for flashings shall be soft temper, super purity (S1 or S1A) and not less than 18 S.W.G(1.2mm) in thickness.

9.4 Smithing, welding and cutting

All smithing, welding, cutting and bending shall be soundly and neatly executed, care being taken not to overheat. All flame cut edged and welds shall be neatly ground off on completion. All welds shall be 8mm fillet welds to comply with Code of Practice 1856 unless shown otherwise.

9.5 Bolts

Mild steel bolts, nuts and washers shall comply with B.S.916 for black bolts with hexagonal heads and nuts, High Tensile Steel Bolts and nuts shall be in accordance with B.S.3139.

9.6 Anchor bolts

Anchor bolts in concrete for steelwork, etc., are to be self drilling anchor bolts of one of the following types:-

Phillips redhead concrete anchors,
Rawplug super drill anchors,
Split self drilling anchors,

Rates are to include for fixing complete with washer.

9.7 Louvre windows

Louvre windows frames are to be aluminium with a clear anodised finish as manufactured by NACO and obtainable from Casements Africa Ltd., or other equal and approved by the Architect/Engineer.

9.8 Metal doors

Steel for metal doors shall conform to the requirements of BS. 1245:1975.

9.9 Burglar bars

Burglar bars shall be as specified by the Architect/Engineer. The bars shall be cleaned and painted as described on trade of painting on metalwork.

9.10 Structural hollow sections

All hollow sections are to be connected by electric welding. For butt welds the fusion surfaces of each member must be aligned and prepared.

9.11 Mild steel tubing

Mild steel tubing shall be in accordance with BS 1387:1975 with screwed sockets and joints.

9.12 Shop inspection

The Architect/Engineer shall granted full facilities and any necessary assistance for inspection of materials and assembled parts in the contractor's (or his Sub-Contractor) workshops. At least two weeks notice shall be given to the Architect/Engineer in writing prior to the dispatch of finished components to the site to enable the Architect/Engineer to inspect and approve the materials and workmanship at the workshops. Approval of work at the workshop does not relieve the Contractor of his obligations to carry out the work complete at the site to the Architect/Engineer's satisfaction in accordance with the contract.

9.13 Marking

All components delivered to the site are to be marked in paint with the Mark number in accordance with any shop and erection drawings.

9.14 Storage

All components are to be stored at site in proper racks provided for the purpose which provide full support to each member and to avoid any deflection and distortion. Steelwork is to be stored at least 250mm clear of the ground and temporary protection is to be provided for protection against water and damage from any other source.

9.15 Erection

Rates for all metalwork are to include for the complete erection including any temporary supports required and any necessary templates and wedges.

10.0 PLUMBING AND ENGINEERING INSTALLATION

10.1 PART ONE: GENERAL REQUIREMENT

10.1.1 SCOPE OF WORK

10.1.1.1 This specification contains general requirements for Plumbing services and associated equipment for water supply installations, sanitary installation, Gas installation and fire fighting installations and equipment.

10.1.1.2 The scope of work shall incorporate the supply, installation, testing and commissioning of the Plumbing services and associated equipment for water supply installation, sanitary installations, gas installations and fire fighting installations and equipment.

10.1.2.0 **GENERAL CONDITIONS**

10.1.2.1 The Contractor shall use a qualified approved plumber to perform the plumbing and engineering installation as a domestic subcontractor.

10.1.2.2 These specifications shall be read in conjunction with the specifications of the rest of the works. No claim will be entertained on the grounds of failure in this regard.

10.1.3.0 **MATERIALS**

10.1.3.1 **Submission of Samples**

The Contractor shall submit a list of suppliers from whom he proposes to purchase the materials necessary for the execution of the works. The Contractor shall be required to submit samples of the materials for approval. Samples shall be taken in accordance with the relevant British Standard where possible. No source of supply shall be changed without prior approval of the Engineer.

10.1.3.2 **Rejected materials**

All sub-standard materials or materials which become damaged or deteriorate so as not to comply with the specification shall be rejected and shall be removed from the site and replaced at the Contractor's expense.

10.1.4.0 **SAFETY**

Safety precautions throughout the execution of the Works shall comply to the Safety Acts as enacted and operating in the Republic of Tanzania.

10.2.0 **PART TWO: GENERAL SPECIFICATION**

10.2.1 **EXECUTION OF THE WORK**

10.2.1.1 The works shall be carried out by a specialist appropriately certified by the relevant Authorities and Boards for the type and/or value of the installations contained herein. Where no particular Specification is given for any material or item of work, the latest edition of relevant British Standard Specification shall apply. In the event of any disagreement between the information shown on the drawing and the specification, the drawing shall take precedence.

10.2.2

10.2.2.1

The works shall be carried out strictly in accordance with the following Standards and Specifications:

- "British Standard Specification for Design, Installation, Testing and Maintenance of Services Supplying Water for Domestic use within Buildings and their Cartilage" **BS 6700: 1987.**
- "British Standard Sanitary Installation: Part1: Code of Practice for Scale of Provision, Selection and Installation of Sanitary Appliances" **BS 6465: Part 1: 1994.**
- "British Standard Sanitary Installation: Part2: Code of Practice for Space Requirements for Sanitary Appliances" **BS 6465: Part 2: 1996.**
- "British Standard Drain and Sewer Systems Outside Buildings:
Part 4: Hydraulic Design and Environmental Considerations"
BS EN 752-4: 1998.
- "British Standard Code of Practice for Drainage of Roofs and Paved areas"
BS 6367: 1983.
- "British Standard Code of Practice for Sanitary Pipe work"
BS 5572: 1978.
- "British Standard Fire Extinguishing Installations and Equipment on Premises: Part 0: Guide for the selection of installed systems and other fire equipment" **BS 5306: Part 0: 1986.**
- "British Standard for Eaves, Gutters and Fittings"
BS EN 607: 1996.
- "British Standard for Gutter Brackets"
BS EN 1462: 1997.
- "British Standard Fire Extinguishing Installations and Equipment on Premises: Part 3: Code of practice for selection, installation and maintenance of portable fire extinguishers" **BS 5306: Part 3: 1985.**
- Gas Safety (Installation and Use), Regulations,1998.
Statutory Instrument 1998/2451. London: The Stationary Office, 1998.
ISBN 0 11 07 9655 1.

- By-laws of the Local Authority.
- The working drawings

10.2.2.0 EXTENT OF WORK

10.2.2.1 The work includes, unless otherwise specified, supply, installation, testing and commissioning and delivering up clean and in working order the installations shown in the drawings and specified in these General and Particular Specifications.

Water supply shall be from rainwater harvesting system from laboratory roof with plastic storage tank, cold water pipes and associated fittings, valves, sanitary appliances including all necessary taps, overflows and discharge fittings, fire fighting installations and equipment, and all labour, materials, tools and instruments necessary to execute the work in a first class manner, even such labour or materials which are not specifically mentioned herein but necessary for completion of the work.

10.2.2.2 The Contractor shall be responsible for ensuring that runs for floors or wall chases, holes to cut or left will be marked out at the appropriate stage of the structural work. The Contractor shall undertake all modifications demanded by the Authorities in order to comply with current regulations, and produce all certificates, if any, from the Authorities without extra charge.

10.2.3.0 EXTENT OF CONTRACTOR'S DUTIES

10.2.3.1.1.1 At commencement of the work, the Contractor shall investigate and report to the Architect/Engineer if all materials and equipment to be used in the work, and not specified as supplied by others are available locally. If not available, the Contractor shall at this stage place orders for the materials in question and copy the orders to the Architect/Engineer. Failure to do so shall in no way relieve the Contractor from supplying the specified materials and equipment in time.

10.2.3.2 Where the Contractor wishes to propose an alternative method of construction or material to that specified for any part of work, full details shall be submitted for approval. The acceptance or otherwise of any alternative shall be entirely at the discretion of the Architect/Engineer. Materials supplied by others for installation and/or connection by the Contractor shall immediately be reported to the Architect/Engineer. The

Contractor shall be responsible for verifying all dimensions relative to his work by actual measurements taken on the site.

10.2.3.3 As built drawings

At practical completion and before final payment certificate is issued, the Contractor shall provide a complete set of "As Built" record drawings of the entire installation. Drawings shall be in a scale and size approved by the Architect/Engineer and submitted in hard bound volumes for each service of water supply installation, sanitary installations, Gas installation and fire fighting systems. Shop drawings, spare parts list, operation and maintenance manual of equipment installed shall be submitted together with the "As Built Drawings".

10.2.4.0 QUALITY OF MATERIALS AND WORKMANSHIP

10.2.4.1 Materials and workmanship

10.2.4.1.1 All materials, equipment and accessories are to be new and in accordance with the requirements of the current rules and regulations where such exist, or in their absence with the relevant British Standards. Uniformity of the type and manufacture of the equipment or accessories is to be preserved as far as practicable throughout the whole work.

10.2.4.1.2 The Contractor shall, if required by the Architect/Engineer, submit samples of materials to the Architect/Engineer for his approval before placing on order. If in this general specification, the practice is adopted of specifying a particular item as "similar" to that of a particular product, it is to be clearly understood that this is to indicate the type and quality of the equipment required. No attempt is being made to give preference to the equipment supplied by the firm whose name or product is quoted. Where particular manufacturers are specified herein, no alternative makes will be considered, and the Architect/Engineer shall be allowed to reject any other makes.

10.2.4.1.3 The Contractor will be entirely responsible for all materials, apparatus, equipment, etc. furnished by him in connection with his work and shall take all care to protect all parts of finished work from damage until handed over.

10.2.4.1.4 The work shall be carried out by competent workmen under skilled supervision. The Architect/Engineer shall have the Authority to have any of the work taken down or changed, which is executed in an unsatisfactory manner.

10.2.4.2 Pipes and Pipe Fittings

10.2.4.2.1 All pipes exposed on faces of walls, unless otherwise specified, shall be fixed at least 25 mm clear of adjacent surfaces with approved holder-bats built into walls, cut and pinned to walls in cement mortar, where fixed to woodwork, suitable clips shall be used.

10.2.4.2.2 All pipes specified as fixed to ceilings, roofs or roof structures shall be fixed with approved mild steel hangers cut and pinned to ceilings, roofs or roof structures. Where three or more tubes are fixed to ceilings, roofs or roof structure close to each other, they shall be fixed in position, which leaves the lower surfaces at the same horizontal level, unless otherwise specified.

10.2.4.2.3 Pipes shall be fixed to true lines, parallel to adjacent lines of the building unless otherwise specified. Where insulated, pipes shall be fixed with the insulation at least 25 mm clear of adjacent surfaces. The spacing for fixings for internally located piping shall be in accordance with BS 6700: 1987 Table 17.

10.2.4.2.4 Each support shall take its due proportion of the weight of the pipe and shall allow free movement for expansion and contraction. All pipes specified as chased into walls shall have the wall face neatly cut and chased, the tubing wedged and fixed and plastered over. Where pipes are laid in trenches care shall be taken to ensure that fittings are not strained.

10.2.4.2.5 All formed bends shall be made so as to retain the full diameter of the pipe. Sleeves shall be provided where pipes pass through walls and solid floors to allow movement of the pipes without damage to the structure. The overall length of the sleeves shall be that it projects at least 2 mm beyond the finished thickness of the wall or partition.

10.2.5.0 TAPS AND VALVES.

10.2.5.1 Taps and valves shall be in accordance with the following Standards:

- Draw-off taps and stop valves shall comply with BS 1010 Part 2: 1973.
- Copper alloy gate and check valves shall comply with BS 5154: 1991..
- Copper floats for ball valves shall comply with BS 1968: 1953 and plastic floats for the same shall comply with BS 2456: 1990.
- Sluice valves shall comply with BS 5163: 1991.
- Draining taps shall comply with BS 2879:1988.

10.2.5.2 All valves and cocks shall have the same flow areas, as the corresponding pipes and shall be accessible for operation and maintenance and suitably

labelled by an approved method. Stop valves shall be fixed in positions shown on the drawings to form branch services for group control, or where else specified.

10.2.5.3 All valves, cocks and taps shall be of the correct pressure rating according to the recommendations of the relevant British Standards or the local authority. At commencement of the contract, the Contractor shall, if necessary, ask the Architect/Engineer for guidance on this point.

10.2.6.0 SANITARY AND OTHER APPLIANCES

The appliances shall be fixed in the positions shown on the drawings or as directed by the Architect/Engineer. The Contractor shall include in his rates for providing all necessary screws, bolts, etc. together with all jointing material required and also for temporarily erecting and securing fittings and in the required position of service and discharge pipes, taking down, storing and fixing after completion of wall finishing, permanently fixing and connecting to service and discharge.

Care shall be taken at all times and particularly after fixing to protect appliances from damage. Upon completion of the work all appliances shall be cleaned for plaster, paint, etc. and carefully examined for defects.

10.2.7.0 FIRE FIGHTING EQUIPMENT

10.2.7.1 The specified fire fighting equipment shall be supplied and installed by the Contractor in the position shown on the drawings.

10.2.7.2 Supply, installation and maintenance of fire fighting equipment shall be in accordance with the following British Standards BS 5306: Fire extinguishing installations and equipment on premises:

- Part 0: 1986: Guide for the selection of installed systems and other fire equipment.
- Part 3: 1985: Code of practice for selection, installation and maintenance of portable fire extinguishers
- BS 5499: Fire safety signs, notices and graphic symbols
Part 1:1995: Specification for fire safety signs

10.2.8.0 GAS INSTALLATION SPECIFICATION

10.2.8.1 All male gas tap assemblies shall be supplied with 3/8" BSP (BS 2779 G3/8" B) male shank 60mm long. Shanks shall be supplied with flat ends suitable for connection with 3/8" BSP female threaded connectors.

- 10.2.8.2 The male gas tap assembly shall require a 17mm diameter hole drilling in the work surface. Care shall be taken to ensure that the outlet nozzles are in a suitable position so that the safety lever has sufficient clearance to function correctly and is clearly visible from a distance. Anti-rotation nuts shall be used for added security.
- 10.2.8.3 Gas supplies shall be within the range of 20 to 25 Mbars air pressure and supplied by means of copper tubing. As with all gas valves and appliances, assemblies shall be soundness tested on a regular basis to ensure safety.
- 10.2.8.4 Emergency Eye Wash with two streams with ABS bowl shall be provided to give an immediate deluge of water that should dilute and wash away injurious materials, such as caustic acids, fire, radioactive materials.
- 10.2.8.5 A manual shutoff valve at the pipe entry to each laboratory shall be provided.
- 10.2.8.6 Gas pipes shall be ventilated along their run by being exposed or/and by the enclosure being punctuated to provide adequate ventilation to avoid explosion due to a build up of gas in the case of leakage.
- 10.2.8.7.1.1 Gas pipes shall be well supported particularly where they are part of a flexible overhead servicing system or at a height accessible to pupils

10.2.9.0 INSPECTION AND TESTING OF COMPLETED INSTALLATIONS

- 10.2.9.1 Testing equipment shall be supplied by the Contractor for the period of execution of works. The equipment shall be set up and maintained in accurate working order throughout the period of use.
- 10.2.9.2 The Contractor shall provide all necessary testing apparatus and facilities for testing the installations and any defective work shall be replaced immediately and shall be subject of re-testing until found satisfactory.

10.2.10.0 INSPECTION AND TESTING OF WATER SUPPLY PIPE WORK

- 10.2.10.1 Testing for underground pipelines
 - 10.2.10.1.1 The installation to be tested shall be inspected for compliance with the drawings and specifications. Significant variations shall be investigated and corrected, if required, before proceeding with the test.
 - 10.2.10.1.2 After laying , jointing and anchoring, the pipeline shall be slowly and carefully filled with water so that all the air is expelled and tested under pressure. If water from supplier's mains is used for filling the pipeline under

test, the main shall be disconnected from the pipeline before the test is begun.

10.2.10.1.3 Testing shall be carried out in accordance with BS 6700: 1987 5886, appropriate to the material of the pipeline. Interim tests shall be applied to every pipeline. For buried pipelines these shall be carried out before back filling is placed over the joints. Long pipelines shall be tested in sections as work proceeds. Final tests shall be carried out only when all relevant work is complete. Completion for buried pipelines includes back filling, compaction and surface finish.

10.2.10.1.4 The test pressure shall be at least twice the working pressure of the pipeline. Precautions shall be taken to ensure that the required test pressure is not exceeded. Pressure gauges shall be checked and re-calibrated, where necessary, before the test. To avoid the risk of contamination, water used for testing shall be obtained from a potable supply.

10.2.10.1.5 Before accepting a pipeline, a check shall be made that valve and hydrant boxes are properly aligned, that suitable operating keys are provided which can be easily fitted to the valves and, in the case of deep valves, that adequate extension spindles are installed.

10.2.11.0 INSPECTION AND TESTING OF SANITARY PIPE WORK

10.2.11.1 Inspections and tests should be made during the installation of the discharge

System in accordance with BS 5572: 1978, as the work proceeds, to ensure that the pipe work is properly secured and clear of obstructing debris and superfluous matter and that all work which is to be concealed is free from defects before it is finally enclosed.

10.2.11.2 The completion of the discharge system should be meticulously inspected to ensure that the recommendations of the code have been observed and that no cement droppings, rubble or other objects are left in the pipes and that no jointing material

projects into the pipe bore. When this has been done, tests for soundness of the pipe work and for performance should be made.

10.2.12.0 INSPECTION AND TESTING OF FIRE EXTINGUISHING INSTALLATIONS

10.2.12.1 The date and programme of acceptance tests shall first be notified to all parties involved, and a joint inspection of the system shall then be made. Before testing commences, an indemnity shall be obtained, signed by the client or the person responsible for the premises at the time.

10.2.12.2 The agreed test programme shall then be carried through and the following shall be recorded:

- The date and time of inspection/test
- The responsible person carrying out/witnessing tests
- The test programme
- The test results and conclusions
- Any external factors significantly affecting the test
- Subsequent action agreed to be required
- The work carried out as a result of external factors and the result test if any
- The final test report.

10.2.13.0 INSPECTION AND TESTING OF GAS INSTALLATIONS

10.2.13.1 All drop gas tap assemblies shall be tested to 5psi before leaving the factory.
All gas installations incorporating Vultex Labline drop lever gas tap assemblies shall not exceed 75 Mbar test pressure to ensure that the sealing and lubricating media is not displaced.

10.2.13.2 Detailed inspection of fume cupboards, gas pipe work and controls shall be carried out at least once a year

10.3.0 PART THREE: PARTICULAR SPECIFICATION

10.3.1.0 PLUMBING

External plumbing for water supply shall be of polyethylene pipes, uPVC pipes for underground rainwater collection system and polypropylene pipes for internal plumbing while vulcathene chemical waste pipes shall be used for both internal and external drainage.

10.3.2.0 STORAGE TANKS

Overhead water storage tanks with capacity of 3000 litres, Simitank 1.70 metres diameter and 1.7 metres height on 1.5 metres blockwork tower shall be provided.

10.3.3.0 FIRE FIGHTING

12 kg ABC dry powder portable fire extinguishers shall be provided.

10.3.4.0 WASTE WATER DISPOSAL

Soak-away pit shall be provided with manhole constructed of block work.

10.3.5.0 CHEMICAL WASTE DISPOSAL

Emergency eye wash sink with two streams with ABS bowl inclusive of fittings shall be provided.

10.3.6.0 SOLID WASTE DISPOSAL

10.3.6.1 Movable plastic bins of capacity of 20 litres shall be provided for temporary collection of solid waste.

10.3.6.2 Incinerator constructed in blockwork and lined with clay burnt bricks inside shall be used for burning solid waste that cannot be buried.

10.3.6.3 Ventilated Improved Pit Latrine (V.I.P.) shall be provided.

11.0 FLOOR, WALL AND CEILING FINISHINGS

11.1 Sand

Sand for backings, floor and wall finishes is to comply with B.S.1199, Table 1.

11.2 Aggregate

Coarse aggregate is to be as described for 'concrete work'.

11.3 Cement

Cement is to be as described for 'Concrete Work'.

11.4 Lime

Lime is to be non-hydraulic hydrated lime to B.S.890 Class 'A' obtained from an approved source and run into putty at least 24 hours before use.

11.5 Workmanship

All concrete beds or slabs shall be thoroughly brushed if necessary and well wetted and flushed over with a cement and sand (1:1) grout immediately before screeds or pavings are laid

Screeds and cement pavings shall be laid in accordance with the relevant BS. Code of practice. Working joints between bays of the floor finish should be placed in accordance with the Architect/Engineer's instructions and will be plain butt joints placed over joints in the concrete bed under. Pavings shall be damp cured with sand or sawdust and kept damp for at least 7 days after laying.

All surfaces to be plastered or rendered must be brushed clean and well wetted before plaster is applied. Joints of walling shall be raked out and concrete hacked to form a key. Care shall be taken to see that paving and plastering do not dry out prematurely

Adequate time intervals must be left between successive coats in two coat work in order that the drying shrinkage of the undercoat may be substantially complete. All internal and external angles shall be pencil rounded.

11.6 In situ pavings generally

Before laying in-situ floor finishes, the concrete beds are to be thoroughly hacked for key, cleaned off, thoroughly wetted with clean water and coated with a stiff cement slurry and rates for screed granolithic and terrazzo paving are to include for this. They are also to include for all necessary curing and protecting until the building is handed over to the Employer.

11.6.1 Cement and sand paving

The cement and sand paving shall be in the proportions of 1:3 by volume and incorporating or treated with an approved hardener. A mix referred to as 1:4 shall mean 1440kgs (1m³) of cement and 4m³ of sand. All other mixes shall be construed in a like manner.

11.6.2 Concrete paving

The concrete paving shall be in the proportions of 1:2:4 by volume, the coarse aggregate used shall not exceed 10mm nominal size. It shall be trowelled smooth with a steel float. If the contractor wishes to use a power float he is to seek the approval of the Architect/Engineer who may require him to complete a sample area before granting permission.

11.6.3 Terrazzo paving

The in-situ terrazzo shall consist of white or coloured cement and marble aggregate: the colours of the cement and aggregate shall be selected by the Architect/Engineer. The mix shall comprise three parts of 6mm nominal aggregate to one part coloured cement by volume. The aggregate shall be clean and granular and shall not contain flakey particles or duct. The underbed shall be cement and sand 1:4 by volume.

The terrazzo topping shall be laid to a minimum of 12mm thickness in a plastic condition while the underbed is still green and this should be watered to minimise absorption from the topping. The terrazzo must be well tamped into position and rolled with a suitable hand roller. The topping should be allowed to take an initial set and then any surface voids must be grouted up with neat cement of the same colour used in the mix. The sacking for at least 72 hours. When dry and hard, the surface shall be machine polished by grinding with carborundum or other stone discs of suitable grade and with rotary polishing pads.

11.6.4 Tyrolean rendering

Tyrolean rendering is to be applied in four coats to obtain a total thickness of 22mm and adequate time intervals must be allowed between successive coats in order that the drying shrinkage at each undercoat may be completed. The first coat shall consist of cement, lime putty and sand mixed at a minimum thickness of 10mm and finished with a wood float finish. The second, third and fourth coats shall consist of one part of natural cement to four parts of fine white chippings including colour pigment to approval applied with an approved "flicking machine" so that the first coat is completely covered and a thickness of 12mm is obtained.

11.6.5 Internal plaster

Internal plaster shall be applied in two coats and adequate time intervals must be allowed between successive coats in order that the drying shrinkage of the undercoat may be substantially complete. The first coat must be well scratched, keyed and wetted to receive the finishing coat. The finishing coat shall be finished smooth with a steel float but care must be taken not to overwork the surface in order to minimise the incidence of shrinkage cracks. All internal and external angles shall be pencil rounded.

Internal plaster, unless otherwise described, shall be lime plaster of 15mm minimum overall finished thickness applied in two coats, the first coat consisting of cement, lime putty and sand mixed in the proportions of (1:2:9). The finishing coat shall be a skin coat comprising cement and lime putty in the proportion of (1:10).

Cement plaster is to be employed where specified on the drawings and is to be applied in two coats of approximately equal thickness to a total of 15mm minimum overall finished thickness. The composition of both coats shall be the same and shall comprise cement and sand (1:4) but a small percentage addition

(not more than 10%) lime putty may be permitted if the Architect/Engineer considers that this will reduce the incidence of shrinkage cracks.

The contractor shall cut out and make good all cracks, blisters and other defects and leave the whole of the plastering and rendering perfect at completion. When making good defects the plaster shall be cut out to a rectangular shape with edges undercut to form dovetailed key, and all finished flush with the face of surrounding plaster.

11.6.6 "Sandtex" finish

'Sandtex' finish shall consist of one part white cement to four parts sand by volume applied in two coats in the manner as described for internal plastering to a total thickness of 15mm and the final coat wet brushed to expose the sand to a texture to be approved by the Architect/Engineer.

11.7. Wall tiling

Glazed wall tiles shall be from an approved manufacturer and shall conform with the requirements of BS. 1281. Tiles shall be with slightly rounded or 'cushion' 'edges' and unless otherwise described shall be 150 x 150 x 6mm thick. Tiles shall be laid with continuous straight joints and internal angles shall be butt jointed.

Rounded on edge tiles shall be used on all external angles and edges of panels. Tiles shall be bedded in approved tile adhesive and pointed in white cement.

Backings to tiles are to be cement and sand in the proportion of 1:4 rendering in one coat to a minimum thickness of 12mm trowelled smooth.

11.8 Wood block flooring

Parquet tile flooring shall be as manufactured by Italwood Ltd. Dar Es Salaam Tanzania or other equal and approved by the Architect/Engineer. It shall be laid on a smooth screed and fixed with approved adhesive. It shall be finally sanded and finished with two coats of Ronseal Hardglaze.

11.9. PVC Flooring

PVC. tile flooring shall be used according to specified standards with an approved base.

The selected colours to be used shall be approved by the Architect/Engineer.

12.0 GLAZING

12.1 General

Glass generally shall comply with the requirements of B.S.952 and shall be free from bubbles, specks waves, flows or any other defects.

Clear sheet glass shall be 24 or 32 oz. (4 or 5mm nominal thickness) flat drawn sheet of ordinary glazing quality.

Glass for louvre blades shall be clear sheet flat drawn or rough cast obscured rolled glass to the thickness shown on the drawings with all exposed edges ground and polished.

12.2 Putty

The putty shall be hard setting tropical putty to B.S.544

12.3 Workmanship

All glass is to be accurately cut to fit easily into rebates with a tolerance of 2mm all round. It is to be well puttied at the back and to the sprigged with non-ferrous pins. The putty is to be mostly trimmed and cleaned off and care must be taken that it does not show beyond the sight lines of the sashes. All rebates must be treated with one coat of lacquer (as described under 'Painting' hereafter) prior to glazing.

12.4 Cleaning and protection

The contractor must allow in his rates for the protection of all work in this section and for replacing any cracked, scratched, broken or defective glass prior to handing over to the Employer. He must also allow for cleaning all the windows inside and out and other glass on completion with an approved window cleaner and wash leather and for removal of all paint splashes.

13.0 PAINTING

13.1 Colour range

All painting shall be carried out in colours selected by the Architect/Engineer.

13.2 Materials

Paints generally shall be ready mixed and supplied by one of the manufacturers listed below and delivered to the site in sealed containers clearly labelled with the a manufacturer's name, type of paint and colour. Oil based priming paint shall comply with B.S.2521-2524 inclusive.

Leyland Paints (T) Ltd
Robbialac Paints (T) Ltd
Sadolins Paints (T) Ltd
Goldstar Paints Tanzania Ltd

Paints are to be used strictly in accordance with the manufacturer's instructions and no contamination by mixing with other brands or materials will be permitted. Thinning is only permitted in so far as it is in accordance with the manufacturer's printed instructions.

13.3 Preparation

All surfaces to receive treatment are to be clean and dry before paint application and surface irregularities are to be removed by filling or the use of suitable abrasives.

13.4 Plastered surfaces

Internal plastered wall surfaces generally are to be treated with plastic emulsion paint. Surfaces are to be allowed to dry out thoroughly prior to paint application. All crack and surface imperfection are to be cut back and filled with a patent filler in accordance with the manufacturer's instructions and rubbed down to a true and even surface.

Apply one primer coat thinned with water and two subsequent coats of Leyland's 'Leymure Co-polymer' or other approved plastic emulsion paint in accordance with the manufacturer's instructions. Where specified internal plastered wall surfaces are to be painted gloss. In addition to the preparation described above, apply one coat of Leyland's P 20 or other approved alkali, resistant primer and flat down with 320 grade 'wet or dry' abrasive paper. Apply two coats Leyland's Leylac Polymeric gloss finish or other equal and approved gloss paint lightly rubbed down coats in accordance with the manufacturer's instructions.

13.5 Woodwork preparations

Large knots in woodwork are to be cut back and replaced with sound wood or scorched back and after priming the surface made good with stopping. All knots are to be treated with two thin coats and patent knotting free from resin.

After priming all nail holes and other imperfections shall be filled with stopping and the whole surface rubbed down to a smooth even finish. The stopping must be 'Scadofil' or other approved make.

13.6 Metalwork

All rust and loose scale on steel and ironwork must be removed by wire brushing and rubbing with emery paper. Where patches of ingrained rust cannot be removed they are to be thoroughly rubbed down and treated with one coat of 'Galvafruid' or other zinc paint in accordance with manufacturer's instructions. One coat of zinc chromate primer will then be applied followed by two undercoats and one finishing coat of gloss paint as described for woodwork above. The contractor is to note that where mild steel burglar bars are housed into wood frames the full length of the bar is to be treated before fixing.

Galvanised metalwork is to receive one coat of white spirit or mordant degreasing solution washed off prior to the application of calcium plumbate primer followed by two undercoats and one finishing coat of gloss as previously described.

Galvanised metalwork is to be painted only where instructions are given by the Architect/Engineer as in some cases galvanised metalwork is to be left untreated.

14.0 DRAINAGE

14.1 Generally

The preambles for the previous trade sections are applicable to this section together with the following preambles. The drainage is to be carried out in accordance with the directions of the Architect/Engineer and the requirements of the Byelaws. No length of drain is to be covered until it has been tested and passed.

14.2 PVC drain pipes

PVC Drain pipes comply with ISO R161 (4kg/cm²) 'Pipes of plastic materials for the transport of fluids.

The drainpipes shall be spigot and socket glued joints.

14.3 Cast iron drain pipes

Shall be centrifugal cast (spun) iron drainpipes with spigot and socket to BS.437 thoroughly coated inside and outside, alternatively similar pipes but class 'B' in accordance with BS. 1211 may be used according to availability. Fittings shall be in accordance with BS.1130.

Pipes shall be jointed with asbestos yarn and caulked with molten lead or jointed with special jointing compound all to approval.

14.5 Concrete drain pipes

Precast concrete pipes shall be in general conformity with BS. 556. Concrete cylindrical pipes and fittings. The concrete mix used for the manufacture of ordinary pipes shall not be weaker than grade '30'.

For foul water drainage sulphate resisting concrete pipes shall always be used. The manufacturer of sulphate resisting pipes shall be in general conformity with BS. 556. The concrete mix not weaker than grade '30'. Pipes up to and including 45cm diameter shall be un-reinforced and shall incorporate spigot and socket type joints. Pipes above 45cm diameter shall be reinforced with not less than steel fabric required by British Standard BS 8110 or the equivalent in mild steel and shall have spigot and socket joints or if the Architect/Engineer so approved shall have open type joints. The main reinforcement to be in circumferential direction. Pipes reinforcement shall be placed midway between the inner and outer surfaces of the concrete. In socketed pipes the reinforcement shall be extended continuously from the pipe barrel into the socket, the longitudinal bars cranked as necessary.

No wall thickness of the pipe barrels is specified but the reinforcement (if any) and the wall thickness must be so balanced that the pipes are in conformity with B.S.556 and the test specified therein.

14.6 Pitch impregnated fibre drainpipes

Pitch impregnated fibre pipes, couplings and fittings shall comply with BS. 2760 Part 1 and 2.

14.7 Manholes

Manholes shall be constructed on drain lines in the positions indicated or wherever ordered by the Architect/Engineer.

Manholes on pipe drains be constructed with an-in-situ base in concrete grade "20" which shall be raised to form the benching and invert of the manhole. The benching and channels shall be carefully formed to shape according to the number, diameter and positions of the incoming and outgoing pipes. The channels in the manholes base shall have circular inverts. The benchings shall be sloped towards the channels at a gradient of 1 in 6 or as otherwise detailed on the drawings.

Benching shall be carried out in concrete grade "20" and rendered with 15mm 1:3 cement mortar. Rendering to be carried out in sulphate resisting cement for foul water drainage. The ends of all entering the manholes are to be carefully cut to shape to suit the internal dimensions of the manholes and are to be as short as possible and are to be surrounded with 150mm concrete up to the first pipe joint.

The manhole shall be constructed in accordance with the drawings for typical and special manholes.

Manholes cast iron steps for manholes shall comply with BS. 1247. All steps be hot dip galvanised after manufacture.

Manhole covers and frames shall be in accordance with the requirements of BS. 497 and as specified on the drawings.

14.8 Concrete beds etc

Concrete beds shall be grade "15" laid to correct falls, 300mm wider than the external diameter of the pipe. Rates are to include for laying in two parts, the first part being laid on the trench bottom 75mm thick and allowed to set before pipe laying is commenced. Individual pipes shall be firmly supported on precast concrete blocks placed immediately behind the socket and in such a manner that each pipe is accurately position in both line and level and the underside of the barrel is at least 75mm above the top of the concrete.

After the joints have been made and the pipelines satisfactorily tested, the first layer of the concrete bed shall be thoroughly washed down and cleaned and the remainder of the bedding concrete (and the launching or surrounding concrete where required) shall be placed and consolidated under and around the pipe in such manner as not to cause any damage or disturbance to the pipe or joints.

The contractor is to ensure that his method of placing this second layer of concrete is such that the full length of each pipe is fully supported. The overall depth of beds is to

be in accordance with the table given on the drawings. Where pipes are specified to be haunched, the bed shall be brought up with the second layer of concrete to a minimum overall depth of 150mm to the underside of the barrel of the pipes plus half the diameter of the pipe and then sloped up to the top of the barrel of the drain pipes. Where pipes are specified to be surrounded, the bed shall be brought up with the second layer of concrete to a minimum overall depth of 150mm to the underside of the barrel of the pipe and then completely surrounded with concrete with 150mm minimum cover all round. Rates for this item are to include for any formwork required.

14.9 Trenches and manhole excavation and back filling

The bottom of drain trenches is to be trimmed and consolidated to correct levels and gradients. If any trenches are over-excavated the contractor to fill up to the proper depth at his own expense with concrete grade "10" where required. Rates for drain trenches are to include for grading bottoms, any necessary planking and strutting and keeping the excavations free from water, returning, filling in and ramming ground over and disposing of surplus material to spoil heaps on site. They shall also include for sieving and hand filling trenches where required for the first 300mm over the drainpipes.

Back filling shall be executed with selected material in 150mm layers (300mm layers if a mechanical rammer is used) each layer being well rammed and watered to obtain the maximum compaction. Care be taken to ensure that no stone or other work is placed within 300mm of such work.

Rates for manhole excavation shall include for levelling the bottoms. All surface material including top soil which differs in any nature whatsoever from the substrata, shall in every case be carefully set aside and stored separately from other excavated materials. No claim for extras will be allowed for setting aside topsoil for later use.

14.10 Pipe laying and jointing generally

All laying and jointing of pipes shall conform generally with C.P. 301. Each cast iron, or concrete pipe shall be tested for soundness before laying by striking with a hammer and any pipe or joint which does not ring true or which shows in any other way any sign of being defective shall be regretted. Each pipe shall be laid accurately to line and gradient so that the finished pipeline shall be in a straight line both in horizontal and vertical planes. The contractor shall fix properly painted and securely positioned sight rail, the levels and positioning of which shall be checked by the Architect/Engineer's representatives before the rails are used and as often thereafter as may be necessary. There shall be at no time less than three sight rails in position on each length of pipeline under construction to any one gradient and the sight rails shall be situated vertically above the line of pipes or immediately adjacent there

14.10.1 Jointing PVC Drain pipes

The type of joint used for drain PVC pipe is cemented spigot and socket. The jointing procedure is as follows:-

- i) The spigot end shall be chamfered
- ii) Clean spigot and socket with wet cloth and let dry
- iii) Un-grease spigot and socket with acetone
- iv) Mark length of joint and spigot
- v) Apply first a relatively thick layer of cement onto spigot and then a thin layer into socket
- vi) Flush home the joint to the mark quickly and give at once a 90 twist.
- vii) Remove pressed out cement
- viii) Do not disturb the joint for five minutes whilst cement is hardening

The cement used shall be supplied by the factory, which is supplying the pipe.

14.10.2: Jointing precast concrete pipes

The contractor shall adopt such measures as may be approved by the Architect/Engineer to ensure that every laid down pipe is concentric with previously laid pipes with which it joints. Unless otherwise approved pipes shall be laid in an up-gradient direction and the spigot shall be laid in the direction of the flow. Before commencing the laying operation, the contractor shall ensure that the portions of pipe, which come into contact with jointing materials, are perfectly clean.

Cement mortar joints for concrete pipes with spigot and socket joints shall be made as follows:-

- i) Before commencing the jointing operation the socket of the previously placed pipe and the spigot of the new pipe shall be cleaned and thoroughly soaked with water.
- ii) The spigot shall be wrapped one complete lap with tarred hemp spun yarn and the new pipe shall be carefully drawn towards the previously laid pipe so that the spigot enters the full depth into the socket of the previously laid pipe. The new pipe shall then be adjusted and fixed in its correct position in line, level and gradient and the yarn shall be caulked tightly home into the socket. On completion of this operation the yarn shall not fill more than one quarter of the total depth of the socket.

- iii) The remainder of the socket shall be completely filled with cement mortar consisting of one part of cement (sulphate resisting cement for foul water drainage) to three parts of sand. The mortar filling shall terminate flush with the socket and shall be neatly trowelled to a smooth finish completely around the pipe.
- iv) To assist the curing of the mortar the contractor shall cover the joints immediately after they are made with a layer of hessian which shall be kept continuously wet during daylight hours and he shall further adopt such other measures as the Architect/Engineer may direct all at the Contractor's expense.

14.11 Position of floor gullies etc.

The contractor shall before positioning floor gullies duck-foot bends for ventilating stacks etc. consult the Architect/Engineer in order to ensure the correct position of these. Failure to do so, shall in no way relieve the contractor from positioning floor gullies, duck-foot bends for ventilating stacks etc. in positions, the Architect/Engineer later may direct.

14.12 Testing

After the drains are laid and jointed and before the trenches are filled in, they are to be tested in the presence of the Architect/Engineer's representatives. The drains shall be tested in lengths between manholes or such shorter lengths as the representative or the Architect/Engineer may approve.

Water shall be passed into the length under test until such time as all the air has been expelled and the line is full of water and subjected to a head of 1500mm at the upstream end. The test shall be considered to be satisfactory if there is no visible leakage, seepage or weeping from any of the pipes or joints and if the head of water in a 76mm diameter upstand tube fitted at the upstream does not fall at a rate faster than 12mm per minute per 30 metres length. The contractor shall make such time allowance as may be necessary for the pipe to absorb water being subjected to test.

Manholes are to be tested for water-tightness in the same way as for drains by filling with water but not exceeding 1500mm head.

The contractor is to supply all testing apparatus and materials necessary for these tests and provide all labour and assistance required. Any failure whatsoever in the drainage system to withstand the specified tests and any defects appearing are to be made good and the drains re-tested to the satisfaction of the Architect/Engineer.

15.0 EXTERNAL WORKS - ROADS AND PARKINGS:

15.1.0 Earthworks

15.1.1 Dimensions:

All earthworks shall be executed to the plan, dimensions lines, slopes, widths and levels shown on the Drawings or supplied by the Engineer. Typical cross-sections and details shall be subject to variation to accord with the contours, levels and falls shown on the Drawings or supplied.

15.1.2 Protection of earthworks

Earthworks shall be properly protected at all times against the risk of damage from natural causes. The Contractor shall take every precaution against damage from sudden storms by phasing the works and by covering, pumping, shoring and forming temporary drains and sumps. Earthworks shall be excavated at all times to levels and falls, which effect drainage. No work shall be carried out which allows the possibility of water to stand in any construction area.

Any earthworks, whether under construction or complete, which suffer damage shall be removed and the work made good with materials and methods required by the Engineer at the Contractor's expense.

15.1.3 Drainage of earthworks

Earthworks shall be executed at all times to levels and slopes, which effect drainage. Water shall not be permitted to stand in construction area at any time. It may be necessary to keep the excavation clear of water by pumping, in which case the contractor shall allow for this. The Contractor shall provide, maintain and operate the pumping equipment, and shall construct such drains and sumps as may be necessary to remove the water from the excavations.

Water shall be dealt with in such a manner as will prevent the surfaces on or against which structures will be constructed from any deterioration of their natural conditions, or from such condition as improved by work executed under the Contract.

15.1.4 Spoil

Spoiling of surplus or unsuitable excavated material within the site may not be permitted and the Contractor's rates for excavation should therefore include for running to an external spoil tip approved by the appropriate authority.

No borrow pits shall be opened on the site.

15.1.5 Formation

The formation is defined as the surface obtained after completion of earthworks, i.e. the top surface of the sub-grade and the underside of the initial layer of construction

15.1.6 Topsoil

Surface spoil shall be removed from all construction areas to the depth stated or required by the Engineer. Sufficient soil shall be stockpiled on site to enable a minimum thickness of 150mm to be returned to those areas, which are designated for grassing or landscaping, and the remainder shall be run to spoil. The Contractor is to exercise care to ensure that topsoil, is not contaminated with sub-soil or construction materials. Should this occur he shall supply replacement topsoil in quality approved by the Engineer at his own expense.

15.1.7 Placing of fill material

Material selected for use as fill shall be approved by the Engineer and shall generally be selected from that obtained during excavation work. Fill shall be placed in layers with upper surfaces parallel to the finished surface of the works and with compacted thicknesses not exceeding those shown on the Drawings unless otherwise agreed by the Engineer.

Layers shall be of uniform thickness after placing any lower make-up layers. The layers shall be of a length suited to the progress of the plant employed in placing and compacting in order to avoid exposure.

All roots, other organic matter, unsuitable material or deleterious substances shall be removed from fill before compaction commences.

Fill layers shall be compacted to 90% BS. Compaction throughout their depth except for the final layer under the formation, which shall be, compacted to 95% BS. Compaction for a minimum depth of 150mm.

The completed surface of the formation and of other fill areas shall be within the following tolerances of the levels and gradients shown on the Drawings or directed by the Engineer.

Formation	+	0mm	- 50mm
Other fill areas	+	50mm	- 50 mm

15.1.8 Excavation

Excavation shall be carried out in a manner ensuring that the excavation plant and vehicles used do not cause rutting or damage to the sub-grade. Excavation shall be to the levels shown on the Drawings or instructed by the Engineer. Should excavation reveal sub-grade material, which is unsuitable in the opinion of the Engineer such material shall be removed and replaced by, approved fill material compacted in layers as specified.

Where instructed by the Engineer, the Contractor shall scarify the sub-grade to a depth of 150mm and the material shall be re-compacted to 95% BS. Compaction. Alternatively where so instructed he shall compact the undisturbed subgrade to 95% BS. Compaction.

The completed surface of the formation and of other cut areas shall be within the following tolerances of the levels and gradients shown on the Drawings or directed by the Engineer:

Formation	+	0mm -	50mm
Other cut areas	+	50mm -	50mm

15.1.9 Construction control testing:

All earthworks shall be subject to construction control testing. For each excavated surface and each layer of fill, the Contractor shall carry out compaction tests at the rate directed by the Engineer.

When the test results demonstrate the area of formation or fill complies in all respects with the requirements of this Specification, he shall apply to the Engineer for approval. Such application shall identify the boundaries of the area submitted and shall be accompanied by a copy of the test results. Upon receipt of an application for approval the Engineer will generally approve the area or layer submitted, but reserves the right to order without unreasonable delay such further tests as he considers to be necessary. This procedure will be relaxed at the discretion of the Engineer as soon as the Contractor consistently achieves by his methods and plant the standards required.

15.1.10 Excavation for structures and services

Excavation shall be carried out to the line and depths shown on the drawings or to such other lines and depths as the Engineer may direct. Excavation shall be of sufficient size to enable the Works to be properly constructed. The faces and beds of all excavations shall be properly trimmed and cleaned of all loose stone, dirt or other debris. The bottom 150mm of material shall not be removed until just before placing of the blinding concrete, mass concrete foundations or bedding as the case may be.

The Contractor shall report to the Engineer when a secure bottom to the excavations has been obtained and is ready for the construction of the new work, and when approval has been obtained the new work shall be constructed without delay. Any work constructed in excavations before they have been inspected and approved shall, if so directed, be removed and new work substituted after approval, all at the Contractor's expense.

15.1.11 Supports for excavations

The sides of pits, trenches and other excavations shall, where necessary, be adequately supported to the satisfaction of the Engineer by timber or by other approved means. Should slips of material occur in trenches or pits the work of re-excavating and making good shall be carried out by the Contractor at his own cost to the Engineer's approval.

15.1.12 Back-filling excavations for structures and services

Excavations shall be back-filled with approved selected excavated material or imported approved material only after the work has been measured and approved by the Engineer.

All filling shall be deposited in layers with a compacted thickness not exceeding 150mm. The material shall be compacted to 90% BS compaction for its full depth. Timber and framing shall be withdrawn ahead of the layer to be compacted, care being taken to keep the sides of the excavation solid and to fill completely all spaces left by withdrawn timber.

15.1.13 Over excavation

Over-excavation in depth and width for pavement works shall be rectified at the Contractor's expense by returning approved selected fill material and compacting to Specification.

Over excavation in depth for structures and services works shall be rectified by refilling with mass concrete but over excavation in width can be made good by returning approved selected fill material and compacting to Specification, all at the Contractor's expense.

15.1.14 Use of explosives;

Except in exceptional circumstances the use of explosives will not be permitted. However, should blasting be permitted, it may only take place at times agreed with the Engineer and the Contractor will be responsible for observing all conditions set forth in Government and Local Authorities Regulations.

Adequate warning must be given to road users and any persons in the neighbourhood when blasting is about to take place.

The Contractor shall indemnify the Employer against any claims for damages to persons or property on or near the site from any cause whatsoever arising out of the use of explosives.

The Contractor will be held solely responsible for and must immediately make good to the approval of the Engineer any damage that may occur through the use of explosives. No claim for extras whatsoever will be considered as a result of prohibition by the Public Authorities from the use of explosives.

15.1.15 Grass

Where instructed by the Engineer the Contractor will provide suitable grass and plant, water, weed, cut, maintain and deliver up the same in good condition at the end of the maintenance period. Planting should take place immediately before a rainy season and should be carried out in accordance with good horticultural practice. Areas, which do not cover or die before they are properly established should be replaced, so that all areas to be grassed are delivered up in a wholly satisfactory condition.

15.2.0 Pavement construction

15.2.1 Preparation:

Prior to the construction of each pavement layer, the previously prepared formation or layer shall be thoroughly cleaned of all foreign substances. Any ruts or soft spots which occur or any deviation from the specified tolerances or degree of compaction shall be corrected by scarifying, removing and/or adding approved material, relaying and re-compacting the unsatisfactory areas to the required density and to the required lines and levels. Should any damage occur to the formation or a pavement layer prior to the construction of the next layer, it shall be rectified to the satisfaction of the Engineer at the expense of the Contractor.

15.2.2. Alignment and level control

Stakes, boards and boning rods of substantial construction shall be furnished, set and maintained by the Contractor, in order that the works will conform to the lines and levels shown on the Drawings. The stakes shall be set at intervals not exceeding 25 metres in lines parallel with the centre line and not parallel with the centre line and not more than 25 metres apart.

Stakes, boards and boning rods shall be painted in such a manner as to indicate clearly the lines and levels to be worked to for each layer of pavement.

15.2.3 Thickness and surface tolerances:

The thickness of each pavement layer shall be such that the depths from the required finished surface levels of the pavement to the surface of each pavement layer shall nowhere be less than the depths shown on the Drawing. The surfaces of each layer other than the final layer be lower than the required surface within the tolerances stated below, provided that any such deficiency shall be made good at the Contractor's expense by increasing the thickness of the course above the surface in question.

Each layer of pavement shall be finished to a surface profile parallel to the finished surface of the pavement shown on the drawings with the level of tolerances shown below:

Variation permitted (mm)

Sub base	+	0-40
Road base	+	0-25
Surfacing	+	6-6

The finished surface of all pavements shall be such that when tested with a straight edge 3 metres long placed in any position and direction, there shall not be any gap greater than 5mm between the bottom of the straight edge and the surface of the pavement. In addition to this requirement, there shall not be any deflection exceeding 10mm from a straight line between any two longitudinal points 30 metres apart. Neither of these requirements shall apply across crowns.

These smoothness tolerances apply to straight profiles and equivalent smoothness tolerances shall be applied to vertical curves

15.2.4 Gravel sub-base

The material used shall be good quality naturally occurring gravel. It shall be subject to suitable testing at the direction of the Engineer to show that it has a 4 days soaked CBR of not less than 30% at 100% BS. Compaction. The grading of the material shall show a smooth grading curve parallel to and within the limits stated below. The material shall have a Plasticity Index not exceeding 20%

The sub-base material shall be spread to the full width of the cross-section and to loose thicknesses so that after compaction the finished thicknesses will be those specified. Oversize pieces shall be removed or separately broken down. The method of compaction shall be approved by the Engineer and shall be such as to compact the material to 100% BS. compaction through its full depth. Control testing shall be carried out if directed by the Engineer.

BS. Sieve size	Percentage passing		
37.5mm	100		
20mm	80-100	100	
10mm	55-80	80-100	100
5mm	40-60	50-75	80-100
2.36mm	30-50	35-60	50-80
1.18mm			40-65
600 microns	15-30	15-35	
300 microns			20-40
75 microns	5-15	5-15	10-25

15.2.5 Gravel road base

The material used shall be best quality naturally occurring laterite or gravel from a source approved by the Engineer. It shall be subject to suitable testing at the direction of the Engineer to show that it has a 4 day soaked CBR of not less than 60% at 100% BS. Compaction. The grading of the material shall show a smooth grading curve parallel to and within the limits stated below. The material shall have a Plasticity Index not exceeding 12%

Immediately before applying the road base, the surface of the sub-base shall in all respects comply with the specification and be thoroughly clear of all loose of foreign matter. The road base material shall be placed on the prepared sub-base by an approved method to a thickness, which on compaction will result in the thickness required. If necessary, the moisture content of the material shall be adjusted to ensure optimum compaction.

Immediately following the placing, the layer shall be compacted by approximately 16 passes of an 8 tonne pneumatic-tyred roller or equivalent passes of a vibrating or smooth-wheeled roller, to 100% BS. Compaction. Rolling shall progress from the sides to the centre of the areas under construction. Areas inaccessible to the roller shall be compacted by mechanical plate compactors. Control testing shall be carried out if directed by the Engineer.

15.2.6 Crushed stone road base:

The aggregates for crushed stone road base shall be obtained from approved sources and consist of hard, tough, heavy, compact, approved rock. After crushing it shall be roughly cubical in shape, free from flat, flakey, elongated, soft or decomposed pieces, excess dust and any dirty, acids or other deleterious substances. The rock from which the stone is to be produced shall have an Aggregate Crushing Value not exceeding 25% a Los Angeles Abrasion Value not exceeding 35% and a Flakiness Index not exceeding 30%.

The grading limits of the material shall be within and approximately parallel to curves defined by the following limits:

BS Sieve	% passing
50	100
37.5	95 - 100
20	65 - 80
10	40 - 60
5	30 - 50
1	20 - 38
0.425	12 - 24
0.075	5 - 13

Before commencing spreading and compaction the Contractor shall determine the maximum dry density and optimum moisture content of the material for each layer in accordance with BS. 1377.

Mixing, handling, transporting, piling, spreading and compacting of the crushed stone shall take place whilst it is in a moist condition and in such a manner as to avoid segregation. The Contractor shall as necessary and further water so that compaction is carried out within the range of - 2% to + 0.5% of the optimum moisture content.

The material shall be spread by means of a mechanical paver, which shall be to the approval of the Engineer and be capable of spreading the crushed stone

material in an even manner without segregation to a thickness which will give the required finished thickness.

No material shall be delivered to the paver over previously compacted material. Spreading shall commence at the high point of a pavement cross-section and finish at the low point or points. Where, in the opinion of the Engineer, segregation has occurred the material in the affected area shall be cut out and replaced.

The material shall be compacted initially with a self-propelled pneumatic tired roller and followed by a heavy vibrating roller until all visible movement under the wheels ceases.

Any voids appearing in the surface shall be filled with crusher fines, watered and re-compacted until a hard dense layer is obtained. Compaction shall proceed from the sides to the centre of the lane under construction or from one side towards previously compacted material. The crushed stone layer shall be compacted to 100% BS. Compaction. Areas inaccessible to the roller shall be compacted by mechanical plate compactors. Control testing shall be carried out if directed by the Engineer.

15.2.7 Protection of pavement layers:

No construction traffic shall run over the exposed formation or over sub-base layers. Sub-base, or road base material where no sub-base is specified, shall be laid on the formation as soon as the last 150mm of material protecting it has been removed, in a continuous operation, and no formation shall be opened which cannot quickly be covered with sub-base or road base respectively.

The placing of the road base shall be followed as soon as practicable by the placing of the surfacing.

15.2.8 Prime coat

A prime coat shall be applied to the road base before the premix or asphalt surfacing; or surface dressing. The surface shall be thoroughly swept by brooms, all laitance, loose and foreign material removed and the clean surface of the base and hard particles in the layer exposed as a mosaic.

All loose material shall be swept well clear of the area to be primed. The surface shall be checked for line, cross-fall and level and made good as necessary and approved by the Engineer before any bitumen prime is applied. Where required by the Engineer, immediately prior to the application of prime, the surface shall be lightly sprayed with water but not saturated.

The prime coat shall be sprayed immediately after the preparation of the stone layer is completed and approved. The type of prime coat shall be medium curing cutback bitumen MC 30 grade. The rate of spray will be as directed by the Engineer between 0.5 lit/m² - 1.0 lit/m². The quantity used must give complete coverage with a slight trace of run off in places. Should the Contractor find that at the rate of spray directed the coverage is inadequate, or there is too much run off, he shall immediately inform the Engineer and amend the spray as directed.

The prime should penetrate about 3 to 6mm and dry to a matt surface in 24 hours, leaving no pools of bitumen on the surface.

During spraying all kerbs, headwalls, drains and the like which are liable to be disfigured by splashing of bitumen shall be protected, and any such feature which is accidentally marred by bitumen, shall be cleaned with a suitable solvent or if this is not possible removed and made good at the Contractor's expense.

15.2.9 Chippings

Chippings used for surface dressing should be single sized, cubical in shape, clean and free from dust, strong, durable and not susceptible to polishing under the action of traffic. These should be selected in accordance to British Standard BS 63, "Single sized road-stone and chippings".

Samples of chippings should be tested for grading, flakiness index, aggregate crushing value and when so instructed by the Engineer, the polished stone value and aggregate abrasion value, before the start of surface dressing operation or when new supplies are delivered.

- Maximum aggregate crushing value (ACV) for surface dressing chippings should be between 20 to 35%
- Aggregate abrasion value (AAV) will be 14 for side and estate roads and 12 for highways (traffic up to 1000 vehicles /lane/day)
- Nominal size will be 6,10,14 and 70mm. "Flaky" chippings are those with thickness (smallest dimension) which is less than 0.6 of their nominal size.

15.2.9.1 The previously primed surface shall be swept clean with brooms and the debris deposited well clear of the surface to be surfaced. Any defects of the surface shall be made good as directed by the Engineer and no binder shall be applied until the surface has been approved by the Engineer.

The binder for surface dressing shall be straight run hot bitumen of grade 80/100 pen applied by a bitumen distributor complying with BS 1707 at a temperature between 145 degrees and 205°C.

15.2.9.2 Dressing

During spraying all kerbs, head walls, drains and the like which are liable to be disfigured by splashing of bitumen shall be protected, and any such feature which is accidentally marred by bitumen, shall be cleaned with a suitable solvent, or if this is not possible, removed and made good at the Contractor's expense

Immediately after the binder has been applied, clean dry stone chippings shall be spread at the rate directed by the Engineer. Directly the stone chippings have been spread they shall be rolled initially so that the whole area receives at least one pass within ten minutes of the bitumen being sprayed. Immediately after the initial rolling, any area, which is deficient in chippings, shall be made good by hand spreading. Brooming of the material to effect redistribution of chippings will not be permitted. The number of passes of the roller shall be laid down by the

Engineer, but shall be at least two. A certain amount of crushing under the roller is permissible, but should any general shattering occur, the Engineer may direct that rolling shall cease, regardless of the number of passes completed.

Pneumatic tyred rollers are preferred for rolling of all bitumen seal work though finishing with smooth steel-wheeled rollers may be permitted with the approval of the Engineer. No rollers or construction equipment shall be permitted to park on the completed work.

The road shall not be opened to traffic until the bitumen has attained sufficient viscosity to prevent stones being removed, and not earlier than 24 hours in the case of the first application of chippings.

Unless allowed otherwise by the Engineer, the area shall not be opened to works traffic before the application of the full number of specified coats.

After traffic has been permitted to run on surface dressing for a period of at least a fortnight, all loose material shall be swept to the side, collected up and disposed of. No windrow of loose chippings shall be allowed to accumulate at the sides.

15.2.10 Asphaltic concrete surfacing

Asphaltic concrete surfacing courses shall comprise a mixture of well-graded aggregate, filler and penetration grade bitumen.

The coarse aggregate shall consist of clean crushed rock, as free as practicable from flat, elongated, soft and weathered pieces and dust, dirt and deleterious matter. It shall have an Aggregate Crushing Value not exceeding 25% and Flakiness Index less than 30%. The fine aggregate may consist of stone screenings or natural sand free from clay and organic matter. The filler may consist of cement, hydrated lime or stone dust. The bitumen shall be straight run of grade 80/100 penetration. The combined grading of aggregates and filler shall show a smooth grading curve parallel to and within the limit is set out below:

BS. Sieve size	Percentage passing	
	Wearing course	Base course
14mm	80-100	75-95
5mm	54-72	52-70
2.36mm	42-58	40-56
1.18mm	34-48	32-46
600 microns	26-38	24-36
300 microns	18-28	16-26
150 microns	12-20	10-18
75 microns	6-12	6-12

Bitumen content

In addition to the above requirements both wearing course and base course material shall when compacted exhibit the following Marshall test values:

Minimum stability 250kg
flow value, between 2 - 5 mm

Control testing to ensure compliance with these requirements shall be carried out as directed by the Engineer.

The surfacing material shall be mixed in a purpose-made mixing plant of the weigh batch or continuous mixing type in good order and approved by the Engineer, shall be transported to the works in clean covered vehicles and laid by a self-propelled mechanical

spreader/finisher without delay. The mix temperature when placed in the spreader shall not be less than 135°C, and the mix shall be rolled immediately after laying and before the temperature falls below 120°C.

Compaction shall be by an 8 - 10 tonne smooth-wheeled roller of roll width greater than 450mm or by pneumatic-tyred roller of equivalent mass. The material shall be rolled from side to centre in a longitudinal direction. Cold joints shall be formed on a new cut vertical face and painted with hot bitumen. Rolling shall continue until all roll marks are eliminated and 98% of the laboratory density is obtained. Rollers shall not stand on newly laid surfacing.

15.2.11 Kerbs, edgings and quadrants

Kerbs, edgings and quadrants may be supplied in precast concrete to BS. 340 or dressed hard stone to the approval of the Engineer. In the latter case, kerbs will be accepted without batter and in random lengths. They shall be bedded and haunched in concrete and the joints are to be pointed in 1:3 cement mortar. The price is to include for excavating; supplying; laying (to radius of required), jointing and back-filling and all materials necessary for completion.

15.2.12 White line markings:

White line markings where specified shall be painted in long life chlorinated rubber road marking paint.

16.0 ELECTRICAL INSTALLATION

16.1 TECHNICAL SPECIFICATIONS I

16.1.1 General Conditions

The Contractor shall use a qualified approved electrician to perform the Electrical works i.e. the Main Contractor is allowed to sublet electrical installation part to approved Electrical Contractor as domestic Sub-contractor.

This specification is to be read in conjunction with "General Conditions of the contract" and any general or particular specification and drawings listed in section six of this bidding documents.

Minor details not shown or specified herein but necessary for proper installation and operation shall be included in the Contractor's estimates.

Any apparatus, appliances, material or work not shown on drawings but mentioned in the specification or vice versa, or any incidental accessories necessary to make work complete and perfect in all respects and ready for operation, even if not particularly specified, shall be furnished delivered, and installed by the Contractor without any additional expense to the employer.

With submission of bid, the contractor shall give written notice to the Engineer of any materials or apparatus believed inadequate or unsuitable, in violation of laws, regulations, and any necessary item(s) or work omitted. In the absence of such notice, it is mutually agreed that the Contractor has included the cost of all required items in his proposal, and that he will be responsible for the approved satisfactory functioning of the entire system without extra compensation.

SECTION IX : BIDDER ELIGIBILITY



TPDF HQ/5025 - 30/11(CLE)

TANZANIA PEOPLE'S DEFENCE FORCES

Defence Forces Headquarters
P.O. Box 9203
DAR ES SALAAM

Telegrams: "NGOME"
Telephone: DSM 2150556/62
Telex : 241051
Telefax : 2153429

RE: Site Handing Over to Contractor Sub: Certificate

CONTRACT: CONSTRUCTION OF VIP WARD FOR GENERAL MILITARY HOSPITAL (GMH) AT 521KJ LUGALO DAR ES SALAAM

B. AUTHORITY: MMJ/5577-1 (NTB)-76

C. CONTRACTOR: M/S KUYELLA ENTERPRISES LTD
P.O BOX 2880 DAR ES SALAAM

D. CONTRACT SUM (TSHS): 775,768,000 (SEVEN HUNDRED SEVENTY FIVE MILLION SEVEN HUNDRED SIXTY EIGHT THOUSAND ONLY)

E. CONTRACT PERIOD: 17 WEEKS

F. DATE OF COMMENCEMENT: 26TH SEPTEMBER 2012

G. DATE OF COMPLETION: 23RD JANUARY 2013

H. DATE OF HANDING OVER SITE TO CONTRACTOR

Certified True Copy of the Original
Sign: Date: 21/12/2012
NAZARIO MICHAEL BUXAY
Advocate, Notary
Public & Commissioner for Oaths

The site has been handed over on this 12TH day of SEPTEMBER 2012 in the presence of BRIG GEN VT LYIMO (on behalf of TPDF) and Felix Kuyella (on behalf of contractor).

SIGNATURE WITH APPOINTMENTS

Brig Gen Vt Lyimo
FOR CLIENT

[Signature]
FOR CONSULTANT

[Signature]
FOR CONTRACTOR
KUYELLA ENTERPRISES LTD
BOX 2880
12 SEP 2012



TANZANIA PEOPLE DEFENCE FORCES

THE DIRECTORATE OF ESTATE DEVELOPMENT AND MAINTAINANCE (DED&M) OFFICE -DAR ES SALAAM

CERTIFICATE OF PRACTICAL COMPLETION

PROJECT : CONSTRUCTION OF VIP WARD FOR GMH AT 521KJ LUGALO-DSM

CONTRACT NO : MMJ/5577-1 (NTB)-76

CONSULTANT : MOD CONSULTING UNIT DAR ES SALAAM

CONTRACTOR : M/S KUYELLA ENTERPRISES LTD PO BOX 2880 DSM

DESCRIPTION OF WORKS : CONSTRUCTION OF VIP WARD FOR GMH 521KJ-LUGALO.

DECLARATION : *WE, THE UNDER SIGNED, DO CERTIFY THAT WE HAVE INSPECTED ALL THE WORKS AS STIPULATED IN THE CONTRACT AGREEMENT AND FOUND THAT ALL THE OBLIGATION HAVE BEEN FULFILLED WE THEREFORE CERTIFY THAT THE SAID PROJECT HAS BEEN COMPLETED TO OUR SATISFACTION ON THIS 1ST DAY OF MAR 2017 FROM WHICH THE DEFECT LIABILITY PERIOD IS GOING TO THE COUNTED WITH RECTIFICATION(S).*

Signed by or on Behalf of Consultant

Name MAS JOFREY MWAKASEGE (Signature)

Address Box 9303 DSM Position Asst. Mgr

Date 01 MAR 17

In the Presence or on Behalf of Employer

Name COL PM Masawe (Signature)

Address 521 KJ Position Asst. Dir

Date 01 Mar 17

Signed by or on Behalf of The Contractor

Name Felix Kuyella (Signature)

Address Box 2880 DSM Position Managing Director

Date 01/03/2017

Certified True Copy of the Original
Signed by _____ Date: 09/03/2017
NAZARIO MICHAEL BUXAY
Notary Public





TANZANIA PEOPLES' DEFENCE FORCES

THE DIRECTORATE OF ESTATE DEVELOPMENT & MAINTANANCE (DED & M) OFFICE - DAR ES SALAAM

CERTIFICATE OF MAKING GOOD DEFECTS

PROJECT NAME : CONSTRUCTION OF VIP WARD FOR GMH AT 521KJ LUGALO

CONTRACT NO. : MMJ/5577 - 1 (NTB) - 76 DATED 27th AUG, 2012

CLIENT : CHIEF OF DEFENCE FORCES P.O.BOX 9203 DAR ES SALAAM.

CONSULTANT : MOD CONSULTING UNIT DAR ES SALAAM.


CONTRACTOR : M/S KUYELLA ENTERPRISES LTD, P.O. BOX 2880 DAR ES SALAAM.

DESCRIPTION OF WORKS : CONSTRUCTION OF VIP WARD FOR GMH AT 521KJ LUGALO


DECLARATION : Under the terms of the above mentioned contract, we certify that all outstanding items and all defects and other faults which appeared during the defects liability period in respect of CONSTRUCTION OF VIP WARD FOR GMH AT 521KJ LUGALO

The Works were in our opinion completed and made good

Signed by or on behalf of Consultant


Name: CEL IIM HOEE (Signature) 
 Address: P.O. BOX 9203 DSM Position: DED & M
 Date: 03 MAY 18


In the Presence or on Behalf of Employer

Name: MAJ ER KAMUHANDA (Signature) 
 Address: PO BOX 60126 DSM Position: HOSPITAL ENGINEER
 Date: 03 MAY 18



Signed by or on Behalf of The Contractor

Name: FELIX KUTELWA (Signature) 
 Address: Box 2880 DSM Position: Managing Director
 Date: 03/05/2018

Certified True Copy of the Original
 Stamp: 
 Date: 2018/05/03

KALAMBO DISTRICT COUNCIL



COMPLETION CERTIFICATE

To:

(The Contractor)

M/S KUYELLA ENTERPRISES LIMITED
P.O. BOX 2880 DAR ES SALAAM

To:

(The Employer)

DISTRICT EXECUTIVE DIRECTOR,
KALAMBO DISTRICT COUNCIL,
P.O. BOX 3 MATAI, KALAMBO - TANZANIA

Contract no: LGA/097/KLB/RWSSP/W/2013/2014/01

Contract title: CONSTRUCTION OF PIPED WATER SUPPLY SCHEME AND CIVIL WORKS AT KISUMEA VILLAGE.


FINAL APPROVAL CERTIFICATE

The following is being issued to comply with the requirements of clause 58 of the General Conditions of Contract.

It is hereby certified that in accordance with the provisions of clause 58.1 of the General Conditions of Contract, that the above mentioned works have been completed and all defects have been corrected in accordance with the provisions of the Contract.

Certified by ,

Date: 31st August 2016


.....
E. Vincent
Project Manager



archplan international ltd

**Certificate of
PRACTICAL COMPLETION**

Issued by: ARCHPLAN INTERNATIONAL LTD
Address: P.O. BOX 76353 DAR ES SALAAM

Employer: GOODLUCK CHARLES LUKUMAY
Address: P.O. BOX 16092 DAR ES SALAAM

Serial No.01
Job reference:

Contractor: M/s KUYELLA ENTERPRISES LIMITED
Address: P.O. BOX 2880 DAR ES SALAAM

Issue date: 7th December 2016

Works: PROPOSED HOTEL BUILDING
Situating at: PLOT NO.12, BLOCK 35A, KINONDONI AREA,
KINONDONI MUNICIPALITY DAR ES SALAAM

Contract dated: 16TH NOVEMBER 2015

Under the terms of the above-mentioned Contract;

We hereby certify that the works have reached Practical Completion.

As such

- The Employer shall take possession of the works (Clause 18)
- The Employer shall be responsible for all insurances associated with the works (Clause 21.3)
- The Contractor shall attend to all snags and defects during the 12 month Defects Liability Period from the issue date indicated herein (Clause 17).

To be signed by
Or for the issuer
Named above

Signed:



Distribution:	Original to	Duplicate to	Copies to	
	<input checked="" type="checkbox"/> Employer	<input type="checkbox"/> Contractor	<input type="checkbox"/> Q/Surveyor	<input type="checkbox"/> Structural Engineer
			<input type="checkbox"/> S/Engineer	<input type="checkbox"/> File

List of Personnel

Qualifications and experience of key personnel proposed for administration and execution of the Contract. (CVs of all key proposed key personnel shall be attached)

S/N	Position	Name	Total work of Experience (Years)	Experience in in similar works
1.	CHIEF OF WORK	JAFARI ISSA KAMENYA	6 YEARS	6 YEARS
2.	PROJECT MANAGER-NO 1	MR. JOHN MODEST LEVIRA	15 YEARS	9 YEARS
3.	A SITE AGENT-NO 1	MR. SAID WILLIAM MSHANA	10 YEARS	9 YEARS
4.	ELECTRICAL TECHNICIAN -NO1	MR. GILBERT MWAMPEPO	9 YEARS	5 YEARS
5.	SERVICES TECHNICIANS (ICT/DATA/PLUMBING)- NO 3	MR. ATHUMAN K. MOHAMED	9 YEARS	9 YEARS

CURRICULUM VITAE

Kamenya, Jafari Issa

P.O. Box 78403 Dares Salaam, Tanzania

Contacts: +255 714 378379, +255 684 693949

Email: Jafari.kamenya@yahoo.com

PERSONAL DETAILS

Surname : Kamenya
First Name : Jafari
Middle Name : Issa
Birth date : 27th March, 1990
Nationality : Tanzanian
Marital Status : Single
Current Residence : Dar es Salaam.
Religion : Muslim
Contact : +255 714378379, +255 684693949
Email : Jafari.kamenya@yahoo.com

Personal Attributes

Dynamic and strongly committed person who can work in a multicultural environment and able to learn and understand new things easily, I am able to work independently under little or no supervision. Open to roles in different sectors and types of organizations. Self-motivated, committed, very determined, hardworking, reliable, honesty, loyal, good team mate and ability to work under pressure.

Key Skills:

- Diligence – Is well organized and meticulous in doing work and pays attention to detail.
- Research – Able to conduct and supervise research projects can organize and analyze both qualitative and quantitative data
- Teamwork – Can work well in a team, both as a team leader and a member of a team.

- Commitment – Take ownership of tasks that I am given and I make sure I see them through within the allocated time.

EDUCATIONAL BACKGROUND

YEAR	INSTITUTION	AWARD
2011-2015	Ardhi University	Bachelor of science in Civil Engineering.
2009-2011	Tabora Boys' High School (A- Level)	Advanced Certificate of Secondary Education Examination (ACSEE)
2005 – 2008	Forodhani Secondary School (O-Level)	Certificate of Secondary Education Examination (CSEE)
1998 – 2004	Kijitonyama Kisiwani Primary School	Certificate of Primary Education Examination(CPEE)

<p>Ardhi University 2011 - 2015</p>	<p>Bachelor of Science in Civil Engineering Major areas of study included: <i>Award the Bachelor of Science in Civil Engineering.</i></p> <p>Major Areas of Study Business aspects: Business Ethics, Introduction to Business Planning and Entrepreneurship</p> <p>Real Estate aspects: Real Estate Marketing and Agency, Property Investment, Property Finance, Corporate Finance (Risk and Return Analysis and Management), Estate and Property Management, Maintenance of the Built up Environment</p> <p>Legal aspects: Law of Contract, Land Law, Conveyance and Disposition, Administrative law, Land Use Planning Law and Land Administration</p> <p>Information Technology aspects: Introduction to Computer Application, Industrial Training, Introduction to Computer Application to Real Estate</p>
<p>Tabora Boy's High School 2011-2013</p>	<p>Advanced Level Education: <i>Award the Advanced Certificate of Secondary Education Examinations [ACSEE].</i></p> <p>Major areas of study included:</p>

	Physics Chemistry Advanced Mathematics General studies
Forodhani Secondary School 2005-2008	Ordinary Level Education: <i>Certificate of Secondary Education Examinations [CSEE]</i> <i>Certificate of Best Student.</i> Major areas of study included: Basic Mathematics Physics Chemistry Biology Mathematics English Kiswahili Civics Geography

COMPUTER LITERATE

- Microsoft office
- MS Project
- AUTOCAD Architecture
- AUTOCAD
- AUTOCAD Civil 3D
- MASTERSERIES Design Software

LANGUAGES AND DEGREE OF PROFIENCY

Language	Speaking	Reading	Writing
English	Fluent	Excellent	Excellent
Swahili	Fluent	Excellent	Excellent

MEMBERSHIP IN PROFESSIONAL ASSOCIATIONS

- Engineers Registration Board (ERB)
-Graduate Engineer Reg. No. 9254
- Engineers Institution of Tanzania
-Graduate Engineer

PROFESSIONAL EXPERIENCE

Firm	Year	Activity
Kuyela Enterprises Ltd.	2013	<ul style="list-style-type: none"> • 1st Phase Kisarawe DCG Terminal Project: Proposed Kisarawe DCG Terminal Warehouses on plot no. 3,4 And 5 Block B at Kisarawe Coast Region. Period: July, 2013 to October, 2013 Client: DSM Corridor Group (DCG) Consultant: Galaxy Project Services Ltd. Position: Supervisor Involvement: -Supervising cut and fills levels preparation for Construction. -Managing schedules for excavator, wheel loader and Bulldozer. -Supervising construction of one store site camp. • 2nd Phase Kisarawe DCG terminal Project: Proposed Kisarawe DCG Terminal Warehouses on plot no. 3, 4 And 5 Block B at Kisarawe Coast Region. Period: October, 2014 to November, 2015 Consultant: Galaxy Project Services Ltd. Position: Site Engineer Involvement: - Structural design and detailing. -Engineering Management -Soil investigation -Project Management Achievement: <ul style="list-style-type: none"> • Designed and detailed structural elements of the building as per British Standards code of practice whereby environmental, safety, economic and aesthetics aspects were considered. • Prepared reinforcement steel bar bending schedule for all

Kuyella Enterprises Ltd.

- structural elements.
- Gained confidence in writing engineering specifications for instance of materials strength and type and construction methodologies.
- Investigating of soil type, condition and adequate depth of foundation on site through trial excavation, observing a soil profile, as a result established a depth on which foundation rested.
- Prepared extra working drawings in order to accommodate variations/clarifications from an architect.
- Gain confidence in playing engineering roles in project team of client, architects, engineers and quantity surveyors so that teamwork and division of responsibilities is maintained.
- Approved a use of materials on site such as sand, aggregate, cement and blocks as a replacement of what was indicated in engineering specification.
- Managing quality of concrete and steel through cube testing and steel tests. This was done to see if construction is done according to required specification of strength of materials.
- Issued site instructions on site.
- Gained confidence in using computer software for structural design and project management.
- Formed a file tracking system in the office for hard files and soft files in order to easily get files when needed.

- **Project: Rehabilitation of the Chalinze Water Treatment Plant, Supply and Tertiary Distribution Network and Construction of Reservoirs in Chalinze Village.**

Period: April, 2017 to March, 2018

Client: Government of Tanzania

Consultant: WAPCOS Ltd.

Position Held: Site Engineer

Main project features: Involved in survey, investigation of Existing distribution system and proposed system, Rehabilitation of Existing four Water pumps Stations and Construction of 19 Reservoirs including intake System at WAMI.

Responsibilities:

- Field surveys for pipe works, designing, preparation of drawings, and cost estimations (BOQ) for proposed Relocation pipe and expansion work.
- Inspection of materials on sites; and Construction supervision of all expansion work (including trench excavation, pipes interconnections, backfilling and compaction, pressure tests following all engineering guidelines and standard).

- Check and approve completed works for the project.
- Reporting in the daily project activities;
- Familiarize with quality control documents applicable to the works such as the tender specification and use them as work bench mark for Construction of water storage tanks;
- Carry out instructions pertaining to works as directed in the Technical specifications;
- Supervision of all site works (Both Civil, Environmental and pipe works);
- Preparation contractors and sub-contractors payments certificates and advising the Client accordingly;
- Make Evaluation of physical progress against the planned schedule
- Supervise material testing at every stage; and Prepare project progress reports weekly, monthly and quarterly
- Monitoring of environmental aspects during construction and protection measures undertaken and propose mitigation measures where necessary to counteract environmental impairment due to construction activities.
- Prepare work as executed drawings and records, and operation manuals and assist to hand over the completed works to the client.
- Prepare a practical completion and outstanding defects Report for each construction contract supervised.
- Prepare a final Completion and Handover report for each construction contract supervised.
- Taking responsibility during Defect Reliability Period

- **Project: Construction of Two Auto Transformer Sub – Stations (ATS) in Dar es Salaam – Morogoro Railway Project.**

Period: June, 2019 to November, 2019

Client: Government of Tanzania

Employer: YAPI MERKEZ

Position Held: Individual Contractor

Main project features: The Construction of ATS which will be used in receiving power from Dar es Salaam main supply.

Responsibilities:

- Materials supply for the ATS
- Structural Construction and Supervision.

EXTRA CURRRICULUM ACTIVITIES

- Participating in community groups activities as a member and leader (religious and social groups)
- Physical exercise

PERSONAL QUALITIES

I'm a person who is responsible, zealous, daring, and confident, with much interest and ability to learn new things. A person with determination to accomplish his goals and at the same time serving the goals of the community. Furthermore am able to work as an individual and in group with minimum and necessary supervision.

REFEREES

1. Eng. Habib Haruna Kitova
Galaxy Project Services Ltd,
P.O Box 32600,
Dar es Salaam – Tanzania
Mobile: +255 655265627/ +255 754265627
Email: hbk@galaxy.go.tz

2. Eng Issa Ramadhani Mshana
AMIC Project Services Ltd,
P.O Box 33460
Dar es Salaam – Tanzania
Mobile: +255 719691486
Email: issa25b@yahoo.com

3. Eng. Abuu Juma Mtambo
TANESCO Tanzania
P.O. Box 124
Iringa-Tanzania
Mobile: +255 653054870

4. Dr. G. Mbatia
CPI-International & Ardhi University
P.O. Box 35176,
Dar es Salaam-Tanzania
Mobile: +255 712495510
E-mail: mbattageo@gmail.com

5. Dr. P Ndumbaro
Ardhi University
P.O. Box 35176,
Dar es Salaam-Tanzania
Mobile: +255 754886412

6. Eng. Mgoyela
Ardhi University
P.O. Box 35176,
Dar es Salaam-Tanzania
Mobile: +255 655294222

DECLARATION

I hereby declare to the best of my knowledge and belief, that the information I have provided is true, correctly and genuine describe me, my qualification and my experience and that I will be liable for any untrue information stated.

Jafari I. Kamenya



Date: 22nd Dec, 2021.



UNITED REPUBLIC OF TANZANIA



ENGINEERS REGISTRATION BOARD

Certificate of Registration

(Under the Engineers Registration Act, 1997)

It is hereby certified that

Jaßari Hamenya

having satisfied the requirements for registration as a

GRADUATE ENGINEER
(Trainee Engineer)

under the provisions of the Engineers Registration Act, 1997, was

registered as such on the 11th day of November, 2016

in the discipline of **Civil** engineering and was

given registration number **9254**

Sealed and given under our hands at Dar es Salaam

this 29th day of May, 2017.

Eng. P. Baroz
Ag.Registrar

Eng. Nuberis P. J. Nyange
Board Member

Eng. Prof. N. M. Lema
Chairman

ARDHI UNIVERSITY



This is to certify

that

Jafari Kamunya

having satisfied the requirements for the award of the

**BACHELOR OF SCIENCE
IN CIVIL ENGINEERING**

Lower Second

was admitted to the degree at a congregation
held in DAR ES SALAAM, on the

Twelfth day of December,

in the year Two Thousand and Fifteen

John B. Makera

Vice Chancellor



Samanga

Deputy Vice Chancellor
(Academic Affairs)

ARDHI UNIVERSITY

Phone : +255-22-2775447

Fax : +255-22-2775391

E-mail : dvcart@aru.ac.tz

Website : www.aru.ac.tz



P.O.Box 35176
DAR ES SALAAM
TANZANIA



TRANSCRIPT OF EXAMINATIONS RESULTS

Surname: KAMENYA		First Name: JAFARI		Middle Names:	
Sex: MALE	Country of Citizenship: TANZANIA	Permanent Address: P.O. BOX 32600, DAR ES SALAAM			
Registration No: 3572/T.2011	Date of Birth: 1990-03-27	Admitted: 2011		Completed: 2015	
College or Campus: ARDHI UNIVERSITY			School or Institute: SCHOOL OF CONSTRUCTION ECONOMICS AND MANAGEMENT		
Name of Programme : BACHELOR OF SCIENCE - CIVIL ENGINEERING					
Overall G.P.A : 3.1			Degree Class : LOWER SECOND		

EXAMINATIONS RESULTS

FIRST YEAR EXAMINATIONS RESULTS

Course Code	Course Title	Units	Grade	Points	GPA
CE 101	ENGINEERING DRAWING I	2.0	A	10	
CE 111	ENGINEERING MECHANICS (STATICS)	2.0	A	10	
CE 151	BUILDING DESIGN AND CONSTRUCTION	4.0	C	8	
DS 101	DEVELOPMENT PERSPECTIVES I	2.0	B	6	
EG 100	WORKSHOP TRAINING	2.0	B-	6	
EI 111	ENGINEERING MATHEMATICS I	2.0	A	10	
GM 116	LAND SURVEYING I	4.0	B	12	
LS 106	COMMUNICATION SKILLS	2.0	C	4	
CE 102	INTRODUCTION TO COMPUTERS AND PROGRAMMING	3.0	A	15	
CE 112	ENGINEERING MECHANICS (DYNAMICS)	2.0	A	10	
CE 161	CONSTRUCTION MATERIALS I	4.0	B	12	
DS 102	DEVELOPMENT PERSPECTIVES II	2.0	B+	8	
GM 117	LAND SURVEYING II	3.0	B	9	
LS 107	COMMUNICATION SKILLS II	2.0	B+	8	
Sub-total		36		128	3.5

SECOND YEAR EXAMINATIONS RESULTS


Course Code	Course Title	Units	Grade	Points	GPA
CE 185	INDUSTRIAL TRAINING I	2.0	B+	8	
CE 201	ENGINEERING DRAWING II (CAD)	3.0	A	15	
CE 211	MECHANICS OF MATERIALS	2.0	C	4	
CE 232	FLUID MECHANICS	2.0	B+	8	
CE 262	CONSTRUCTION MATERIALS II	4.0	C	8	
EI 213	ENGINEERING MATHEMATICS II	2.0	B+	8	
EI 233	HYDROLOGY	3.0	C	6	
CE 212	STRUCTURAL ANALYSIS I	2.0	B+	8	
CE 222	TRAFFIC ENGINEERING AND PLANNING	2.0	B	6	
CE 223	HIGHWAY ENGINEERING	2.0	C	4	
CE 262	SEMESTER PROJECT I	3.0	A	15	
EI 214	ENGINEERING MATHEMATICS III	2.0	C	4	
EI 223	WATER RESOURCES AND TRANSPORTATION ENGINEERING	3.0	C	6	
EI 375	PUMPS AND PUMPING STATIONS	2.0	B+	8	
Sub-total		34		106	3.1

THIRD YEAR EXAMINATIONS RESULTS

Course Code	Course Title	Units	Grade	Points	GPA
CE 285	INDUSTRIAL TRAINING II	2.0	B+	8	
CE 312	STRUCTURAL ANALYSIS II	2.0	A	10	
CE 315	DESIGN OF TIMBER STRUCTURES	2.0	B+	8	
CE 316	DESIGN OF STEEL STRUCTURES	2.0	B	6	
CE 333	WASTEWATER ENGINEERING	4.0	B	12	
CE 381	SEMESTER PROJECT II	3.0	B+	12	
EI 132	SOIL MECHANICS AND GEOLOGY	2.0	B	6	
EI 395	HYDRAULIC STRUCTURES	2.0	B	6	
CE 301	QUANTITATIVE METHODS AND RESEARCH METHODOLOGY	2.0	B	6	
CE 317	DESIGN OF REINFORCED CONCRETE STRUCTURES	3.0	B	9	
CE 318	DESIGN OF MASONRY STRUCTURES	1.0	C	2	
CE 342	FOUNDATION ENGINEERING	2.0	B	6	
CE 351	CONSTRUCTION MANAGEMENT I	3.0	C	6	
CE 382	SEMESTER PROJECT III	2.0	B+	8	
CE 416	STRUCTURAL DYNAMICS AND EARTHQUAKE ENGINEERING	2.0	C	4	
CE 417	DESIGN OF BRIDGES	2.0	B+	8	
Sub-total		36		117	3.2

FOURTH YEAR EXAMINATIONS RESULTS

Course Code	Course Title	Units	Grade	Points	GPA
BE 447	ENTREPRENEURSHIP	2.0	B	6	
CE 385	INDUSTRIAL TRAINING III	2.0	B+	8	
CE 425	PAVEMENT MAINTENANCE AND REHABILITATION	2.0	C	4	
CE 429	TRANSPORTATION ECONOMICS	2.0	C	4	
CE 451	CONSTRUCTION MANAGEMENT II	2.0	A	10	
CE 452	CONSTRUCTION TECHNOLOGY	2.0	B+	8	
CE 453	PROFESSIONAL PRACTICE	2.0	B+	8	
CE 481	SEMESTER PROJECT IV	3.0	C	6	
CE 499	DISSERTATION	15.0	C	30	
Sub-total		32		84	2.6



Deputy Vice Chancellor
Academic Affairs

10-05-2016

Date

OFFICIAL SEAL

***** END OF TRANSCRIPT *****

1. The transcript will be valid only if it bears the University Seal.

2. Key to the Grades and other Symbols for University Examinations: SEE THE TABLE BELOW

Grade	A	B+	B	C	D	E
Marks	70 - 100%	60 - 69%	50 - 59%	40 - 49%	34 - 39%	0 - 34%
Grade Points	5.0	4.0	3.0	2.0	1.0	0.0
Remarks	Excellent	Very Good	Good	Satisfactory	Marginal Fail	Absolute Fail

3. Key to Classification of Awards: SEE THE TABLE BELOW

Degree	
Overall G.P.A.	Class
4.4 - 5.0	FIRST
3.5 - 4.3	UPPER SECOND
2.7 - 3.4	LOWER SECOND
2.0 - 2.6	PASS

The National Examinations Council of Tanzania



Advanced Certificate of Secondary Education

This is to certify that **JAFARI KAMENYA**

Index No. **50155-0571**

sat for the Advanced Certificate of Secondary Education Examination
at **TABORA BOYS SECONDARY SCHOOL** in **FEBRUARY 2011**

and qualified for the award of an
ADVANCED CERTIFICATE OF SECONDARY EDUCATION
in Division **TWO**

after attaining the following performance:-

Subject	Grade
GENERAL STUDIES	S (PASS)
PHYSICS	C (PASS)
CHEMISTRY	C (PASS)
ADVANCED MATHEMATICS	E (PASS)

[Signature]
Chairperson

[Signature]
Executive Secretary

This is a secure document using special inks and paper. Hold this document to the light to verify the NECTA watermark and security thread can be seen through the paper. Any alteration or amendment to

AC11 001966R



The National Examinations Council of Tanzania



Certificate of Secondary Education

This is to certify that **JAFARI KAMENYA**

Index No. **S0311-0218**

sat for the Certificate of Secondary Education Examination

at **FORODHANI SECONDARY SCHOOL**

in **OCTOBER 2008**


and qualified for the award of a

CERTIFICATE OF SECONDARY EDUCATION

in Division **ONE**

after attaining the following performance:-

Subject	Grade
BASIC MATHEMATICS	B (PASS)
BIOLOGY	C (PASS)
ENGLISH LANGUAGE	D (PASS)
PHYSICS	A (PASS)
CHEMISTRY	A (PASS)
GEOGRAPHY	D (PASS)
KISWAHILI	C (PASS)
HISTORY	D (PASS)
CIVICS	C (PASS)


Chairperson


Executive Secretary

This is a secure document using special inks and paper. Hold this document to the light to verify the NECTA watermark and security thread can be seen through the paper. Any alteration or amendment to

CS080049944



THE UNITED REPUBLIC OF TANZANIA

CERTIFICATE OF BIRTH

B No 00491357

(1)	No. of entry	31651/2002
(2)	Where born	AGA KHAN HOSPITAL DAR ES SALAAM
(3)	Name if any	JAFARI
(4)	Sex	MALE
(5)	Name and surname of father	ISSA KAMENYA
(6)	Father's occupation and residence	SITE AGENT DAR ES SALAAM
(7)	Father's Nationality	CITIZEN OF TANZANIA
(8)	Name and maiden name of mother	BLANDINA OBASSY MWASABWITE
(9)	Mother's Occupation and residence	BUSINESSWOMAN DAR ES SALAAM
(10)	Mother's Nationality	CITIZEN OF TANZANIA
(11)	Signature, description and residence of informant	SGD. BLANDINA O. MWASABWITE MOTHER OF CHILD DAR ES SALAAM
(12)	Date of birth	TWENTY SEVENTH MARCH 1990
(13)	Date of registration	FIFTEENTH MAY 2002
(14)	Signature of registering officer	SGD. C.O. KAISI
(15)	Baptismal name added or alias registration	

Certified under the Births and Deaths Registration Ordinance (Cap. 108 of the Laws), to be a true Copy of an entry in the register in my custody of Birth for District of ILALA in Tanzania.

Dated this 15TH day of MAY 2002

GPP-Dsm
Fee Paid Shs. 250/-

DISTRICT REGISTRAR
DAR ES SALAAM
DISTRICT REGISTRAR

C/No. 42280



المجلس الأعلى للشؤون الإسلامية بـتـنـزانيا

BARAZA KUU LA WAISLAMU WA TANZANIA (BAKWATA) 

THE NATIONAL MUSLIM COUNCIL OF TANZANIA

قال رسول الله صلى الله عليه وسلم
النكاح من سنتي فمن رغب عن سنتي فليس مني

Shahada ya Ndoa وثيقة النكاح
CERTIFICATE OF MARRIAGE

MTAA / STREET	شارع	MKOA / REGION	محافظة	NCHI / COUNTRY	دولة
MAHEAU STREEET		MOROGORO		TANZANIA	
Majira ya wafunga ndoa / Names of Parties	اسم الزوج و الزوجة	عمر / Age	محل الإقامة / Residence	اسم الأب / Father's Name	
1. JAFAR ISSA		26	DAR	ISAHAKAMENYA	
2. AZIZA SHABAN		23	DAR	SHABAN KISWIR	
Walili wa mke aifungia ndoa / Father / Authorized person to contract marriage	قولي الذي تولى عقد النكاح	Jina / Name	الإسم	Sahibi / Signature	
Makazi / Amount	مقدم المعهر / Given	الاسم والشهر	الإسم والشهر		
MAHARI/ DOWRY	مؤخر المعهر / Balance	Mashahidi / Witnesses	الإسم والشهر		
900,000/-	700,000/-	2. RAJABU OMARI			

Ndoa hii imefungwa kwa misingi ya Kislamu. Hivyo maisha ya ndoa, talaka na mirathi vitafuata maadili
This marriage has been contracted under Islamic law. So bond, divorcing, inheritance must follow Islamic law.

Saini ya Waliofungwa ndoa / Contract less Signature
Mume / Husband
Mke / Wife

الإسم
التوقيع



JAMHURI YA MUUNGANO WA TANZANIA

WIZARA YA ELIMU

SHULE YA SEKONDARI YA WAVULANA

TABORA

Hati ya Kufanya Vizuri

Hii ni kuthibitisha kwamba

..... JARAFI KAMUSYA... wa kidato cha V.....

Anehudhuria mafunzo ya Sekondari tangu 2009

..... mpaka 2011

na katika muda huo anejitokeza katika

KUSHIRIKI UKARABATI WA MAKYARA NA BEADS INTERNATIONAL


KUTOKA UINGEREZA.

na kufanya vizuri zaidi kuliko wengine.



MWALIMU MLEZI

TAREHI 31/08/2009



MKUU WA SHULE
SHULE YA SEKONDARI YA WAVULANA
MKUU WA SHULE

TAREHI 31/08/2009

2019	TO DATE	<p>COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.</p> <p>PROJECT: PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM.</p> <p>POSITION: PROJECT MANAGER</p> <p>To attend site meetings, inspection of works, coordination and assisting the project engineer in preparation and/or revising working programs, preparation of safety plans, cash flow/budgeting.</p> <p>RELEVANT TECHNICAL AND MANAGEMENT:</p> <ul style="list-style-type: none"> • To oversee construction projects from beginning to end • To manage the budget and estimate costs, • To determine the necessary equipment, materials, and manpower needed • To keep track of inventory, tools and equipment, • To ensure supplies and equipment are ordered and delivered according to schedule • To prepare reports regarding job status, • To resolve any problems that may arise, • To ensure compliance with safety regulations and building codes, • To evaluate risks, • Train and mentor construction workers and construction laborers depending on the size of the project, • To collaborate with subcontractors, engineers, architects and key team members of the project team, • To negotiate with external vendors on contract agreements, • To obtain the appropriate permits and licenses from authorities for construction sites, • To plan construction operations, • To ensure all deadlines are met, • To hire contractors and staff including construction laborers, • To delegate responsibilities, • To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects, • Keep all stakeholders aware of the progress on projects and prepare progress reports regularly • Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate. • Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.
------	---------	---

		PERSONNEL INFORMATION	
		NAME: JOHN MODEST LEVIRA	DATE OF BIRTH 02/10/1983
FROM*	TO*	COMPANY, PROJECT, POSITION, AND RELEVANT TECHNICAL AND MANAGEMENT EXPERIENCE*	

2019	TO DATE	<p>COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.</p> <p>PROJECT: PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM.</p> <p>POSITION: PROJECT MANAGER</p> <p>To attend site meetings, inspection of works, coordination and assisting the project engineer in preparation and/or revising working programs, preparation of safety plans, cash flow/budgeting.</p> <p>RELEVANT TECHNICAL AND MANAGEMENT:</p> <ul style="list-style-type: none"> • To oversee construction projects from beginning to end • To manage the budget and estimate costs, • To determine the necessary equipment, materials, and manpower needed • To keep track of inventory, tools and equipment, • To ensure supplies and equipment are ordered and delivered according to schedule • To prepare reports regarding job status, • To resolve any problems that may arise, • To ensure compliance with safety regulations and building codes, • To evaluate risks, • Train and mentor construction workers and construction laborers depending on the size of the project, • To collaborate with subcontractors, engineers, architects and key team members of the project team, • To negotiate with external vendors on contract agreements, • To obtain the appropriate permits and licenses from authorities for construction sites, • To plan construction operations, • To ensure all deadlines are met, • To hire contractors and staff including construction laborers, • To delegate responsibilities, • To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects, • Keep all stakeholders aware of the progress on projects and prepare progress reports regularly • Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate. • Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.
------	---------	---

2017

2018

COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.

PROJECT: PROPOSED 7 STOREYS AND BASEMENT RESIDENTIAL COMMERCIAL BUILDING AT KAWE-DAR ES SALAAM.

POSITION: PROJECT MANAGER

RELEVANT TECHNICAL AND MANAGEMENT:

- To oversee construction projects from beginning to end
- To manage the budget and estimate costs,
- To determine the necessary equipment, materials, and manpower needed
- To keep track of inventory, tools and equipment,
- To ensure supplies and equipment are ordered and delivered according to schedule
- To prepare reports regarding job status,
- To resolve any problems that may arise,
- To ensure compliance with safety regulations and building codes,
- To evaluate risks,
- Train and mentor construction workers and construction laborers depending on the size of the project,
- To collaborate with subcontractors, engineers, architects and key team members of the project team,
- To negotiate with external vendors on contract agreements,
- To obtain the appropriate permits and licenses from authorities for construction sites,
- To plan construction operations,
- To ensure all deadlines are met,
- To hire contractors and staff including construction laborers,
- To delegate responsibilities,
- To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects,
- Keep all stakeholders aware of the progress on projects and prepare progress reports regularly
- Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate.
- Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.

2017	2018	<p>COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.</p> <p>PROJECT: PROPOSED CONSTRUCTION OF STUDENT HOSTEL, RESTAURANT AND OFFICE & SHOPS AT RAU URBAN VILLAGE IN MOSHI- KILIMANJARO.</p> <p>POSITION: PROJECT MANAGER</p> <p>RELEVANT TECHNICAL AND MANAGEMENT:</p> <ul style="list-style-type: none"> • To oversee construction projects from beginning to end • To manage the budget and estimate costs, • To determine the necessary equipment, materials, and manpower needed • To keep track of inventory, tools and equipment, • To ensure supplies and equipment are ordered and delivered according to schedule • To prepare reports regarding job status, • To resolve any problems that may arise, • To ensure compliance with safety regulations and building codes, • To evaluate risks, • Train and mentor construction workers and construction laborers depending on the size of the project, • To collaborate with subcontractors, engineers, architects and key team members of the project team, • To negotiate with external vendors on contract agreements, • To obtain the appropriate permits and licenses from authorities for construction sites, • To plan construction operations, • To ensure all deadlines are met, • To hire contractors and staff including construction laborers, • To delegate responsibilities, • To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects, • Keep all stakeholders aware of the progress on projects and prepare progress reports regularly • Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate. • Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.
------	------	--

2016	2017	<p>COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.</p> <p>PROJECT: PROPOSED CONSTRUCTION OF COMMERCIAL BUILDING-CLOCK TOWER SHOPPING CENTRE.</p> <p>POSITION: PROJECT MANAGER</p> <p>RELEVANT TECHNICAL AND MANAGEMENT:</p> <ul style="list-style-type: none"> • Develop written procedures for quality control/quality assurance. • Perform needed tests on site and in the laboratory to ensure conformity of material and works according to the contract specifications. • Supervision of the contractors in the implementation of the work. • Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate. • Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA
------	------	---

2016

2018

COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.

PROJECT: PROPOSED REHABILITATION OF EXTERNAL WATER ARTICULATION & WATER TANKS AT AIR FORCE BASE - NGERENGERE

POSITION: PROJECT MANAGER

RELEVANT TECHNICAL AND MANAGEMENT:

- To oversee construction projects from beginning to end
- To manage the budget and estimate costs,
- To determine the necessary equipment, materials, and manpower needed
- To keep track of inventory, tools and equipment,
- To ensure supplies and equipment are ordered and delivered according to schedule
- To prepare reports regarding job status,
- To resolve any problems that may arise,
- To ensure compliance with safety regulations and building codes,
- To evaluate risks,
- Train and mentor construction workers and construction laborers depending on the size of the project,
- To collaborate with subcontractors, engineers, architects and key team members of the project team,
- To negotiate with external vendors on contract agreements,
- To obtain the appropriate permits and licenses from authorities for construction sites,
- To plan construction operations,
- To ensure all deadlines are met,
- To hire contractors and staff including construction laborers,
- To delegate responsibilities,
- To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects,
- Keep all stakeholders aware of the progress on projects and prepare progress reports regularly
- Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate.
- Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.

2012

2016

COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.

PROJECT: PROPOSED OF SHOPPING TERMINAL AT MAKUMBUSHO AREA IN DAR ES SALAAM

POSITION: PROJECT MANAGER

RELEVANT TECHNICAL AND MANAGEMENT:

- To oversee construction projects from beginning to end
- To manage the budget and estimate costs,
- To determine the necessary equipment, materials, and manpower needed
- To keep track of inventory, tools and equipment,
- To ensure supplies and equipment are ordered and delivered according to schedule
- To prepare reports regarding job status,
- To resolve any problems that may arise,
- To ensure compliance with safety regulations and building codes,
- To evaluate risks,
- Train and mentor construction workers and construction laborers depending on the size of the project,
- To collaborate with subcontractors, engineers, architects and key team members of the project team,
- To negotiate with external vendors on contract agreements,
- To obtain the appropriate permits and licenses from authorities for construction sites,
- To plan construction operations,
- To ensure all deadlines are met,
- To hire contractors and staff including construction laborers;
- To delegate responsibilities,
- To allocate and manage resources to ensure that they are available when they are needed throughout the construction projects.
- Keep all stakeholders aware of the progress on projects and prepare progress reports regularly
- Assess work activities for which labor based construction methods are appropriate and for those sections where heavy machinery is appropriate.
- Reporting directly to the Materials Engineer or Resident Engineer for the project as directed from time to time about the QC/QA.

PROFESSIONAL CERTIFICATES:

ENGINEERS REGISTRATION BOARD
TANZANIA



Certificate of Registration

(Under the Engineers Registration Act, 1997)

It is hereby certified that
John M. Levira

having satisfied the requirements for registration as a
GRADUATE ENGINEER
(Trainee Engineer)

under the provisions of the Engineers Registration Act, 1997, was
registered as such on the 06th day of May, 2011

in the discipline of **Civil** engineering and was

given registration number **4550**

sealed and given under our hands at Dar es Salaam

the 21st day of June, 2011

Eng. S. D. M. Mwak
Registrar

Eng. Prof. H. M. Lemu
Chairman

Eng. Dr. E. V. Silebi
Board Member

The validity of this certificate is three years and expires on 06th day of May, 2014

		PERSONNEL INFORMATION	
		NAME: SAID WILLIAM MSHANA	DATE OF BIRTH 22/03/1981
FROM*	TO*	COMPANY, PROJECT, POSITION, AND RELEVANT TECHNICAL AND MANAGEMENT EXPERIENCE*	
2013	TO DATE	<p>COMPANY: KUYELLA ENTERPRISES LIMITED</p> <p>PROJECT: PROPOSED CONSTRUCTION OF VIP WARD AT 512 KJ LUGALO MILITARY</p> <p>POSITION: A SITE AGENT</p> <p>RELEVANT TECHNICAL AND MANAGEMENT:</p> <ul style="list-style-type: none"> • Construction of Msalato Health center ministry of defense. • Construction of JKT Mlakuwa health center in Dar es Salaam. • Construction of Warehouse at Matimila Village in Songea District Council • Rehabilitation of Sonamco Warehouse in Ruvuma District. • Rehabilitation and Construction of Health and Safety Coordinator offices in Mbeya Cement Co. Limited. • Rehabilitation of Maintenance Block at Mbeya Cement Co. LTD • Construction of Oil interceptors at Mbeya Cement co. LTD • Construction of Bag Filter foundation at Mbeya Cement Co. LTD • Construction of Rice Husks Warehouse at Mbeya Cement Co. LTD • Construction of UDEM office container at Kibaha Municipal Council • Rehabilitation works along Mlowo – Kamsamba Regional Roads • Periodic Maintenance works along Saza – Kapalala Regional roads • Upgrading of Stand – Bomani road to double surface dressing at Same Municipal Council. 	

2009

2010

COMPANY: PWANI BUILDING CONTRACTORS LIMITED.

PROJECT: PROPOSED CONSTRUCTION OF VIP WARD AT 512 KJ LUGALO MILITARY

POSITION: A SITE AGENT

RELEVANT TECHNICAL AND MANAGEMENT:

- Renovation, Repair and Maintenance of Kariakoo Market Building At Ilala Municipal Council In Dar – Es –Salaam (MASOKO).
- Construction Of 2.0 Km Gravel Road From Kigale To Mnyampanda At Liwale District In Lindi Region.
- Construction of Luwangwa Bridge At Rungwe District Council
- Construction of Two Classrooms at Mama Mkapa Primary School In Ilala Municipal.
- Construction of Sidi Farm Health Center In Songea Municipal
- Construction of Azimio Irrigation Scheme Namtumbo District Council
- Construction of Kitanda Ward Extension Officers Resident Namtumbo District Council.

PROFESSIONAL CERTIFICATES:



UNITED REPUBLIC OF TANZANIA
ENGINEERS REGISTRATION
BOARD



Certificate
of Registration

(Under the Engineers Registration Act, 1997)

It is hereby certified that

Saidi William

having satisfied the requirements for registration as a

PROFESSIONAL ENGINEER

under the provisions of the Engineers Registration Act, 1997, was

registered as such on the 30th day of June, 2014

in the discipline of Civil engineering

and was given registration number 3868.


Scaled and given under our hands at Dar es Salaam

this 04th day of August, 2014.



Eng. S. D. M. Mute
Registrar




Eng. F. Klawoko
Board Member

UNIVERSITY OF DAR ES SALAAM



This is to certify

that

Saidi William

having satisfied the requirements for the award of the

DEGREE OF
BACHELOR OF SCIENCE IN CIVIL
AND STRUCTURAL ENGINEERING
WITH HONOURS.

Second Class, Upper Division

was admitted to the degree at a congregation

held in DAR ES SALAAM, on the

Fifth day of December,

in the year Two thousand and one

K. M. M. M. M. M.



Position*		ELECTRICAL TECHNICIAN	
Personnel information	Name *	GILBERT MWAMPEPO	
	Date of birth	03/09/1981	
Present employment	Professional qualifications *civil engineer, contract manager etc. submit professional certified certificate* REGISTERED ELECTRO MECHANICAL		
	Name of Employer: KUYELLA ENTERPRISES LIMITED		
	Address of Employer: PLOT NO. 40 KINONDONI AREA, URAMBO STREET, KINONDONI DISTRICT P.O.BOX 2880, DAR ES SALAAM, TANZANIA		
	Telephone: +255 (754) 023 359	Contact (manager / personnel officer) MR. FELIX KUYELA	
Fax	E-mail <u>kuyella@yahoo.com</u>		
Job title: ELECTRICAL & ICT /DATA TECHNICIAN	Years with present Employer 2016- TO DATE		

2019

TO DATE

COMPANY: KUYELLA ENTERPRISES LIMITED

PROJECT: PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM.

POSITION: ELECTRICAL TECHNICIAN

RELEVANT TECHNICAL AND MANAGEMENT:

- Formulation of design philosophy and concepts of service design (*Mechanical, Electrical design and ICT and Security*).
- Lighting design calculation and Lighting design installations.
- Preparing the detail design of Power, Data, Security systems, Fire detection systems and Telecommunications outlets points.
- Selection of suitable lighting fitting and Power fitting as well as its accessories.
- Design electrical service outlets Air conditioning, Ventilation fans, Extracting fans and water pumps system.
- Preparing the design of the main power supply including Transformers, Generators and Main, Sub main distribution panel.
- Preparing detail design for plumbing work (Wast water systems, water supply system, septic tank, soak away pit and water storage tanks).
- Preparing detail design for firefighting system (Horse reel, Sprinkler system and fire Hydrants).
- Preparing detail design for Air conditioning system, Ventilations system and cold rooms.
- Preparing budget estimate of the project, specifications, Bill of quantities and Tender document for both Electrical and Mechanical

2016

2018

COMPANY: KUYELLA ENTERPRISES LIMITED P.O. BOX 2880, DAR ES SALAAM.

PROJECT: PROPOSED REHABILITATION OF EXTERNAL WATER ARTICULATION & WATER TANKS AT AIR FORCE BASE - NGERENGERE

POSITION: ELECTRICAL TECHNICIAN

RELEVANT TECHNICAL AND MANAGEMENT:

- Formulation of design philosophy and concepts of service design (*Mechanical, Electrical design and ICT and Security*).
- Lighting design calculation and Lighting design installations.
- Preparing the detail design of Power, Data, Security systems, Fire detection systems and Telecommunications outlets points.
- Selection of suitable lighting fitting and Power fitting as well as its accessories.
- Design electrical service outlets Air conditioning, Ventilation fans, Extracting fans and water pumps system.
- Preparing the design of the main power supply including Transformers, Generators and Main, Sub main distribution panel.
- Preparing detail design for plumbing work (Wast water systems, water supply system, septic tank, soak away pit and water storage tanks).
- Preparing detail design for firefighting system (Horse reel, Sprinkler system and fire Hydrants).
- Preparing detail design for Air conditioning system, Ventilations system and cold rooms.
- Preparing budget estimate of the project, specifications, Bill of quantities, and Tender document for

2008

2016

COMPANY: EMIRATE BUILDERS CO. LIMITED

PROJECT: PROPOSED SHOWROOM AND SHOPPING COMPLEX FOR MR. VICENT WERIA TO BE BUILT ON PLOT NO 14, BLOCK 12, MJIMPYA.

POSITION: ELECTRICAL TECHNICIAN

RELEVANT TECHNICAL AND MANAGEMENT:

- Formulation of design philosophy and concepts of service design (*Mechanical, Electrical design and ICT and Security*).
- Lighting design calculation and Lighting design installations.
- Preparing the detail design of Power, Data, Security systems, Fire detection systems and Telecommunications outlets points.
- Proposed construction of Godown / showroom building for Dar ceramic centre to be built in Mbeya Region.
- Proposed Construction of Staff houses at Simiyu Districts in for Various Dispensaries/Health Centers.
- Proposed Construction of Staff Houses in Rural area Busega, Bariadi & Itilima Districts.

Position*		SERVICES TECHNICIANS (ICT/DATA/PLUMBING)	
Personnel information	Name *	ATHUMAN K. MOHAMED	
	Date of birth	09/01/1952	
	Professional qualifications *civil engineer, contract manager etc. submit professional certified certificate* FULL TECHNICIAN CERTIFICATE IN ELECTRONICS & TELECOMMUNICATIONS ENGINEERING.		
Present employment	Name of Employer: KUYELLA ENTERPRISES LIMITED		
	Address of Employer: PLOT NO. 40 KINONDONI AREA, URAMBO STREET, KINONDONI DISTRICT P.O.BOX 2880, DAR ES SALAAM, TANZANIA		
	Telephone: +255 (754) 023 359	Contact (manager / personnel officer) MR. FELIX KUYELA	
	Fax	E-mail kuyella@yahoo.com	
	Job title: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)	Years with present Employer 2017- TO DATE	

2019

TO
DATE

COMPANY: KUYELLA ENTERPRISES LIMITED

PROJECT: PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in Autocad and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

2017

2018

COMPANY: KUYELLA ENTERPRISES LIMITED

PROJECT: PROPOSED 7 STOREYS AND BASEMENT RESIDENTIAL COMMERCIAL BUILDING AT KAWE-DAR ES SALAAM.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in Autocad and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

2017

2018

COMPANY: KUYELLA ENTERPRISES LIMITED

PROJECT: PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in Autocad and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

2016

2017

COMPANY: EMIRATE BUILDERS COMPANY LIMITED

PROJECT: PROPOSED CONSTRUCTION OF STAFF HOUSES 10 UNITS IN HANANG – DC MANYARA. CONTRACT NO BMAF/GF/2014/15/W/01.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in Autocad and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

2014

2016

COMPANY: EMIRATE BUILDERS COMPANY LIMITED

PROJECT: PROPOSED CONSTRUCTION OF OBSTETRIC THEATERS IN SELECTED HEALTH FACILITIES CENTRE IN BARIADI (NGULYATI) AND BUSEGA (IGALUKILO DISTRICT COUNCIL).CONTRACT NO: BMF/MFP2/2015/216/W/01.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in Autocad and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

2011

2014

COMPANY: EMIRATE BUILDERS COMPANY LIMITED

PROJECT: CONSTRUCTION OF STAFF HOUSES IN SELECTED HEALTH FACILITIES IN RURAL AREAS. CONTRACT NO BMAF/GF/2013/14/W/03.

POSITION: SERVICES TECHNICIANS (ICT/DATA/PLUMBING)

RELEVANT TECHNICAL AND MANAGEMENT:

- Assist in the development of design approaches and concepts on assigned duties.
- Assist in the data collection and /or field verification
- Assist in the selection of equipment to fit the project design.
- Produce detailed plumbing and fire protection layouts in AutoCAD and Revit, based on applicable codes and standards.
- Produce plumbing fixture schedules and riser programs.
- Produce project based plumbing and fire protection specifications
- Ensure that all drawings are prepared with accuracy, neatness, and prior to project deadline.
- Communicate with team members, team leader, other disciplines, and outside vendors to obtain necessary information for drawings.
- Assist with on- site observations during construction and coordinate design requirements with contractors and equipment suppliers under the direction of project engineer.

KUYELLA ENTERPRISES LIMITED
 ACCOUNT STATEMENT (Jun 10, 2020 - Nov 23, 2021)



Kuyella Enterprises Limited I
 Londoni Dsm Address Line2

Account No: 56030030003068	Account Type:	CURRENT
	Currency:	TZS
	Opening Balance:	100,000.00
	Total Debit:	165,772,590.78
	Total Credit:	165,937,884.08
	Closing Balance:	165,293.30

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
10-Jun-2020	10-Jun-2020	CDB GRACE SOLOMON			100,000.00	100,000.00
10-Jun-2020	10-Jun-2020	CHEQUE FEE CHARGE 53100.000000 45000.000000		53,100.00		46,900.00
2-Jun-2020	12-Jun-2020	BRELLA SEARCH FEE		40,000.00		6,900.00
0-Jun-2020	30-Jun-2020	R10300700271975/ANTELOPE FREIGHT AND LOGISTICS LIM			4,000,000.00	4,006,900.00
01-Jul-2020	01-Jul-2020	CWB FELICIAN KUYELA		1,200,000.00		2,806,900.00
01-Jul-2020	01-Jul-2020	ARRANGEMENT FEE		1,575,476.88		1,231,423.12
2-Jul-2020	01-Jul-2020	WITHDRAWAL TRANSACTION CHARGES ON TZ401		1,200.00		1,230,223.12
2-Jul-2020	01-Jul-2020	VAT ON WITHDRAWAL CHARGES TZ401:01-07-2020		216.00		1,230,007.12
03-Jul-2020	03-Jul-2020	UBAT/GTE/20/047:UBAT GTEE 062 20 KUYELLA UBAT GTEE 062 20 KUYELLA		578,750.00		651,257.12



KUYELLA ENTERPRISES LIMITED

ACCOUNT STATEMENT (Jun 10 2020 - Nov 23 2021)



UBA
United Bank for Africa

560XXXX003068 - [CURRENT ACCOUNT - CORPORATE] - TZS

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
03-Jul-2020	03-Jul-2020	UBAT/GTE/20/047:18% VAT ON SWIFT TT 18% VAT ON SWIFT TT		104,175.00		547,082.12
30-Jul-2020	02-Aug-2020	FROM 01-AUG-20 TO 02-AUG-20		12,000.00		535,082.12
30-Jul-2020	02-Aug-2020	FROM 01-AUG-20 TO 02-AUG-20		2,160.00		532,922.12
24-Aug-2020	24-Aug-2020	CWB FELICIAN KUYELA	156401	430,000.00		102,922.12
25-Aug-2020	24-Aug-2020	VAT ON WITHDRAWAL CHARGES T2607/24-08-2020		77.40		102,844.72
25-Aug-2020	24-Aug-2020	WITHDRAWAL TRANSACTION CHARGES ON T2607		430.00		102,414.72
26-Aug-2020	26-Aug-2020	219605637ST3383/TANZANIA AIRPORT AUTHORITY			55,218,313.40	55,320,728.12
31-Aug-2020	02-Sep-2020	FROM 01-SEP-20 TO 02-SEP-20		12,000.00		55,308,728.12
31-Aug-2020	02-Sep-2020	FROM 01-SEP-20 TO 02-SEP-20		2,160.00		55,306,568.12
01-Sep-2020	01-Sep-2020	CWB FELICIAN KUYELA	156408	21,000,000.00		34,306,568.12
01-Sep-2020	01-Sep-2020	WITHDRAWAL TRANSACTION CHARGES ON T2293		21,000.00		34,285,568.12
01-Sep-2020	01-Sep-2020	VAT ON WITHDRAWAL CHARGES T2293		3,780.00		34,281,788.12
02-Sep-2020	02-Sep-2020	CWB FELICIAN KUYELA	156405	6,550,000.00		27,731,788.12
02-Sep-2020	02-Sep-2020	WITHDRAWAL TRANSACTION CHARGES ON T269		6,550.00		27,725,238.12
02-Sep-2020	02-Sep-2020	VAT ON WITHDRAWAL CHARGES T269		1,179.00		27,724,059.12
28-Sep-2020	28-Sep-2020	Bank Statement charges Fee for fical no: 4386723		2,360.00		27,721,699.12
30-Sep-2020	02-Oct-2020	FROM 01-OCT-20 TO 02-OCT-20		12,000.00		27,709,699.12



KUYELLA ENTERPRISES LIMITED
ACCOUNT STATEMENT (Jun 10, 2020 - Nov 23, 2021)




580xxxxx003068 (CURRENT ACCOUNT - CORPORATE) - TZ5

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
30-Sep-2020	02-Oct-2020	FROM 01-OCT-20 TO 02-OCT-20		2,160.00		27,707,539.12
30-Nov-2020	30-Nov-2020	FROM 01-NOV-20 TO 02-NOV-20		12,000.00		27,695,539.12
30-Nov-2020	30-Nov-2020	FROM 01-NOV-20 TO 02-NOV-20		2,160.00		27,693,379.12
31-Dec-2020	31-Dec-2020	FROM 01-DEC-20 TO 02-DEC-20		12,000.00		27,681,379.12
31-Dec-2020	31-Dec-2020	FROM 01-DEC-20 TO 02-DEC-20		2,160.00		27,679,219.12
19-Jan-2021	19-Jan-2021	Bank Statement charges Fee for ticket no: 4962167		2,360.00		27,676,859.12
29-Jan-2021	29-Jan-2021	FROM 01-JAN-21 TO 02-JAN-21		12,000.00		27,664,859.12
29-Jan-2021	29-Jan-2021	FROM 01-JAN-21 TO 02-JAN-21		2,160.00		27,662,699.12
26-Feb-2021	26-Feb-2021	FROM 01-FEB-21 TO 02-FEB-21		12,000.00		27,650,699.12
26-Feb-2021	26-Feb-2021	FROM 01-FEB-21 TO 02-FEB-21		2,160.00		27,648,539.12
24-Mar-2021	24-Mar-2021	2566401 175T3383/TANZANIA AIRPORT AUTHORIT			51,745,892.68	79,394,431.80
29-Mar-2021	29-Mar-2021	CWB FELICIAN KUYELA	156420	1,000,000.00		78,394,431.80
29-Mar-2021	29-Mar-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ152		1,000.00		78,393,431.80
29-Mar-2021	29-Mar-2021	VAT ON WITHDRAWAL CHARGES TZ152		180.00		78,393,251.80
29-Mar-2021	29-Mar-2021	CWB FELICIAN KUYELA	156421	10,000,000.00		68,393,251.80
29-Mar-2021	29-Mar-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ499		10,000.00		68,383,251.80
29-Mar-2021	29-Mar-2021	VAT ON WITHDRAWAL CHARGES TZ499		1,800.00		68,381,451.80



KUYELLA ENTERPRISES LIMITED

ACCOUNT STATEMENT (Jun 10, 2020 - Nov 23, 2021)



560xxxx003068 (CURRENT ACCOUNT - CORPORATE) - TZS

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
31-Mar-2021	31-Mar-2021	CWB FELICIAN KUYELA	156423	9,000,000.00		59,381,451.80
31-Mar-2021	31-Mar-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ477		9,000.00		59,372,451.80
31-Mar-2021	31-Mar-2021	VAT ON WITHDRAWAL CHARGES TZ477		1,620.00		59,370,831.80
31-Mar-2021	31-Mar-2021	FROM 01-FEB-21 TO 02-MAR-21		10,000.00		59,360,831.80
31-Mar-2021	31-Mar-2021	FROM 01-FEB-21 TO 02-MAR-21		1,800.00		59,359,031.80
31-Mar-2021	31-Mar-2021	FROM 01-FEB-21 TO 02-MAR-21		1,000.00		59,358,031.80
01-Apr-2021	01-Apr-2021	CWB FELIX KUYELA	28391	1,000,000.00		58,358,031.80
01-Apr-2021	01-Apr-2021	COUNTER CHQ CHARGE		20,000.00		58,338,031.80
01-Apr-2021	01-Apr-2021	VAT ON COUNTER CHQ		3,600.00		58,334,431.80
06-Apr-2021	06-Apr-2021	CWB FELICIAN KUYELA	156426	29,999,420.00		28,335,011.80
06-Apr-2021	06-Apr-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ147		29,999.00		28,305,012.80
06-Apr-2021	06-Apr-2021	VAT ON WITHDRAWAL CHARGES TZ147		5,399.90		28,299,612.90
30-Apr-2021	30-Apr-2021	FROM 01-APR-21 TO 02-APR-21		12,000.00		28,287,612.90
30-Apr-2021	30-Apr-2021	FROM 01-APR-21 TO 02-APR-21		2,160.00		28,285,452.90
06-May-2021	06-May-2021	CWB FELICIAN KUYELA	0156424	6,000,000.00		22,285,452.90
06-May-2021	06-May-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ355		6,000.00		22,279,452.90
06-May-2021	06-May-2021	VAT ON WITHDRAWAL CHARGES TZ355		1,080.00		22,278,372.90



KUYELLA ENTERPRISES LIMITED
ACCOUNT STATEMENT (Jun 10, 2020 - Nov 23, 2021)



UBA
United Bank for Africa

560xxxx00306B-(CURRENT ACCOUNT - CORPORATE) - TZS

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
10-May-2021	10-May-2021	CWB ADAM SALEHE	156428	4,000,000.00		18,278,372.90
10-May-2021	10-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T2302		4,000.00		18,274,372.90
10-May-2021	10-May-2021	VAT ON WITHDRAWAL CHARGES T2302		720.00		18,273,652.90
13-May-2021	13-May-2021	CWB ADAM SALEHE	0156430	3,000,000.00		15,273,652.90
13-May-2021	13-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T2318		3,000.00		15,270,652.90
13-May-2021	13-May-2021	VAT ON WITHDRAWAL CHARGES T2318		540.00		15,270,112.90
17-May-2021	17-May-2021	CWB ADAM SALEHE	0156429	5,000,000.00		10,270,112.90
17-May-2021	17-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T2134		5,000.00		10,265,112.90
17-May-2021	17-May-2021	VAT ON WITHDRAWAL CHARGES T2134		900.00		10,264,212.90
20-May-2021	20-May-2021	CWB ADAM SALEHE	0156422	3,000,000.00		7,264,212.90
20-May-2021	20-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T2230		3,000.00		7,261,212.90
20-May-2021	20-May-2021	VAT ON WITHDRAWAL CHARGES T2230		540.00		7,260,672.90
21-May-2021	21-May-2021	CWB ADAM SALEHE	0156427	4,000,000.00		3,260,672.90
21-May-2021	21-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T2259		4,000.00		3,256,672.90
21-May-2021	21-May-2021	VAT ON WITHDRAWAL CHARGES T2259		720.00		3,255,952.90
24-May-2021	24-May-2021	CWB ADAM SALEHE	0156425	1,000,000.00		2,255,952.90
24-May-2021	24-May-2021	WITHDRAWAL TRANSACTION CHARGES ON T284		1,000.00		2,254,952.90



KUYELLA ENTERPRISES LIMITED

ACCOUNT STATEMENT (Jun 10, 2020 - Nov 23, 2021)



560xxxx003068 (CURRENT ACCOUNT - CORPORATE) - TZS

TRANS DATE	VALUE DATE	NARRATION	CHQ. NO	DEBIT	CREDIT	BALANCE
24-May-2021	24-May-2021	VAT ON WITHDRAWAL CHARGES TZ84		180.00		2.25
25-May-2021	25-May-2021	CWB ADAM SALEHE	156419	1,700,000.00		5
25-May-2021	25-May-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ310		1,700.00		5
25-May-2021	25-May-2021	VAT ON WITHDRAWAL CHARGES TZ310		306.00		5
26-May-2021	26-May-2021	CWB SAID ADAM	156431	400,000.00		1
26-May-2021	26-May-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ368		400.00		1
26-May-2021	26-May-2021	VAT ON WITHDRAWAL CHARGES TZ368		72.00		
31-May-2021	31-May-2021	FROM 01-MAY-21 TO 02-MAY-21		12,000.00		
31-May-2021	31-May-2021	FROM 01-MAY-21 TO 02-MAY-21		2,160.00		
30-Jun-2021	30-Jun-2021	Bank Statement charges Fee for ticket no: 5819982		4,720.00		
30-Jun-2021	30-Jun-2021	FROM 01-JUN-21 TO 02-JUN-21		12,000.00		
30-Jun-2021	30-Jun-2021	FROM 01-JUN-21 TO 02-JUN-21		2,160.00		
30-Jul-2021	31-Jul-2021	FROM 01-JUL-21 TO 02-JUL-21		12,000.00		
30-Jul-2021	31-Jul-2021	FROM 01-JUL-21 TO 02-JUL-21		2,160.00		
31-Aug-2021	31-Aug-2021	FROM 01-AUG-21 TO 02-AUG-21		12,000.00		
31-Aug-2021	31-Aug-2021	FROM 01-AUG-21 TO 02-AUG-21		2,160.00		
02-Sep-2021	02-Sep-2021	5E07802109020368/LARSEN TOUBRO LIMITED			24,898,382.00	



KUYELLA ENTERPRISES LIMITED

ACCOUNT STATEMENT: (Jun 10, 2020 - Nov 23, 2021)



UBA
United Bank for Africa

560xxxxx003068 - (CURRENT ACCOUNT - CORPORATE) - TZS

TRANS DATE	VALUE DATE	NARRATION	CHQ NO	DEBIT	CREDIT	BALANCE
06-Sep-2021	06-Sep-2021	CDB FELICIAN KUYELA			3,000.00	24,992,316.90
06-Sep-2021	06-Sep-2021	CWB FELICIAN KUYELA	00156435	24,890,000.00		102,316.90
06-Sep-2021	06-Sep-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ124		24,890.00		77,426.90
06-Sep-2021	06-Sep-2021	VAT ON WITHDRAWAL CHARGES TZ124		4,480.20		72,946.70
06-Oct-2021	06-Oct-2021	CHQ CLEARING CHARGES/KUYELLA		590.00		72,356.70
06-Oct-2021	06-Oct-2021	CHQ000797/LARSEN/SCB/KUYELLA			5,272,598.00	5,344,954.70
06-Oct-2021	06-Oct-2021	CWB FELICIAN KUYELA	00156436	5,230,000.00		114,954.70
06-Oct-2021	06-Oct-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ261		5,230.00		109,724.70
06-Oct-2021	06-Oct-2021	VAT ON WITHDRAWAL CHARGES TZ261		941.40		108,783.30
27-Oct-2021	27-Oct-2021	SE07802110272448/LARSEN TOUBRO LIMITED			24,699,698.00	24,808,481.30
29-Oct-2021	29-Oct-2021	CWB FELICIAN KUYELA	156437	24,600,000.00		208,481.30
29-Oct-2021	29-Oct-2021	WITHDRAWAL TRANSACTION CHARGES ON TZ151		24,600.00		183,881.30
29-Oct-2021	29-Oct-2021	VAT ON WITHDRAWAL CHARGES TZ151		4,428.00		179,453.30
29-Oct-2021	29-Oct-2021	FROM 01-OCT-21 TO 02-OCT-21		12,000.00		167,453.30
29-Oct-2021	29-Oct-2021	FROM 01-OCT-21 TO 02-OCT-21		2,160.00		165,293.30





CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/29/2021 7:21:18 AM
 Printed By: HR Agwa
 Page Number: 1 of 30

Name: KUYELLA ENTERPRISES LTD
 Customer No: 001243016
 Address: P O BOX 2580 D'SALAAM
 MSIMBAZI / TWIGA STR - K KOO

Branch: 204 - Karakor
 Account Number: 2040000449
 Account Description: KUYELLA ENTERPRISES LTD,
 NMB-BUSINESS ACCOUNTS
 Account Class: 00102010
 Account Open Date: 2040000449
 Old Account Number: 025
 Account Currency: 01/01/2019
 From Date: 23/11/2021
 To Date:



Book Date	Value Date	Tr. B. Name	Description	Ref	Chq. or No.	Debit	Credit	Balance
01/01/2019			OPENING BALANCE			0	0	1,000,000.00
02/01/2019	02/01/2019	Ntd House	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01900241549 003	1025 18	990,000	0	10,000.00
02/01/2019	02/01/2019	Ntd House	007 Cheque Withdrawal fee - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01900241549 003	1025 18	3,430	0	6,569.97
02/01/2019	02/01/2019	Ntd House	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01900241549 003	1025 18	012	0	6,581.97
02/01/2019	02/01/2019	Ntd House	430 Balance Enquiry fee - Balance Enquiry Fee on 02-JAN-2019	2040000449		1,271.99	0	4,910.78
02/01/2019	02/01/2019	Ntd House	510 VAT Payable on Comm and Fees - Balance Enquiry Fee on 02-JAN-2019	2040000449		328.91	0	4,581.87
03/01/2019	03/01/2019	Kurash	430 Balance Enquiry fee - Balance Enquiry Fee on 02-JAN-2019	2040000449		1,271.99	0	3,210.78
03/01/2019	03/01/2019	Kurash	510 VAT Payable on Comm and Fees - Balance Enquiry Fee on 02-JAN-2019	2040000449		328.91	0	2,881.87
17/01/2019	17/01/2019	Naka	011 Inhouse Cheque Deposit - RTH TECHNOCON PRIVATE LIMITED From EARTH TECHNOCON PRIVATE LIMITED - KUYELLA ENTERPRISES LTD.	10004346524 9654		0	2,580,000	2,582,881.87
17/01/2019	17/01/2019	Siza	427 Bank Statement fee - on 17-JAN-2019	2040000449		3,305.05	0	2,405,770.00
17/01/2019	17/01/2019	Siza	510 VAT Payable on Comm and Fees - on 07-JAN-2019	2040000449		304.91	0	2,400,161.98
17/01/2019	17/01/2019	Siza	427 Bank Statement fee - on 07-JAN-2019	2040000449		10,151.89	0	2,482,060.29
17/01/2019	17/01/2019	Siza	510 VAT Payable on Comm and Fees - on 07-JAN-2019	2040000449		2,858.3	0	2,482,151.99


Printed From:



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 10:11:19 AM
 Printed By: n/n ngawo
 Page Number: 2 of 39

16/01/2019	16/01/2019	Nzige	516 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81901940392 412	1526 21	612	0	2,176,169.09
19/01/2019	19/01/2019	Nzige	006 Cash Cheque - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ81901940392 696	1526 20	2,190,000	0	16,162.99
19/01/2019	19/01/2019	Nzige	017 Cheque Withdrawal fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ81901940392 696	1526 20	3,400	0	12,769.99
19/01/2019	19/01/2019	Nzige	516 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ81901940392 696	1526 20	612	0	12,157.99
26/01/2019	26/01/2019	Nzige	416 Balance Enquiry fee - Balance Enquiry Fee on 26-JAN-2019	20406600440		1,271.10	0	10,886.8
26/01/2019	26/01/2019	Nzige	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 26-JAN-2019	20406600440		328.91	0	10,557.99
*25/01/2019	31/01/2019	Kariakoo	017 Cheque deposit - outside clearance - (EMBASSY OF RWANDA)	1090250	0070 70	6	1,500,000	1,510,657.09
31/01/2019	31/01/2019	Siiza	006 Cash Cheque - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81903143015 307	1526 22	1,400,000	0	20,657.99
31/01/2019	31/01/2019	Siiza	007 Cheque Withdrawal fees - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81903143015 307	1526 22	3,400	0	17,257.99
31/01/2019	31/01/2019	Siiza	516 VAT Payable on Comm and Fees - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81903143015 307	1526 22	612	0	16,645.99
31/01/2019	01/02/2019	Kariakoo	416 Monthly fee for Savings and Current Accounts -			13,000	0	3,645.99
31/01/2019	01/02/2019	Kariakoo	516 VAT Payable on Comm and Fees -			2,340	0	1,303.99
29/02/2019	29/02/2019	Nzige	011 Incoming Cheque Deposit - RTM TECHNOCCON PRIVATE LIMITED) From: CARTH TECHNOCCON PRIVATE LIMITED) - KUYELLA ENTERPRISES LTD.	651029106420 65140		0	1,847,100	1,848,447.99
29/02/2019	29/02/2019	Kariakoo	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81905940379 592	1526 15	1,840,000	0	6,407.99
29/02/2019	29/02/2019	Kariakoo	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81905940379 692	1526 15	5,804.47	0	2,053.52



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 7:31:18 AM
 Printed By: mungawa
 Page Number: 3 Of 25

Date	Period	Type	Description	Account No.	Amount	Balance	Balance
11/03/2019	11/03/2019	Receipt	011 Invoice Credit Deposit - RTH TECHNOCON PRIVATE LIMITED From EARTH TECHNOCON PRIVATE LIMITED ↔ KUYELLA ENTERPRISES LTD.	425002150306 6881	0	1,000,000	1,000,000
11/03/2019	11/03/2019	Debit	904 Balance Enquiry Commission - Balance Enquiry Fee on 09- MAR-2019	0118END19009 02UT	1,049.16	0	998,950.84
11/03/2019	11/03/2019	Debit	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 09-MAR-2019	0118END19009 02UT	350.34	0	648,600.50
11/03/2019	11/03/2019	Receipt	904 Balance Enquiry Commission - Balance Enquiry Fee on 19- MAR-2019	0118END19070 030	1,049.16	0	649,649.66
11/03/2019	11/03/2019	Debit	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 19-MAR-2019	0118END19070 030	350.34	0	300,000
11/03/2019	11/03/2019	Receipt	410 Monthly fee for Savings and Current Accounts -		11,076.01	0	311,076.01
11/03/2019	11/03/2019	Receipt	516 VAT Payable on Comm and Fees -		2,340	0	313,416.01
12/03/2019	12/03/2019	Debit	005 Cash Cheque - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81907144901 753	1526 26	0	12,021.99
12/03/2019	12/03/2019	Debit	007 Cheque Withdrawal Fee - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81907144901 753	1526 26	0	10,495.73
12/03/2019	12/03/2019	Debit	516 VAT Payable on Comm and Fees - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ81907144901 753	1526 26	0	8,969.47
12/03/2019	12/03/2019	Debit	904 Balance Enquiry Commission - Balance Enquiry Fee on 12- MAR-2019	2475END19071 02VN	1,949.16	0	7,020.31
12/03/2019	12/03/2019	Debit	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 12-MAR-2019	2475END19071 02VN	350.34	0	6,669.97
30/03/2019	01/04/2019	Receipt	410 Monthly fee for Savings and Current Accounts -		3,221.99	0	3,431.96
01/04/2019	01/04/2019	NMB Head Office	372 Incoming Funds Transfer - Sender's Ref: 130712911512416 ↔ Ordering Customer 011027842019 * TANZANIA BUS DRNGS EXPEND ↔ Remittance Info: FUNDS TRANSFER		0	61,268,135.58	61,268,135.58
			410 Monthly fee for Savings and Current				



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2011 7:31:19 AM
 Printed By: WJ1029WA
 Page Number: 4 of 39

Period	Transaction Type	Description	Reference	Debit	Credit	Balance
02/04/2019 - 02/04/2019	Stake	007 Cheque Withdrawal fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ51909245961 333	1526 27	5,506.47	61,170,509.11
02/04/2019 - 02/04/2019	Stake	510 VAT Payable on Comm and Fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ51909245961 333	1526 27	591.53	61,169,917.58
02/04/2019 - 02/04/2019	Stake	006 Cash Cheque - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ51909245969 139	1526 32	21,900,000	29,869,917.58
02/04/2019 - 02/04/2019	Stake	007 Cheque Withdrawal fees - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ51909245969 139	1526 32	32,460.5	29,837,457.08
02/04/2019 - 02/04/2019	Stake	510 VAT Payable on Comm and Fees - PAID FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ51909245969 139	1526 32	0,029.5	29,837,427.58
02/04/2019 - 02/04/2019	Stake	373 Commission on Funds Transfer - Sender's Ref 2477TQ019620001 => Ultimate Beneficiary: 0164071006 * KUYELLA ENTERPRISES LTD => Remittance Info: ROC KULIPA MKOPO			6,474.59	29,830,953.00
02/04/2019 - 02/04/2019	Stake	375 Outgoing Funds Transfer Cheque - Sender's Ref 2477TQ019620001 => Ultimate Beneficiary: 0164071006 * KUYELLA ENTERPRISES LTD => Remittance Info: ROC KULIPA MKOPO		1526 31	20,000,000	9,830,953.00
02/04/2019 - 02/04/2019	Stake	510 VAT Payable on Comm and Fees - Sender's Ref 2477TQ019620001 => Ultimate Beneficiary: 0164071006 * KUYELLA ENTERPRISES LTD => Remittance Info: ROC KULIPA MKOPO			1,526.42	9,829,426.58
02/04/2019 - 02/04/2019	Stake	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ51909246046 477	1526 34	3,900,000	5,929,426.58
02/04/2019 - 02/04/2019	Stake	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ51909246046 477	1526 34	5,506.47	5,885,709.11



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2021 7:31:19 AM
Printed By: nmb.rgr/wd
Page Number: 5 01/29

Table with columns for Date, Type, Description, Reference, Amount, and Balance. Rows include transactions such as '007 Cheque Withdrawal fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER/ OR From KUYELLA ENTERPRISES LTD.', '816 VAT Payable on Comm and Fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER/ OR From KUYELLA ENTERPRISES LTD.', '410 Monthly fee for Savings and Current Account -', '011 Income Cheque Deposit - RTH TECHNOCON PRIVATE LIMITED@ From EARTH TECHNOCON PRIVATE LIMITED @ KUYELLA ENTERPRISES LTD.', '006 Cash Cheque - Issued - Kuyella From KUYELLA ENTERPRISES LTD.', '007 Cheque Withdrawal fees - Issued - Kuyella From KUYELLA ENTERPRISES LTD.', '016 VAT Payable on Comm and Fees - Issued - Kuyella From KUYELLA ENTERPRISES LTD.', '004 Balance Enquiry Connected - Salem Enquiry Fee on 10-MAY-2019', '016 VAT Payable on Comm and Fees - Balance Enquiry Fee on 10-MAY-2019', '410 Monthly fee for Savings and Current Accounts -', '512 Excess Duty remission -', '016 VAT Payable on Comm and Fees -', '011 Income Cheque Deposit - RTH TECHNOCON PRIVATE LIMITED@ From EARTH TECHNOCON PRIVATE LIMITED @ KUYELLA ENTERPRISES LTD.', '006 Cash Cheque - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER/ OR From KUYELLA ENTERPRISES LTD.', and '007 Cheque Withdrawal fees - DRAWN BY FELICIAN EDWARD'.



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2021 7:31:19 AM
 Printed By: mhgpmw
 Page Number: 2 of 39

19/06/2019	21/06/2019	Karaoke	517 Cheque deposit - surward clearance - NATIONAL SERVICE CONVST DEB	119X155	7276 15	0	1,600,000	1,810,217.56
21/06/2019	21/06/2019	Siapa	005 Cash Cheque - FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD	FJ81917249719 373	1526 08	1,600,000	0	20,217.56
21/06/2019	21/06/2019	Siapa	007 Cheque Withdrawal fee - FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD	FJ81917249719 314	1023 08	5,508.47	0	14,709.11
21/06/2019	21/06/2019	Siapa	010 VAT Payable on Comm and Fees - FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD	FJ81917249719 318	1509 08	991.02	0	13,717.56
21/06/2019	21/06/2019	Siapa	004 Balance Enquiry Commission - Balance Enquiry Fee on 21- JUN-2019	247SENG19172 08GU		1,948.36	0	11,769.42
21/06/2019	21/06/2019	Siapa	010 VAT Payable on Comm and Fees - Balance Enquiry Fee on 21-JUN-2019	247SENG19172 08GU		350.84	0	11,417.56
29/06/2019	29/06/2019	Siapa	004 Balance Enquiry Commission - Balance Enquiry Fee on 29- JUN-2019	247SENG19180 0FAA		1,948.36	0	9,469.4
29/06/2019	29/06/2019	Siapa	010 VAT Payable on Comm and Fees - Balance Enquiry Fee on 29/06/2019	247SENG19180 0FAA		350.84	0	9,117.56
29/06/2019	29/06/2019	NMB Head Office	072 Incoming Funds Transfer - Sender's Ref 57VC19002372 => Ordering Customer - DEPENDENCE DEVELOPMENT ELECTRONIC => Remittance Info			0	572,901,394.77	572,910,412.35
29/06/2019	01/07/2019	Karaoke	419 facility fee for Savings and Current Accounts -			13,000	0	572,897,412.35
29/06/2019	01/07/2019	Karaoke	010 VAT Payable on Comm and Fees -			2,340	0	572,895,072.35
01/07/2019	01/07/2019	Siapa	005 Statement Enquiry Commission - Account Statement Enquiry Fee on 21-MAY-2019	247SENG19141 0ASF		49,152.39	0	572,845,919.96
01/07/2019	01/07/2019	Siapa	010 VAT Payable on Comm and Fees - Account Statement Enquiry Fee on 21- MAY-2019	247SENG19141 0ASF		8,847.32	0	572,837,072.64
01/07/2019	01/07/2019	Siapa	008 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD	FJ81918250216 979	1526 45	1,000,000	0	571,837,072.64
01/07/2019	01/07/2019	Siapa	007 Cheque Withdrawal fee - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD	FJ81918250216 979	1526 42	5,508.47	0	571,831,564.17
			010 VAT Payable on Comm and Fees -					



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 7:31:19 AM
 Printed By: admin@nmb
 Page Number: 1 of 25

02/07/2019	02/07/2019	Bank	371 Outgoing Funds Transfer - Drive Debit - @30-COL FEE 2040600449	1525 45	3,900,000	0	375,380,690.26
02/07/2019	02/07/2019	Bank	003 Cash Withdrawal - BY FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJR1918350342 024	13,200,000	0	362,180,690.26
02/07/2019	02/07/2019	Bank	004 Telex Withdrawal Fee - BY FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1918350342 024	13,248.4	0	362,167,441.86
02/07/2019	02/07/2019	Bank	516 VAT Payable on Comm and Fees - BY FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1918350342 024	2,490.6	0	362,164,951.26
02/07/2019	02/07/2019	Bank	FES TACH Charge - 2019_07_02_597185		2,000	0	362,162,951.26
02/07/2019	02/07/2019	Bank	003 Cash Withdrawal - CHQ BOOK ON PROCESS From KUYELLA ENTERPRISES LTD.	FJB1918350354 080	89,400,000	0	272,762,951.26
02/07/2019	02/07/2019	Bank	004 Telex Withdrawal Fee - CHQ BOOK ON PROCESS From KUYELLA ENTERPRISES LTD.	FJB1918350354 080	91,344.8	0	272,671,606.46
02/07/2019	02/07/2019	Bank	516 VAT Payable on Comm and Fees - CHQ BOOK ON PROCESS From KUYELLA ENTERPRISES LTD.	FJB1918350354 080	16,435.7	0	272,655,170.76
02/07/2019	02/07/2019	Bank	010 Cash Withdrawal - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918450376 905	26,860,000	0	245,795,170.76
02/07/2019	02/07/2019	Bank	004 Telex Withdrawal Fee - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918450376 905	27,141.62	0	245,768,029.14
02/07/2019	02/07/2019	Bank	516 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918450376 905	4,850.35	0	245,763,178.79
02/07/2019	02/07/2019	Bank	904 Balance Enquiry Commission - Balance Enquiry Fee on 03-JUL-2019	2475ENQ19194 0687	1,618.10	0	245,761,560.69
02/07/2019	02/07/2019	Bank	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 03-JUL-2019	2475ENQ19194 0687	250.84	0	245,759,309.85
02/07/2019	02/07/2019	Bank	371 Outgoing Funds Transfer - Drive Debit - @KULIPA MAMBOMBA M M INDUSTRIES LIMITED		58,500,500	0	187,258,809.35
04/07/2019	04/07/2019	Bank	006 Cash Cheque - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918600480 480	3,700,000	0	177,558,809.35
			007 Cheque Withdrawal Fee - FELICIAN From KUYELLA	FJB1918600480 480	1526 51		177,546,748.35



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2011 10:31:19 AM
 Printed By: w.r.gowda
 Page Number: 10 of 30

05/07/2010	05/07/2010	Bank	314 Outgoing Funds Transfer - Sender's Ref: 247FTOT101860003 => Ultimate Beneficiary / 0152206221330 * JOSEPH JAMES NDWILA => Residence Info: ROCKKULIPA, DENI			17,000.000	0	160,540,808.20
05/07/2010	05/07/2010	Bank	372 Incoming Int Funds Transfer - Sender's Ref: 247FTOT101860023 => Ultimate Beneficiary / 0152206221330 * JOSEPH JAMES NDWILA => Residence Info: ROCKKULIPA, DENI			5,474.55	0	160,535,423.88
05/07/2010	05/07/2010	Bank	510 VAT Payable on Comm and Fees - Sender's Ref: 247FTOT101860033 => Ultimate Beneficiary / 0152206221330 * JOSEPH JAMES NDWILA => Residence Info: ROCKKULIPA, DENI			1,525.42	0	160,531,898.26
05/07/2010	05/07/2010	Bank	006 Cash Cheque - FELIX KUYELA EDWARD From KUYELA ENTERPRISES LTD.	FJ0101860020 004	1526 02	1,300.000	0	159,231,898.26
05/07/2010	05/07/2010	Bank	007 Cheque Withdrawal Net - FELIX KUYELA EDWARD From KUYELA ENTERPRISES LTD.	FJ0101860020 004	1525 02	9,508.47	0	159,229,389.79
05/07/2010	05/07/2010	Bank	510 VAT Payable on Comm and Fees - FELIX KUYELA EDWARD From KUYELA ENTERPRISES LTD.	FJ0101860020 004	1526 02	991.53	0	159,227,398.26
05/07/2010	05/07/2010	Web House	006 Cash Cheque - FELICIAN KUYELA From KUYELA ENTERPRISES LTD.	FJ0101860020 794	1526 04	250.000	0	159,277,398.26
05/07/2010	05/07/2010	Web House	007 Cheque Withdrawal Net - FELICIAN KUYELA From KUYELA ENTERPRISES LTD.	FJ0101860020 794	1526 04	5,932.47	0	159,271,889.79
05/07/2010	05/07/2010	Web House	510 VAT Payable on Comm and Fees - FELICIAN KUYELA From KUYELA ENTERPRISES LTD.	FJ0101860020 794	1526 04	391.53	0	159,270,898.20
05/07/2010	05/07/2010	Web House	006 Sell of Forex - From KUYELA ENTERPRISES LTD.	FJ0101860020 340		7,980.000	0	151,287,898.20
06/07/2010	06/07/2010	Bank	371 Outgoing Funds Transfer - Sender's Ref: 247FTOT101860001 => Ultimate Beneficiary / 0152319004100 * FRENK BETRON NDWILA => Residence Info: ROCKKULIPA, SCMDA			27,000.000	0	124,287,898.20



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/03/2019 7:01:15 AM
 Printed By: nlt.ngawa
 Page Number: 11 Of 29

06/07/2019	06/07/2019	Since	510 VAT Payable on Comm and Fees - Sender's Ref: 247FTOT191800001 => Ultimate Beneficiary / 0142818004100 FRENK BETRON KOMDA => Remittance Info: ROC/OLIPW ECMSA			1,525.42	0	124,277,998.26
06/07/2019	06/07/2019	Since	371 Outgoing Funds Transfer - Sender's Ref: 247FTOT191800502 => Ultimate Beneficiary / 2000075507 * TRANS AFRICA WATER SYSTEM => Remittance Info: ROC/OLIPW PAMP YA MAJ			35,681,000	0	88,596,998.26
06/07/2019	06/07/2019	Since	373 Commission on Funds Transfer - Sender's Ref: 247FTOT191800502 => Ultimate Beneficiary / 2000075507 * TRANS AFRICA WATER SYSTEM => Remittance Info: ROC/OLIPW PAMP YA MAJ			5,474.58	0	83,122,523.68
06/07/2019	31/07/2019	Since	510 VAT Payable on Comm and Fees - Sender's Ref: 247FTOT191800502 => Ultimate Beneficiary / 2000075507 * TRANS AFRICA WATER SYSTEM => Remittance Info: ROC/OLIPW PAMP YA MAJ			1,525.42	0	81,597,000.26
06/07/2019	06/07/2019	Since	000 Cash Cheque - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918000090 536	1526 57	30,849,000	0	50,748,000.26
06/07/2019	06/07/2019	Since	007 Cheque Withdrawal fee - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918000090 536	1526 57	31,768.44	0	47,716,531.82
06/07/2019	06/07/2019	Since	510 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1918000090 536	1526 57	5,720.37	0	42,036,211.45
06/07/2019	06/07/2019	Since	004 Balance Enquiry Commission - Balance Enquiry Fee on 05- JUL-2019	247BENO19189 00F9		1,040.16	0	41,016,071.29
06/07/2019	06/07/2019	Since	510 VAT Payable on Comm and Fees - Balance Enquiry Fee on 05-JUL-2019	247BENO19189 00F9		350.84	0	40,665,220.45
06/07/2019	09/07/2019	From House	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1919000778 961	1528 58	10,000,000	0	30,665,220.45
06/07/2019	05/07/2019	From House	007 Cheque Withdrawal fee - FELICIAN From KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1918000778 961	1528 58	10,505	0	20,160,215.45
		Since	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA A	FJB1919000778 961	1528 58			



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2021 7:31:19 AM

Printed By: m.r.garcia

Page Number: 12 OF 30

Date	Description	Account	Reference	Debit	Credit	Balance
09/07/2019	09/07/2019	Neto Habit	016 VAT Payable on Comm and Fees - FELICIAN KUYELA From KUYELLA ENTERPRISES LTD.	FJB1919050779 187	1526 09	27,630,779.45
10/07/2019	12/07/2019	Kasapala	017 Cheque deposit - outward deposits - @NATIONAL SERVICE COMMITTEE	1207504	1277 02	29,908,379.45
10/07/2019	10/07/2019	Siapa	006 Cash Cheque - FELIX KUYELA EDWARD From KUYELLA ENTERPRISES LTD.	FJB1919150817 542	1526 80	29,761,379.45
10/07/2019	10/07/2019	Siapa	007 Cheque Withdrawal Neto - FELIX KUYELA EDWARD From KUYELLA ENTERPRISES LTD.	FJB1919150817 522	1526 80	29,777,879.99
10/07/2019	10/07/2019	Siapa	016 VAT Payable on Comm and Fees - FELIX KUYELA EDWARD From KUYELLA ENTERPRISES LTD.	FJB1919150817 522	1526 80	29,776,879.45
10/07/2019	10/07/2019	Neto Habit	006 Cash Cheque - FELICIAN KUYELA From KUYELLA ENTERPRISES LTD.	FJB1919150842 001	1126 81	29,376,879.45
10/07/2019	10/07/2019	Neto Habit	007 Cheque Withdrawal Neto - FELICIAN KUYELA From KUYELLA ENTERPRISES LTD.	FJB1919150842 001	1526 81	29,171,379.99
10/07/2019	10/07/2019	Neto Habit	016 VAT Payable on Comm and Fees - FELICIAN KUYELA From KUYELLA ENTERPRISES LTD.	FJB1919150842 001	1526 81	29,170,379.45
10/07/2019	10/07/2019	Siapa	905 Statement Enquiry Commission - Account Statement Enquiry Fee on 10-JUL-2019	2475ENQ19191 0F7N		29,152,140.93
10/07/2019	10/07/2019	Siapa	016 VAT Payable on Comm and Fees - Account Statement Enquiry Fee on 10- JUL-2019	2475ENQ19191 0F7N		29,146,379.57
10/07/2019	10/07/2019	Siapa	905 Statement Enquiry Commission - Account Statement Enquiry Fee on 10-JUL-2019	2475ENQ19191 0F7N		29,134,915.2
10/07/2019	10/07/2019	Siapa	016 VAT Payable on Comm and Fees - Account Statement Enquiry Fee on 10- JUL-2019	2475ENQ19191 0F7N		29,122,379.94
10/07/2019	10/07/2019	Siapa	905 Statement Enquiry Commission - Account Statement Enquiry Fee on 10-JUL-2019	2475ENQ19191 0F7D		29,112,040.72
10/07/2019	10/07/2019	Siapa	016 VAT Payable on Comm and Fees - Account Statement Enquiry Fee on 10- JUL-2019	2475ENQ19191 0F7D		29,106,379.76
10/07/2019	10/07/2019	Siapa	905 Statement Enquiry Commission - Account Statement Enquiry Fee on 10-JUL-2019	2475ENQ19191 0F7P		29,098,040.84



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 7:31:19 AM

Printed By: NTC/qa/m

Page Number: 13 Of 30

10/07/2019	10/07/2019	Siège	510 VAT Payable on Comm and Fees - Account Statement Enquiry Fee on 10-JUL-2019	2475END19141 0770		3,000.00	0	28,000.350
11/07/2019	11/07/2019	Nmb House	009 Sale of Funds - From KUYELLA ENTERPRISES LTD.	FJ01910250880 402		11,535.000	0	16,525.350
11/07/2019	11/07/2019	Nmb House	006 Cash Cheque - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ01910250900 280	1526 03	5,300.000	0	11,225.350
11/07/2019	11/07/2019	Nmb House	007 Cheque Withdrawal fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ01910250880 280	1526 03	0.000.1	0	11,219.949
11/07/2019	11/07/2019	Nmb House	510 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ01910250880 280	1526 03	1,044.9	0	11,218.530
12/07/2019	12/07/2019	Nmb House	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01910300961 001	1526 04	2,420.000	0	7,818.530
12/07/2019	12/07/2019	Nmb House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01910300961 001	1526 04	6,608.47	0	7,883,011.33
12/07/2019	12/07/2019	Nmb House	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01910300961 001	1526 04	861.53	0	7,812,000
15/07/2019	15/07/2019	Mimosa City	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ0191901041 618	1526 05	900.000	0	7,012,000
15/07/2019	15/07/2019	Mimosa City	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ0191901041 618	1526 05	5,308.47	0	7,006,511.53
15/07/2019	15/07/2019	Mimosa City	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ0191901041 618	1526 05	861.53	0	7,005,520
15/07/2019	15/07/2019	Mimosa City	301 Balance Enquiry Commission - Balance Enquiry Fee on 15-JUL-2019	2255END19190 0H1Q		1,949.10	0	7,003,570.84
15/07/2019	15/07/2019	Mimosa City	510 VAT Payable on Comm and Fees - Balance Enquiry Fee on 15-JUL-2019	2255END19190 0H1Q		350.84	0	7,003,220
15/07/2019	15/07/2019	Nmb House	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ0191901096 603	1526 00	700.000	0	6,303,220
15/07/2019	15/07/2019	Nmb House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ0191901096 603	1526 00	6,808.47	0	6,297,711.53
		Nmb	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA	FJ0191901096 603	1526			



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 7:31:19 AM
 Printed By: not signed
 Page Number: 14 of 28

17072019	17072019	Share	007 Cheque Withdrawal fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ01919051186 664	1526 67	5,908.47	0	28,091,211.53
17072019	17072019	Share	515 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJ01919051190 694	1526 57	991.53	0	28,090,220
17072019	17072019	Nett House	105 Bal of Fore - self From KUYELLA ENTERPRISES LTD.	FJ01919051223 491		2,316,000	0	25,774,220
17072019	17072019	Nett House	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051223 741	1526 70	25,102,000	0	2,674,220
17072019	17072019	Nett House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051223 714	1526 70	33,911.7	0	2,650,308.3
17072019	17072019	Nett House	515 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051223 741	1526 70	-4,302.3	0	2,646,006
17072019	17072019	Share	504 Balance Equity Commission - Balance Equity Fee on 17-JUL-2019	24752HQ19199 004L		1,949.84	0	2,644,056.84
17072019	17072019	Share	515 VAT Payable on Comm and Fees - Balance Equity Fee on 17-JUL-2019	24752HQ19199 904L		350.84	0	2,643,706
18072019	18072019	Nett House	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051277 278	1526 71	300,000	0	2,343,706
18072019	18072019	Nett House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051277 278	1526 71	5,508.47	0	2,338,197.53
18072019	18072019	Nett House	515 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ01919051277 278	1526 71	351.23	0	2,337,846
19072019	19072019	Share	005 Cash Cheque - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ01920051306 480	1526 72	2,000,000	0	337,846
19072019	19072019	Share	007 Cheque Withdrawal fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ01920051306 480	1526 72	5,508.47	0	331,337.53
19072019	19072019	Share	515 VAT Payable on Comm and Fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJ01920051306 480	1526 72	991.53	0	330,346



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/22/2019 7:31:19 AM

Printed By: nmg698

Page Number: 10 of 28

19072019	19072019	Stnx	006 Cash Cheque - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJB1920051300 466	1526 72	2,000,000	0	2,337,200
19072019	19072019	Stnx	006 Cash Cheque - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJB1920051307 156	1526 72	200,000	0	2,137,200
19072019	19072019	Stnx	007 Cheque Withdrawal fee - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJB1920051307 156	1526 72	5,026.47	0	2,131,601.53
19072019	19072019	Stnx	519 VAT Payable on Comm and Fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJB1920051307 156	1526 72	691.53	0	2,130,758
19072019	19072019	Mtr House	006 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1920051303 414	1526 72	100,000	0	2,030,758
19072019	19072019	Mtr House	007 Cheque Withdrawal fee - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1920051303 414	1526 72	5,026.47	0	2,025,191.53
19072019	19072019	Mtr House	519 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1920051303 414	1526 72	691.53	0	2,024,200
19072019	19072019	Stnx	904 Balance Enquiry Commission - Balance Enquiry Fee on 19- JUL-2019	247BEND19200 0HEP		1,845.16	0	2,022,355.34
19072019	19072019	Stnx	519 VAT Payable on Comm and Fees - Balance Enquiry Fee on 19-JUL-2019	247BEND19200 0HEP		350.84	0	2,021,600
20072019	20072019	Stnx	006 Cash Cheque - FELICIAN EDWARD KUYELLA (From KUYELLA ENTERPRISES LTD.	FJB1920151361 567	1520 74	1,500,000	0	521,600
20072019	20072019	Stnx	007 Cheque Withdrawal fee - FELICIAN EDWARD KUYELLA (From KUYELLA ENTERPRISES LTD.	FJB1920151361 567	1526 74	5,006.47	0	196,301.53
20072019	20072019	Stnx	519 VAT Payable on Comm and Fees - FELICIAN EDWARD KUYELLA (From KUYELLA ENTERPRISES LTD.	FJB1920151361 567	1526 74	691.53	0	515,409
22072019	22072019	Mtr City	006 Cash Cheque - FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	FJB1920251294 060	1520 72	500,000	0	15,400
			007 Cheque Withdrawal fee - FELICIAN EDWARD KUYELLA (EITHER / OR From					



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2021 7:31:19 AM
 Printed By: NINIGAWA
 Page Number: 10 Of 25

Date	Transaction Description	Account	Reference	Debit	Credit	Balance
22/07/2018	372 Incoming Funds Transfer - Sender's Ref: 1488054775T386 -> Ordering Customer: 011010042002 - NATIONAL SERVICE CONST DE -> Remittance Info: VPAA VVA LUENZI	NMB Head Office		0	14,774,000	14,782,900
23/07/2018	008 Cash Cheque - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	Bank House	FJ81820401429 070	1520 76	300,000	14,482,900
23/07/2018	007 Cheque Withdrawal fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	Bank House	FJ81820401479 878	1520 76	5,508.47	14,477,391.53
23/07/2018	510 VAT Payable on Comm and Fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	Bank House	FJ81820401479 878	1520 76	891.53	14,476,500
23/07/2018	904 Balance Enquiry Commission - Balance Enquiry Fee on 25-JUL-2018	Share	2478ENQ19204 0870		1,349.16	14,475,150.84
23/07/2018	510 VAT Payable on Comm and Fees - Balance Enquiry Fee on 25-JUL-2018	Share	2478ENQ19204 0870		390.84	14,474,760
24/07/2018	008 Cash Cheque - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	Share	FJ81820601508 807	1520 77	350,000	14,124,760
24/07/2018	007 Cheque Withdrawal fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	Share	FJ81820601508 807	1520 77	5,508.47	14,119,251.53
24/07/2018	510 VAT Payable on Comm and Fees - DRAWN BY FELICIAN EDWARD KUYELLA (EITHER / OR From KUYELLA ENTERPRISES LTD.	Share	FJ81820601508 807	1520 77	961.53	14,117,600
25/07/2018	008 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	Share	FJ81820601501 761	1520 78	14,900,000	117,000
25/07/2018	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	Share	FJ81820601501 761	1520 78	14,600	102,937
25/07/2018	510 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	Share	FJ81820601501 701	1520 78	2,837	100,300
25/07/2018	904 Balance Enquiry Commission - Balance Enquiry Fee on 25-JUL-2018	Share	2478ENQ19206 0871		1,949.16	98,350.84
	510 VAT Payable on Comm and Fees -					

NMB CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/03/2019 7:31:19 AM
 Printed By: W.S.KIWA
 Page Number: 17 of 39

Date	Branch	Description	Account No.	Debit	Credit	Balance
26/07/2019	NVR Head Office	372 Incoming Funds Transfer - Sender's Ref: 142825197573+15 ** Debiting Customer: 011107942010 TANZANIA BUILDINGS EXPEND ** Remittance Info: PAYMENT FOR MAINTENANCE V.I.P HOUS		0	28,726,813.06	28,726,813.56
27/07/2019	Siriza	006 Cash Cheque - Issued From KUYELLA ENTERPRISES LTD.	FJD1920051713 150	1526.79	1,000.000	27,826,813.56
27/07/2019	Siriza	007 Cheque Withdrawal fees - Issued From KUYELLA ENTERPRISES LTD.	FJD1920051713 150	1526.79	5,506.41	27,821,306.69
27/07/2019	Siriza	516 VAT Payable on Comm and Fees - Issued From KUYELLA ENTERPRISES LTD.	FJD1920051713 100	1526.79	991.53	27,820,313.56
27/07/2019	Siriza	006 Cash Cheque - FELICIAN From KUYELLA ENTERPRISES LTD.	FJD1920051733 404	1526.51	6,000.000	21,820,313.56
27/07/2019	Siriza	007 Cheque Withdrawal fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJD1920051733 404	1526.51	6,527	21,813,786.56
27/07/2019	Siriza	516 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJD1920051733 404	1526.51	1,173	21,812,613.56
27/07/2019	Siriza	304 Balance Enquiry Commission - Balance Enquiry Fee on 27-JUL-2019	24785ND19209 0490		1,049.10	21,810,564.4
27/07/2019	Siriza	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 27-JUL-2019	24785ND19209 0490		390.04	21,810,313.56
27/07/2019	Karakoo	422 Cheque Book Charges -			36,900	21,773,413.56
27/07/2019	Karokoo	516 VAT Payable on Comm and Fees -			7,380	21,766,033.56
27/07/2019	Karokoo	421 Stamp duty Charges -			10,000	21,756,033.56
27/07/2019	Karokoo	422 Cheque Book Charges -			4,100	21,751,933.56
26/07/2019	Siriza	004 Cash Cheque - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJD1921051765 677	1526.82	6,000.000	15,751,933.56
29/07/2019	Siriza	007 Cheque Withdrawal fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJD1921051765 677	1526.82	6,527	15,745,406.56
29/07/2019	Siriza	516 VAT Payable on Comm and Fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJD1921051765 677	1526.82	1,173	15,744,233.56
		304 Balance Enquiry Commission - Balance				



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 7:31:19 AM

Printed By: unassigned

Page Number: 16 Of 39

31/07/2019	31/07/2019	Bank House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921281940 163	1528 54	5,568.47	0	11,336,426.09
31/07/2019	31/07/2019	Bank House	516 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921281940 166	1525 54	991.53	0	11,336,432.56
31/07/2019	01/08/2019	Karakoo	415 Monthly fee for Savings and Current Accounts -			13,000	0	11,320,432.56
31/07/2019	01/08/2019	Karakoo	516 VAT Payable on Comm and Fees -			2,340	0	11,320,093.56
01/08/2019	01/08/2019	Bank House	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921301992 471	1528 55	8,000.000	0	3,320,093.56
01/08/2019	31/08/2019	Bank House	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921301992 471	1526 55	5,501	0	2,311,532.56
01/08/2019	01/09/2019	Bank House	516 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921301992 471	1525 55	1,339	0	2,309,893.56
03/08/2019	03/08/2019	Bank	005 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921562101 123	1525 56	2,290,000	0	1,305,593.56
03/08/2019	03/08/2019	Bank	007 Cheque Withdrawal fees - Felician Kuyella From KUYELLA ENTERPRISES LTD.	FJ81921562101 123	1528 56	5,508.47	0	1,304,495.09
03/08/2019	03/08/2019	Bank	516 VAT Payable on Comm and Fees - Felician Kuyella From KUYELLA ENTERPRISES LTD.	FJ81921562101 123	1525 56	561.53	0	1,103,493.56
03/08/2019	03/08/2019	Bank	001 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921152173 341	1526 57	600,000	0	803,493.56
03/08/2019	03/08/2019	Bank	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921752173 341	1526 57	5,508.47	0	497,985.09
03/08/2019	03/08/2019	Bank	516 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJ81921752173 341	1525 57	511.53	0	495,973.56
05/08/2019	05/08/2019	Bank	804 Balance Enquiry Commission - Balance Enquiry Fee on 05-AUG-2019	2475ENQ19217 800		1,949.16	0	495,044.4
05/08/2019	05/08/2019	Bank	516 VAT Payable on Comm and Fees - Balance Enquiry Fee on 05-AUG-2019	2475ENQ19217 800		350.84	0	494,693.56
06/08/2019	06/08/2019	Karakoo	517 Cheque deposit - account clearance - NATIONAL SERVICE CONSTITUTE	1224423	7278 59	0	2,400,000	2,894,693.56
			005 Cash Cheque -					



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2019 10:11:19 AM
 Printed By: mngmwo
 Page Number: 19 Of 28

06/08/2019	06/08/2019	Stoca	316 VAT Payable on Comm and Fees - FELICIAN From KUYELLA ENTERPRISES LTD.	FJB162180217 979	1526 50	391.53	0	2,418,702.59
06/08/2019	06/08/2019	Stoca	904 Balance Equity Commission - Balance Equity Fee on 06-AUG-2019	2478ENO19215 0878		1,949.16	0	2,416,214.4
06/08/2019	06/08/2019	Stoca	316 VAT Payable on Comm and Fees - Balance Equity Fee on 06-AUG-2019	2478ENO19215 0878		390.64	0	2,415,450.96
06/08/2019	06/08/2019	Stoca	000 Cash Cheque - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1922102325 421	1526 50	2,400,000	0	16,853.56
06/08/2019	06/08/2019	Stoca	007 Cheque Withdrawal fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1922150330 421	1526 40	5,328.47	0	10,385.09
06/08/2019	06/08/2019	Stoca	316 VAT Payable on Comm and Fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1922152335 421	1526 30	901.53	0	9,263.58
26/08/2019	26/08/2019	Karakaoo	017 Cheque deposit - outward clearance - NATIONAL SERVICE CONST DEPT	1235216	7279 52	0	4,000,000	4,000,305.96
26/08/2019	26/08/2019	Karakaoo	017 Cheque deposit - outward clearance - NATIONAL SERVICE CONST DEPT	1235234	7279 42	0	354,000	4,354,305.96
26/08/2019	26/08/2019	Karakaoo	000 Cash Cheque - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1924052199 214	1526 51	4,300,000	0	12,393.56
26/08/2019	26/08/2019	Karakaoo	007 Cheque Withdrawal fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1924053199 214	1526 51	5,508.47	0	7,865.28
26/08/2019	26/08/2019	Karakaoo	316 VAT Payable on Comm and Fees - FELICIAN KUYELLA From KUYELLA ENTERPRISES LTD.	FJB1924053199 214	1526 01	601.53	0	6,263.56
31/08/2019	01/09/2019	Karakaoo	410 Monthly fee for Savings and Current Accounts -			1,193.56	0	0
09/09/2019	09/09/2019	1810 Head Office	372 Incoming Funds Transfer - Sender's Ref: 152220517573415 => Ordering Customer: 01/02/2019 TANZANIA BUILDINGS EXPEND => Remittance Info: MAINTANANCE EX CDA HOUSE			0	9,576,271.19	9,576,271.19
09/09/2019	09/09/2019	Stoca	001 Cash Deposit - BY FELICIAN From KUYELLA ENTERPRISES LTD.	FJB1925237779 047		0	1,400,000	10,976,271.19
		Head	000 Cash Cheque - Felician Kuyella From KUYELLA	FJB1925237803	1526			



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/23/2021 10:11:19 AM
Printed By: kmngawa
Page Number: 31 of 32

Table with columns for Date, Description, NMB Head Office, Transaction Type, Reference Number, Amount, and Balance. Includes entries for Incoming Funds, Cash Cheques, Cheque Withdrawals, VAT Payable, and Salary Equity Commission.



CUSTOMER ACCOUNT STATEMENT

Period Date: 11/23/2021 7:31:19 AM
 Period By: nrmrplwls
 Page Number: 38 of 39

Date	Period	Branch	Description	Account No.	Code	Debit	Credit	Balance
20/07/2021	02/08/2021	Karaka	017 Cheque deposit - outward clearance - SUBARU CONSTRUCTION COMPANY LTD@	7294 54		0	-7,350,000	6,578.43
31/07/2021	01/08/2021	Karaka	418 Monthly fee for Savings and Current Accounts -			6,578.43	0	0
02/08/2021	03/08/2021	Karaka	017 Cheque deposit - outward clearance - SUBARU CONSTRUCTION COMPANY LTD@	1615811	7294 54	0	7,350,000	7,350,000
09/09/2021	09/09/2021	Karaka	418 Monthly fee for Savings and Current Accounts -			4,929.27	0	7,350,000.13
09/08/2021	01/09/2021	Karaka	512 Excess bill commission -			1,181.7	0	7,548,978.43
09/08/2021	09/08/2021	Karaka	515 VAT Payable on Deposit and Fees -			2,340	0	7,340,538.43
05/08/2021	05/08/2021	Suva	008 Cash Cheque - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJ82121784345 843	1027 09	7,332,909	0	16,538.43
06/08/2021	05/08/2021	Suva	007 Cheque Withdrawal Fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJ82121784345 942	1027 09	7,677.97	0	8,060.46
05/09/2021	06/09/2021	Suva	515 VAT Payable on Commission and Fees - FELICIAN EDWARD KUYELLA From KUYELLA ENTERPRISES LTD.	FJ82121784345 942	1027 09	1,417.92	0	7,242.54
05/08/2021	05/08/2021	Suva	305 Statement Enquiry Commission - Account Statement Enquiry Fee on 03-AUG-2021	247SENG021215 571C		3,389.92	0	3,852.72
05/08/2021	05/08/2021	Suva	515 VAT Payable on Commission and Fees - Account Statement Enquiry Fee on 03- AUG-2021	247SENG021215 571C		610.36	0	3,242.36
31/08/2021	01/09/2021	Karaka	418 Monthly fee for Savings and Current Accounts -			3,242.55	0	0
01/10/2021	01/10/2021	NMB Head Office	372 Incoming Funds Transfer - Sender's Ref FP32024FA181CEBA to Ordering Customer 0150042863500 TAN CRDS T25 Expenditure Account to Remittance Info FormCardustawarbe @			0	17,886,471.93	17,886,471.93
01/10/2021	01/10/2021	Suva	305 Statement Enquiry Commission - Account Statement Enquiry Fee on 10-AUG-2021	247SENG021222 58VF		32,203.29	0	17,804,268.64
01/10/2021	01/10/2021	Suva	515 VAT Payable on Commission and Fees - Account Statement Enquiry Fee on 10- AUG-2021	247SENG021222 58VF		5,716.52	0	17,248,472.12
			008 Cash Cheque - KUYELLA					



CUSTOMER ACCOUNT STATEMENT

Printed Date: 11/25/2021 7:01:18 AM
 Printed by: nri.ngrs@nmb
 Page Number: 20 of 20

Date	Period	Branch	Description	Account No.	Debit	Credit	Balance	
01/10/2021	01/10/2021	Mirani City	516 VAT Payable on Comm and Fees - KUYELLA ENTERPRISES LTD, From KUYELLA ENTERPRISES LTD,	FJ2027487100 910	1527 70	3,333.01	0	31,618.78
01/10/2021	01/10/2021	Karaka	410 Monthly fee for Savings and Current Accounts -		8,575.74	0	23,043.04	
01/10/2021	01/10/2021	Karaka	512 Excess duty commission -		1,181.7	0	21,861.34	
01/10/2021	01/10/2021	Karaka	516 VAT Payable on Comm and Fees -		2,340	0	19,521.34	
01/10/2021	01/10/2021	Karaka	410 Monthly fee for Savings and Current Accounts -		11,818.3	0	7,703.04	
01/10/2021	01/10/2021	Karaka	512 Excess duty commission -		1,181.7	0	6,521.34	
01/10/2021	01/10/2021	Karaka	516 VAT Payable on Comm and Fees -		2,340	0	4,181.34	
01/10/2021	01/11/2021	Karaka	410 Monthly fee for Savings and Current Accounts -		4,181.34	0	0	

Total Debt Amount	1,011,194,451.17
Total Credit Amount	1,010,194,357.2
Number of Debt Transactions	532
Number of Credit Transactions	67
Current Balance	0
Unallocated Amount	0
Available Balance	0

[Handwritten signature and stamp]

Standard Power of Attorney

TO ALL IT MAY CONCERN

THAT BY THIS POWER OF ATTORNEY given on the 12/01/2022,
WE the undersigned KUYELLA ENTERPRISES LIMITED of P.O Box 2880 Dar es Salaam, by virtue of authority conferred to us by the Board Resolution No. 05 of 11 day Of January, 2022, do hereby ordain nominate and appoint FELIX KUYELLA of P.O Box 2880 Dar es Salaam, to be our true lawful Attorney and Agent, with full power and authority, for us and in our names, and for our accounts and benefits, to do any, or all of the following acts, in the execution of tender No. LGA/147/2021/2022/W/IMF/6 that is to say;

1. To act for the company and do any other thing or things incidental LGA/147/2021/2022/W/IMF/6 of PROPOSED CONSTRUCTION OF EMERGENCY MEDICAL DEPARTMENT BUILDING AT MKALAMA DISTRICT HOSPITAL;

AND provided always that this Power of Attorney shall not revoke or in any manner affect any future power of attorney given to any other person or persons for such other power or powers shall remain and be of the same force and affect as if this deed has not been executed.

AND we hereby undertake to ratify everything, which our Attorney or any substitute or substitutes or agent or agents appointed by him under this power on his behalf herein before contained shall do or purport to do in virtue of this Power of Attorney.

SEALED with the common seal of the said KUYELLA ENTERPRISES LIMITED and delivered in the presence of us 12 day Of January, 2022.

IN WITNESS whereof we have signed this deed on 12 day Of January, 2022 at DAR ES SALAAM for and on behalf of KUYELLA ENTERPRISES LIMITED.

SEALED and DELIVERED by the
Common Seal of KUYELLA ENTERPRISES
LIMITED, this, 12 day Of January, 2022


DONOR

BEFORE ME:


COMMISSIONER FOR OATHS



Acknowledgement

I FELIX KUYELLA doth hereby acknowledge and accept to be Attorney of the said KUYELLA ENTERPRISES LIMITED under the terms and conditions contained in this POWER OF ATTORNEY and I promise to perform and discharge my duties as the lawfully appointed Attorney faithfully and honestly.

SIGNED AND DELIVERED by the said
FELIX KUYELLA Identified to me
By FELICIAN KUYELLA
The latter known to me personally
This 12 day Of January, 2022

}


.....
DONEE

BEFORE ME



.....
COMMISSIONER FOR OATHS



KUYELLA ENTERPRISES LIMITED

BUILDING CONTRACTORS

Company Profile

P.O. Box 2880 - Dar Es Salaam Mobile Number, +255 (0) 754023359

E - mail: kuyella2000@yahoo.com

INTRODUCTION

Kuyella Enterprises Limited was registered as company by BRELA in February 2008 and assigned Certificate of Incorporation Number 64370, in May 2008.

Kuyella Enterprises is registered as a class "Four" Building Contractors by The Contractors Registration Board vide Certificate Number: "B4/0299/5/08" specializing in Building Construction

Besides being registered in Tanzania mainland, Kuyella Enterprises Limited is registered by the registrar of companies in Zanzibar vide Certificate of Compliance Number: "F20462010"

Kuyella Enterprises is wholly owned by Tanzania Citizens with vast and depth experience in the fields of construction industry.

Our Vision:

To be respectable building contractors in Tanzania delivering beyond expectation.

Our Mission:

To do all that is in our power to ensure customers are satisfied with our services and professionalism in value and quality.

To procure projects at competitive pricing, provide safe working conditions and deliver quality work within reasonable time frame.

To contribute to the positive development and prosper of the local contractor's industry in Tanzania.

COMPANY INFORMATION

Company Directors:

Arch. Felix Kuyella
Vaillet Edward
Felician Kuyella

Physical Address:

Head Office:

Kuyella Enterprises Limited
P.O. Box 2880
3rd Floor Redeso Building - Kinondoni Area
Mob: +255 754 023359
Email: kuyella2000@yahoo.com

Zanzibar Office:

Kuyella Enterprises Limited
P.O. Box 1532
Kikwajuni Area - Zanzibar
Phone: +255 24 2230324
Mob: +255 758 217686
Email: kuyella2000@yahoo.com

TECHNICAL PERSONEL

Name: Arch. Felix Kuyella
Position: Managing Director
Qualification: BSc. Architectural Design (Bangalore University, India)
Experience: 28 years
Email: kuyella2000@yahoo.com
Mob: +255 754 023359

Name: John M. Levira
Position: Site Engineer
Qualification: BSc. In Civil & Structural Engineering (UDSM)
Experience: 10 years
Email: jlevira2009@gmail.com
Mob: +255 769 398138

Name: Ali Mzindu
Position: Site Technician
Qualification: F. T. C in Civil Engineering (DIT)
Experience: 27 years
Email: allymzindu@yahoo.com
Mob: +255 718 868922

Name: David Tilya
Position: Quantity Surveyor
Qualification: BSc. In Building Economics (ARDHI)
Experience: 5 years
Email: collinsdavid2005@gmail.com
Mob: +255 717 278725

Name: Ephrahim G. Rusuladeza
Position: Site Engineer
Qualification: Structural Engineer
Experience: 14 years
Email: rusurae@gmail.com
Mob: +255 769 448648

Name: George M. Maro
Position: Asst. Architect
Qualification: H N D Construction (Architectural Design) (Malaysia)
Experience: 4 years
Email: georgearchitect.gm@gmail.com
Mob: +255 658 026560

TECHNICAL PERSONEL

Name: Denise Kyamba
Position: Site Technician
Qualification: F. T. C in Civil Engineering (DIT)
Experience: 18 years
Email: deniskyamba@gmail.com
Mob: +255 753 727598

Name: Ali Msabaha
Position: Steel Fixer
Qualification: VETA
Experience: 29 years
Email: amsabaha2000@yahoo.com
Mob: +255 713 449215

Name: Abdala Mwakobe
Position: Carpenter
Qualification: VETA
Experience: 20 years
Email: abdmwakobe2001@yahoo.com
Mob: +255 712 176578

KN 15/0305

10:95064

TFN 226
(Rev. 1/91)



JAMHURI YA MUUNGANO WA TANZANIA

KINWANG'ANI
MUNICIPAL
COUNCIL

LESENI YA BIASHARA

B 0010305

(Jumla kwa chini ya Sheria ya Leseni za Biashara No. 25 ya Mwaka 1972 inarekebisha ya mwaka 1980 na ruzikari jilipo njema)

*Futa isiyotakwa

1. Ofisi iliyotolewa MANISPAHA YA KINWANG'ANI
2. Nambari ya Ushuru wa mapato 106-505-218
3. Leseni ilitolewa kwa KUYELLA ENTERAPRAISZI K.F.U
kundi la biashara ya BUILDING CONTRACTOR CLASS
katika Wilaya/Kanda* ya KINWANG'ANI Mkoa KINWANG'ANI
4. Ni ya Shina/Tare* RUJINI
Ada Sh. 1,621,000/- Nambari ya Stokohafu 695730
ya tarehe 28/09/2021
5. Mpya inaonekana* 2.3197462
ya tarehe 04/07/2019

(ii) Muda wa leseni hii unachia 30/08/2022

Tarehe 28/09/2021

GP/CSM BOY/0507

(Signature and Stamp)

(Signature and Stamp)
30/10/2021



No. 2654

CONTRACTORS REGISTRATION BOARD
CERTIFICATE OF REGISTRATION

This is to Certify that

Ruyella Enterprises Limited

is registered as

BUILDING CONTRACTOR

Class Four

Registration No *B4/0299/5/08* Category *Local*

*In accordance with the provisions of The Contractors Registration
Act No. 17 of 1997*

*In witness whereof the common seal has been affixed
hereto on this 22nd day of May, 2008*

[Signature]

Registrar




Chairman

The certificate is valid subject to the By-laws made under the Act

Copy of [Signature] of the Original
[Signature]
DAR ES SALAM
5/22/2008

TIN 0807194



TANZANIA REVENUE AUTHORITY

CERTIFICATE OF REGISTRATION
FOR
TAXPAYER IDENTIFICATION NUMBER (TIN)

THIS IS TO CERTIFY THAT
KUYELLA ENTERPRISES LIMITED

HAS BEEN REGISTERED WITH THE TANZANIA REVENUE AUTHORITY
AND ASSIGNED THE TAXPAYER IDENTIFICATION NUMBER


106-525-218

WITH EFFECT FROM 12 March 2008

TRA LOCATION ILALA TAX OFFICE ILALA

PHYSICAL LOCATION PLOT No. 1 BLOCK No. M

STREET / AREA: MSIMBAZI



OFFICIAL SEAL
COMMISSIONER FOR DOMESTIC REVENUE

READ THE REGULATIONS FOR THE TIN IDENTIFICATION IN THE STATE - ILALA

Copy of the Original
S/O GISHAGA
Commissioner for Customs
S/O ES SALAMU
5/10/2021



TANZANIA REVENUE AUTHORITY

Certificate of Registration for Value Added Tax (VAT)

SECTION 25(1) OF THE VALUE ADDED TAX ACT NO. 30 OF 1997

**THIS IS TO CERTIFY THAT
KUYELLA ENTERPRISES LIMITED**

**WHOSE TAXPAYER IDENTIFICATION NUMBER (TIN) IS
106-525-218**

**HAS BEEN REGISTERED FOR VALUE ADDED TAX (VAT)
AND ASSIGNED VAT REGISTRATION NUMBER (VRN)
40-001915-U**

**FOR BUSINESS LOCATED AT MSIMBAZI 1
DAR ES SALAAM**

WITH EFFECT FROM 11 July 2008

GIVEN UNDER MY HAND

THIS 8th DAY OF July 2008

**JOANNES N. A. MALLY
COMMISSIONER FOR VAT**

Handwritten signature and stamp
The Original
KUYELLA ENTERPRISES LIMITED
DAR ES SALAAM
30/07/2008



NOTE: THE REGISTRATION UNDER WHICH THIS CERTIFICATE IS ISSUED IS VALID UNLESS



THE UNITED REPUBLIC OF TANZANIA
MINISTRY OF LABOUR, EMPLOYMENT AND YOUTH DEVELOPMENT
OCCUPATIONAL SAFETY AND HEALTH AUTHORITY



OSHA 1

CERTIFICATE OF REGISTRATION OF FACTORY/WORKPLACE

No. of Certificate **DAR/001879**

Date of issue **04/12/2009**

I hereby certify that the factory/workplace named below has been duly registered in pursuance of section 16 of The Occupational Health and Safety Act, No. 5 of 2002

Name of the Occupier / Owner: **KUYELLA ENTERPRISES LTD.**

Address and location of Factory/Workplace: **P.O BOX 2880, D'SALAAM
KARIAKOO**

Nature of work **CONSTRUCTION OF COMMERCIAL BUILDING**

H.I. Kitumbo
H.I. Kitumbo
CHIEF INSPECTOR

Note

- 1 This certificate is valid only in respect of the occupier and factory/workplace named above
- 2 This certificate is issued under, and solely for the purpose of, the Occupational Health and Safety Act, and without prejudice to the requirements of any other legislation relating to the occupation of premises for industry purposes
- 3 This Certificate should be attached to the General Register



TANZANIA



Certificate of Incorporation

Section 15

No **64370**

I HEREBY CERTIFY THAT

KUYELLA ENTERPRISES LIMITED *****

is this day incorporated under the Companies Act, 2002 and that the Company is Limited.

Given under my hand at Dar es salaam
this **21ST** day of **FEBRUARY**
TWO THOUSAND AND EIGHT

Asst. Registrar of Companies

CHECKED BY: [Signature]
[Stamp: TANGANYIKA PUBLIC COMPANYIES ACT, 2002, DAR ES SALAAM]
30/10/2021

PROJECT REFERENCES

	PROJECT DESCRIPTION	CLIENT	PROJECT VALUE (Tsh)	STATUS
1.	Construction of shopping mall	Mkonge Hotel	313,775,000.00	Completed
2.	Construction of 9 Storeys residential / commercial apartment	Renshitts Co. Ltd	611,250,000.00	Completed
3.	Construction of 8 Storeys + Basement residential apartment	Aslam Haroon Khamis	1,082,157,000.00	Completed
4.	Construction of Hotel building	Al Murad	590,875,000.00	Completed
5.	Construction of staff house Tabora Girls Sec. School	UNHCR	458,437,500.00	Completed
6.	Construction of 5 storeys commercial building	William Lucas kweka	713,125,000.00	Completed
7.	Construction of commercial building	Clock Tower Shopping Center	1,059,500,000.00	Completed
8.	Construction of office building	Big Bon Petroleum Co.	407,500,000.00	Completed
9.	Construction of warehouse & office building	Oil Com Tanzania Ltd	224,125,000.00	Completed
10.	Construction of 7 storeys commercial building at Masaki	Mustafa Jaffer	1,597,400,000.00	Completed
11.	Construction of show room	East Africa investment Limited	692,750,000.00	Completed
12.	Construction of Military & War Heroes Cemetery 512 KJ Mtwara	TPDF	387,125,000.00	Completed
13.	Renovation of operation building & VIP Lounge at 603 ATS - Air Force Base	TPDF	133,660,000.00	Completed

PROJECT REFERENCES

	PROJECT DESCRIPTION	CLIENT	PROJECT VALUE (Tsh)	STATUS
14.	Construction of VIP ward at 512 KJ Lugalo Military Hospital - DSM	TPDF	1,155,767,800.00	Completed
15.	Construction of Male Dormitory building for Moravian Church - Tz	Teofilo Kisanji University	1,294,220,000.00	In Progress 60%
16.	Construction of Satellite Village at Dungu - Kigamboni.	NSSF	1,152,780,636.47	In Progress 50%
17.	Construction of 7 storeys residential apartment building at Msasani Village	Amverton Hotel Apartments	2,625,223,500.00	Completed
18.	Supply of building materials and tools for construction at RTS - Kihangaiko Military Base	TPDF	1,084,177,826.00	Completed
19.	Supply of furniture at 603 ATS - Air Force Base	TPDF	105,100,000.00	Completed
20.	Rehabilitation of external water articulation & water tanks at Air Force Base - Ngerengere	TPDF	2,000,000,000.00	In Progress 90%
21.	Construction of gravity pipe scheme, water storage tanks, water points, cattle trough & rain water harvesting for Luondoluo Village - Longido	Longido District Council	1,100,000,000.00	In Progress 95%
22.	Construction of 7 storeys + basement residential commercial building - Kawe	United Traders JV Mark Bomani	15,000,000,000.00	In Progress 10%
23.	Construction of Shopping arcade & Bus Terminal at Makumbusho - DSM	Kinondoni Municipal Council		Completed

PROJECT REFERENCES

	PROJECT DESCRIPTION	CLIENT	PROJECT VALUE (Tsh)	STATUS
24.	Construction of Student Hostel, Restaurant, Office & Shops at Rau - Moshi	M. C. Calyst Maro	1,700,000,000.00	Completed
25.	Construction of 9 storeys Residential commercial building at Jangwani Mafia Street - DSM	S. F. Koka	2,200,000,000.00	In Progress 95%
26.	Construction of 7 storeys commercial building at Kurasini	Dar Es Salaam Corridor Group (DCG)	2,500,000,000.00	Completed

1.1 Work performed as prime Contractor on works of a similar nature and volume over the last 5 years.

S/N	PROJECT NAME AND COUNTRY	NAME OF EMPLOYER AND FULL ADDRESS	CONTRACTOR PARTICIPATION	TYPE OF WORK PERFORMED	YEAR	VALUE OF CONTRACT
1.	PROPOSED REHABILITATION OF EXTERNAL WATER ARTICULATION & WATER TANKS AT AIR FORCE BASE - NGERENGERE	TANZANIA PEOPLES DEFENCE FORCE DAR ES SALAAM, TANZANIA.	Main Contractor	Construction of pipe network, water storage tank, water point, supply and installation of submersible pump and diesel engine, Rain water harvest system.	2020	2,500,000,000.00
2.	PROPOSED CONSTRUCTION OF STUDENT HOSTEL, RESTAURANT AND OFFICE & SHOPS AT RAU URBAN VILLAGE IN MOSHI-KILIMANJARO.	M.C. CALYST	Main Contractor	Masonry works, Framed structure works, plumbing and drainages works, Electrical Installation works, Mechanical works, and Glass works	2019	1,700,000,000.00
3.	PROPOSED CONSTRUCTION OF COMMERCIAL BUILDING AT KURASINI, KILWA ROAD-DAR ES SALAAM, TANZANIA	DAR ES SALAAM CORRIDOR GROUP (DCG)	Main Contractor	Masonry works, Framed structure works, plumbing and drainages works, Electrical Installation works, Mechanical works, and Glass works	2019	2,500,000,000.00
4.	PROPOSED OF SHOPPING TERMINAL AT MAKUMBUSHO AREA IN DAR ES SALAAM	KINONDONI MUNICIPALITY COUNCIL MOBILE: +255 (786) 919 090	Main Contractor	Masonry works, Framed structure works, plumbing and drainages works, Electrical Installation works, Mechanical works, and Glass works	2015-2019	1,200,000,000.00

	PROPOSED CONSTRUCTION	AMVERTON HOTEL APARTMENTS		2015-2017	1,200,000,000.00
5.	OF 7 STOREYS RESIDENTIAL APARTMENT AT MASAKI, MSASANI VILLAGE		Main Contractor	Construction of Load bearing walls frame structure, Lift shaft & stairs, finishing works, doors & windows, I.T 5 gauge 28 roofing works, service works such as, electrical works, plumbing & mechanical works and external works.	
6.	PROPOSED CONSTRUCTION OF VIP WARD AT 512 KJ LUGALO MILITARY	TANZANIA PEOPLES DEFENCE FORCE DAR ES SALAAM, TANZANIA.	Main Contractor	2014-2016	1,155,767,800.00
7.	PROPOSED CONSTRUCTION OF STAFF HOUSE TABORA GIRLS SEC. SCHOOL	UNHCR- REDESSO	Main Contractor	2017-2018	458,437,500.00

EXECUTED PROJECTS IN PICTURES BY KUYELLA ENTERPRISES LIMITED:

Appendix 1. Proposed construction of commercial warehouses at Pugu Road



Figure 1: The completed warehouses at Pugu Road in Dar es Salaam, TANZANIA



Figure 2: The completed warehouses at Pugu Road



Figure 3: The side view of the completed warehouse



Figure 4: The in front view of one of the warehouses at Pugu Road

Appendix II. Proposed Construction of Makumbusho Shopping Arcade



Figure 5: The Completed Makumbusho Shopping Arcade

Appendix III. Proposed Shopping mall/Residential apartments at Misasani, Dar es



Figure 1



Selaam



Figure 2

Figure 3



INFORMATION RELATED TO CURRENT COMMITMENT

S/No.	Name of Contract	Employer's Contact Address, Tel, Fax	Value of Outstanding Work [Current Tanzania shillings]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Current Tanzania shillings]
1.	PROPOSED STORAGE WAREHOUSE, SHOPPING MALL AND RESIDENTIAL APARTMENTS ON PLOT NO. 576 MSASANI BEACH, KINONDONI, AND DAR ES SALAAM	United Traders Joint Venture Mr. Bomani Mr. Fuad Salmin +255 (686) 544 384 EMAIL ADDRESS: charlescock@gmail.com	4,000,000,000/=	March 2022	250,000,000.00/=

PROJECT UNDERTAKEN



Project Name:	Residential Apartment Building
Project Value:	1,200,000,000.00 (Tsh.)
Location:	Karakoo
Status:	Complete
Client:	Al Muraad

PROJECT UNDERTAKEN



Project Name:

Shopping Arcade & Bus Terminal

Project Value:

1,200,000,000.00 (Tsh.)

Location:

Makumbusho

Status:

Complete

Client:

Kinondoni Municipal Council

PROJECT UNDERTAKEN



Project Name:

Project Value:

Location:

Status:

Client:

Residential/Commercial Building

1,200,000,000.00 (Tsh.)

Lumumba - Kariakoo
Complete

Al Muraad

PROJECT UNDERTAKEN



Project Name:

Residential/Commercial Building

Project Value:

1,200,000,000.00 (Tsh.)

Location:

Masaki

Status:

Complete

Client:

Amverton Hotel Apartment

PROJECT UNDERTAKEN



Project Name:

VIP Ward at 521KJ Lugalo

Project Value:

1,155,767,800.00 (Tsh.)

Location:

Mosaki

Status:

Complete

Client:

TPDF

PROJECT UNDERTAKEN



Project Name:

Student Hostel, Restaurant & Office

Project Value:

1,700,000,000.00 (Tsh.)

Location:

Rau - Moshi

Status:

Complete

Client:

M. C. Calyst

PROJECT UNDERTAKEN



Project Name:

Rehabilitation of water articulation & water tanks

Project Value:

2,000,000,000.00 (Tsh.)

Location:

Ngerengere - Air Force Base

Status:

In Progress 90%


Client:

TPDF

PROJECT UNDERTAKEN



Project Name:	Residential/commercial Apartment Building
Project Value:	15,000,000,000.00
Location:	Kawe
Status:	In Progress 10%
Client:	United Traders JV Mark Boman



PROPOSED CONSTRUCTION OF MALE DOMITORY BLOCK FOR MURAVIAN
CHURCH IN TANZANIA TEOFILO KISANJI UNIVERSITY ON PLOT No. 560
BLOCK T IN MBEYA



PROPOSED CONSTRUCTION OF MALE DOMITORY BLOCK FOR MORAVIAN
CHURCH IN TANZANIA TEOFILO KISANJI UNIVERSITY ON PLOT No. 560
BLOCK T IN MBEYA

FRONT ELEVATION.



PROPOSED CONSTRUCTION OF RESIDENTIAL/COMMERCIAL BUILDING BUILT AT NYATI STREET
KARIAKOD DAR ES SALAAM



THE UNITED REPUBLIC OF TANZANIA
MINISTRY OF LABOUR, EMPLOYMENT AND YOUTH DEVELOPMENT



CD/HR 1

CERTIFICATE OF REGISTRATION OF FACTORY/WORKPLACE

No. of Certificate: **DAR/001879**

Date of issue: **04/12/2009**

I hereby certify that the factory/workplace named below has been duly registered in
pursuance of section 16 of The Occupational Health and Safety Act No. 512003

Name of the Occupier / Owner: **KUYELLA ENTERPRISES LTD.**

Address and location of Factory/Workplace: **P.O BOX 2880, D'SALAAM
KARIAKOO**

Nature of work: **CONSTRUCTION OF COMMERCIAL BUILDING**


H. I. Kitumbi
H. I. Kitumbi
CHIEF INSPECTOR

Note:

1. This certificate is valid only in respect of the occupier and factory/workplace named above.
2. This certificate is issued under and solely for the purpose of the Occupational Health and Safety Act, and without prejudice to the requirements of any other legislation relating to the occupation of premises for similar purposes.
3. This Certificate should be attached to the General Register.


ETG

ETG (Ethyl Glucuronide) is a metabolite of alcohol. It is used in forensic toxicology to detect alcohol consumption. The presence of ETG in a person's system indicates that they have consumed alcohol within the last 24-48 hours. ETG is excreted in urine and can be detected using immunoassay or chromatography methods. The concentration of ETG in urine is directly proportional to the amount of alcohol consumed. ETG is a stable metabolite and is not affected by the body's natural processes, making it a reliable marker for alcohol consumption.



PLANT AND EQUIPMENT AVAILABLE.

S/No	Item of Equipment.	Description, Make and age (year).	Condition.	Remarks.
1	Truck	2 ton Tipper Make: 1 Isuzu, 1 Mitsubishi	Condition: good Number: 2	Owned
2	Trucks	1 ton canter Make: Mitsubishi Year: 1994	Condition: good Number: 1	Owned
3	FWD vehicles	1 Station wagon Make: Landruiser Prado Year: 1999	Condition: good Number: 1	Owned
4	Pick up	1 Pick ups Make: Nissan Single Cabin, Year: 1998	Condition: good Number: 1	Owned
5	Welding Machine	Make: Year:	Condition: good Number: 2	Owned
6	Hand Grinding Machine	Make: Year:	Condition: good Number: 1	Owned
7	Plate Compactor	Make: Year:	Condition: good Number: 1	Owned
8	Concrete Mixers	Make: Lister Peter Year: 1999, 1994, 1997	Condition: good Number: 3	Owned



KUYELLA ENTERPRISES LTD

P.O Box 2880 DAR ES SALAAM – TANZANIA

TEL: +255 686 600 556, +255 754 023 359

Email: kuyella2000@yahoo.com

13th January, 2022.

To

THE SECRETARY
COUNCIL TENDER BOARD
P.O BOX 1007
MKALAMA – SINGIDA.


Dear Sir,

REF: ACCEPTANCE OF BID VALIDATION PERIOD

Refer to the heading above.

We, Kuyella Enterprises Limited, following the bid for the project of Proposed Construction of Emergency Medical Building at the District Hospital, with contract Identification Tender no. LGA/147/2021/2022/W/IMF/6; have agreed with the 90 days Bid Validation as mentioned in Tender Data Sheet (TDS). Duration of execution of works is three months and two weeks (104 days).

Yours Faithfully,



Felix Kuyella,
Managing Director,

KUYELLA ENTERPRISES LIMITED



Tender-Securing Declaration

Date: 13/01/2022

Tender No.: LGA/147/2021/2022/W/IMF/6

Alternative No.: -

To: MKALAMA DISTRICT COUNCIL.

We, *KUYELLA ENTERPRISES LIMITED*, the undersigned, declare that:

We understand that, according to your conditions, Tenders must be supported by a Tender-Securing Declaration.

We accept that we will automatically be suspended from being eligible for tendering in any contract with the PE for the period of time determined by the Authority, if we are in breach of our obligation(s) under the Tender conditions, because we:

- a) have withdrawn or modified our Tender during the period of tender validity specified in the Form of Tender;
- (b) Disagree to arithmetical correction made to the tender price; or
- (c) have been notified of the acceptance of our Tender by the PE during the period of tender validity, (i) fail or refuse to execute the Contract, if required, failure to sign the contract if required by PE to do so or (ii) fail or refuse to furnish the Performance Security or to comply with any other condition precedent to signing the contract specified in the tendering documents, in accordance with the ITB. We understand this Tender Securing Declaration shall expire if we are not the successful Tenderer, upon the earlier of (i) our receipt of your notification to us of the name of the successful Tenderer; or (ii) twenty-eight days after the expiration of our Tender.

Signed: *Felix Kuyella* In the capacity of *Managing Director*

Name: *FELIX KUYELLA*

Duly authorized to sign the Tender for and on behalf of: *KUYELLA ENTERPRISES LIMITED*.

Dated on 13 day of 01, 2022



STATEMENT OF NON-LITIGATION

I (We) the undersigned,


On behalf of the board of Director of **KUYELLA ENTERPRISES** do hereby certify that there is no pending or threatened actions of law that will affect the dedication of subdivision improvements in any of our current project **PROPOSED CONSTRUCTION OF EMERGENCY MEDICAL DEPARTMENT BUILDING AT MKALAMA DISTRICT HOSPITAL, TENDER NO. LGA/147/2021/2022/W/IMF/6** or even intended new coming projects.

I (We) further certify that all contract having been done, subcontracted, material suppliers, engineers attorneys, or other persons, firms or corporation retained for the purpose of accomplishing any project have been paid in full.

Authorized Officer of the Company

Name: **FELIX KUYELLA**

Designation: **MANAGING DIRECTOR**

Signature: 

This is to certify that **FELIX KUYELLA** has this **13th** of **January** in the year of our Lord **2022** in my presence signed this Statement of Non Litigation and on behalf of the Company above named.

BEFORE ME:



.....
COMMISSIONER FOR OATHS



UNDERTAKING BY BIDDER ON ANTI - BRIBERY POLICY / CODE OF
CONDUCT AND COMPLIANCE PROGRAMME


- (1) Each Bidder must submit a statement, as part of the bid documents, in either of the two given formats which must be signed personally by the Chief Executive Officer or other appropriate senior corporate officer of the bidding company and, where relevant, of its subsidiary in the United Republic of Tanzania. If a bid is submitted by a subsidiary, a statement to this effect will also be required of the parent company, signed by its Chief Executive Officer or other appropriate senior corporate officer.
- (2) Bidders will also be required to submit similar No-bribery commitments from their subcontractors and consortium partners; the Bidder may cover the subcontractors and consortium partners in its own statement, provided the Bidder assumes full responsibility.
- (3)
 - (a) Payment to agents and other third parties shall be limited to appropriate compensation for legitimate services.
 - (b) Each Bidder will make full disclosure in the bid documentation of the beneficiaries and amounts of all payments made, or intended to be made, to agents or other third parties (including political parties or electoral candidates) relating to the bid and, if successful, the implementation of the contract.
 - (c) The successful Bidder will also make full disclosure [quarterly or semi-annually] of all payments to agents and other third parties during the execution of the contract.
 - (d) Within six months of the completion of the performance of the contract, the successful Bidder will formally certify that no bribes or other illicit commissions have been paid. The final accounting shall include brief details of the goods and services provided that are sufficient to establish the legitimacy of the payments made.
 - (e) Statements required according to subparagraphs (b) and (d) of this paragraph will have to be certified by the company's Chief Executive Officer, or other appropriate senior corporate officer.
- (4) Bids which do not conform to these requirements shall not be considered.
- (5) If the successful Bidder fails to comply with its No-bribery commitment, significant sanctions will apply. The sanctions may include all or any of the following:

- a) Cancellation of the contract;
 - b) Liability for damages to the public authority and/or the unsuccessful competitors in the bidding possibly in the form of a lump sum representing a pre-set percentage of the contract value (liquidated).
- (6) Bidders shall make available, as part of their bid, copies of their anti-Bribery Policy/Code of Conduct, if any, and of their-general or project - specific - Compliance Program.
- (7) The Government of the United Republic of Tanzania has made special arrangements for adequate oversight of the procurement process and the execution of the contract, and has invited civil society and other competent Government Departments to participate in the oversight. Those charged with the oversight responsibility will have full access to all documentation submitted by Bidders for this contract, and to which in turn all Bidders and other parties involved or affected by the project shall have full access (provided, however, that no proprietary information concerning a Bidder may be disclosed to another Bidder or to the public).

MEMORANDUM (Format 2)

Regulation 78 (2) of the Public Procurement Regulations GN No. 446 of 2013 as Amended in 2016

This company KUYELLA ENTERPRISES LIMITED has issued, for the purposes of this bid, a Compliance Program copy attached -which includes all reasonable steps necessary to assure that the No-bribery commitment given in this statement will be complied with by its managers and employees, as well as by all third parties working with this company on the public sector projects or contract including agents, consultants, consortium partners, subcontractors and suppliers)"

Authorized Signature: 

Name and Title of Signatory: Felix Kuyella - KUYELLA ENTERPRISES LTD

Name of Bidder: KUYELLA ENTERPRISES LTD

Address: Box 2880 - D5m

